

California High-Speed Rail Program



RFP No.: HSR 13-57

Request for Proposal for Design-Build Services for Construction Package 2-3

Book III, Part B – Directive Drawings

California High-Speed Rail Authority



RFP No.: HSR 13-57

**Request for Proposals for Design-Build
Services for Construction Package 2-3**

**Book II, Part B.1
Directive Drawings**

General

CIVIL DIRECTIVE NOTES

A. GENERAL SITE NOTES

1. FIELD VERIFY ALL EXISTING SITE CONDITIONS PRIOR TO THE COMMENCEMENT OF WORK AND REPORT ANY DISCREPANCIES TO THE AUTHORITY'S REPRESENTATIVE.
2. ALL CONSTRUCTION ACTIVITIES AFFECTING THIRD PARTY FACILITIES SHALL BE COORDINATED WITH THE PROPER JURISDICTION AUTHORITY.
3. FOR ABBREVIATIONS, SEE GENERAL DIRECTIVE DRAWINGS.
4. FOR SYMBOLS, SEE GENERAL DIRECTIVE DRAWINGS.
5. "ORIGINAL GROUND" SHOWN ON CROSS SECTIONS REFERS TO THE APPROXIMATE EXISTING GROUND LINE AT THE DESIGNATED CENTERLINE, BASELINE, LAYOUT LINE OR SECTION LINE.
6. ALL WORK SHALL CONFORM TO ALL LOCAL, STATE AND FEDERAL CODES AND ORDINANCES IN EFFECT.
7. PROVIDE AND MAINTAIN PROPER BARRICADES, RAILINGS, GUARDS, FLAGGING, LIGHTING, OR OTHER DEVICES NECESSARY FOR THE PROTECTION OF LIFE AND PROPERTY.
8. VERIFY ALL CONTROLLING FIELD DIMENSIONS BEFORE ORDERING OR FABRICATING MATERIALS.

B. GRADING

1. DO NOT PERFORM ANY GRADING OPERATION SO AS TO CAUSE FALLING ROCKS, SOIL OR DEBRIS IN ANY FORM TO FALL, SLIDE OR FLOW ONTO ADJOINING PROPERTIES, STREETS OR NATURAL WATERCOURSES. SHOULD SUCH VIOLATION OCCUR THE CONTRACTOR MAY BE CITED AND THE CONTRACTOR SHALL IMMEDIATELY MAKE ALL REMEDIAL ACTIONS NECESSARY.
2. KEEP THE PROJECT AREA AND SURROUNDING AREA FREE FROM DUST NUISANCE.
3. PROVISIONS SHALL BE MADE TO PREVENT SURFACE WATERS FROM DAMAGING THE CUT FACE OF AN EXCAVATION OR THE SLOPED SURFACES OF A FILL. FURTHERMORE, PROVISIONS SHALL BE MADE TO PREVENT SEDIMENT-LADEN RUNOFF FROM LEAVING THE SITE.
4. THE LIMITS OF THE AREA TO BE GRADED SHALL BE FLAGGED BEFORE THE COMMENCEMENT OF THE GRADING WORK.
5. ALL GRADING OPERATIONS SHALL BE PERFORMED IN CONFORMANCE WITH THE APPLICABLE PROVISIONS OF THE WATER POLLUTION CONTROL AND WATER QUALITY STANDARDS CONTAINED IN THE LATEST CALTRANS STORM WATER QUALITY HANDBOOKS.

2/11/2014 4:59:51 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32160\DD-GE-001.dgn mincio

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY S. MILITELLO
DRAWN BY R. MINCIO
CHECKED BY H. NGUYEN
IN CHARGE J. CHIRCO
DATE 01/24/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
GENERAL DIRECTIVE

 GENERAL DIRECTIVE NOTES
 CIVIL

CONTRACT NO.
DRAWING NO. DD-GE-001
SCALE NO SCALE
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

TRACK DIRECTIVE NOTES

1. THE GENERAL BASIS FOR TRACK STANDARDS AND MATERIALS SHALL BE THE AREMA MANUAL.
2. TRACK AND TRACK COMPONENTS SHALL BE DESIGNED AND FABRICATED TO PERFORM UNDER THE PREVAILING AND EXTREME CLIMATIC AND ENVIRONMENTAL CONDITIONS OCCURRING WITHIN THE GEOGRAPHIC EXTENT OF THE SYSTEM.
3. THE PROFILE GRADE LINE IS CARRIED ON THE TOP OF LOW RAIL THROUGH HORIZONTAL CURVES AND SPIRALS FOR THE DESIGNATED TRACK.
4. THE LENGTHS OF TRACK IS BASED ON CENTER OF TRACK ALIGNMENT.
5. UNLESS SEPARATE TRACK PROFILES ARE GIVEN, TRACK PARALLEL TO THE DESIGNATED TRACK ARE AT THE SAME TOP OF RAIL ELEVATIONS PROJECTED ON EITHER PERPENDICULAR OR RADIAL LINES FROM THE DESIGNATED TRACK CENTERLINES.
6. BALLASTED TRACKS ARE GENERALLY PREFERRED FOR YARD TRACKS. DESIGNERS SHALL FOLLOW THE REQUIREMENTS ASSOCIATED WITH CONSTRUCTION OF BALLASTED TRACK IN THE CALIFORNIA HIGH SPEED TRAIN DESIGN MANUAL.

2/11/2014 5:04:06 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32160\DD-GE-002.dgn mincio

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY S. MILITELLO
DRAWN BY R. MINCIO
CHECKED BY H. NGUYEN
IN CHARGE J. CHIRCO
DATE 01/24/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
GENERAL DIRECTIVE

 GENERAL DIRECTIVE NOTES
 TRACK

CONTRACT NO.
DRAWING NO. DD-GE-002
SCALE NO SCALE
SHEET NO.

STRUCTURAL DIRECTIVE NOTES:

A. SPECIFICATIONS FOR DESIGN AND CONSTRUCTION

1. CONSTRUCTION SPECIFICATION SHALL BE THE DESIGN-BUILD STANDARD SPECIFICATION, CALIFORNIA HIGH SPEED TRAIN.
2. THE STRUCTURAL DESIGN OF STRUCTURES SUPPORTING HIGH SPEED TRAINS SHALL BE BASED ON THE REQUIREMENTS OF THE CALIFORNIA HIGH SPEED RAIL AUTHORITY.
3. DESIGN CRITERIA FOR HIGHWAY BRIDGES SHALL BE THE CALIFORNIA BRIDGE DESIGN SPECIFICATION. FOR HIGHWAY BRIDGES PASSING OVER THE HIGH SPEED TRAIN THE BRIDGE DESIGN SPECIFICATION SHALL BE SUPPLEMENTED BY THE CALIFORNIA HIGH SPEED TRAIN REQUIREMENTS FOR SEISMIC DESIGN.
4. DESIGN CRITERIA FOR RAILROAD STRUCTURES NOT SUPPORTING HIGH SPEED TRAINS SHALL BE THE AMERICAN RAILWAY ENGINEERING AND MAINTENANCE-OF-WAY ASSOCIATION (AREMA) MANUAL FOR RAILWAY ENGINEERING (APRIL 2008). FOR RAILROAD BRIDGES PASSING OVER THE HIGH SPEED TRAIN THE BRIDGE DESIGN SPECIFICATION SHALL BE SUPPLEMENTED BY THE CALIFORNIA HIGH SPEED TRAIN REQUIREMENTS FOR SEISMIC DESIGN.

B. DESIGN METHOD

1. DESIGN SHALL BE PERFORMED TO THE LOAD AND RESISTANCE FACTOR (LRFD) DESIGN METHOD.
2. THE DESIGN OF PRESTRESSING AND PARTIAL PRESTRESSING SHALL CONFORM TO THE REQUIREMENTS OF SUBSECTION 5.9 OF AASHTO LRFD WITH CALIFORNIA AMENDMENTS WITH THE FOLLOWING EXCEPTION: NET TENSION STRESSES ARE NOT ALLOWED IN THE PRECOMPRESSED TENSILE ZONE AFTER ALL LOSSES HAVE OCCURRED.

C. GENERAL

1. SEE GENERAL DIRECTIVE DRAWINGS FOR ACRONYMS AND ABBREVIATIONS.
2. ALL STRUCTURAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH THE SPECIFICATIONS AND ALL OTHER DRAWINGS RELATED TO THE WORK.
3. EMBEDDED ITEMS SUCH AS PIPES, INSERTS, SLEEVES AND CONDUITS, AND ANY RECESSES, NICHES OR OPENINGS REQUIRED FOR UTILITY, ARCHITECTURAL, MECHANICAL AND ELECTRICAL INSTALLATIONS ARE NOT SHOWN ON THE STRUCTURAL DRAWINGS. CONTRACTOR SHALL REFER TO THE UTILITY, ARCHITECTURAL, MECHANICAL AND ELECTRICAL DRAWINGS FOR THE LOCATIONS AND DETAILS OF THESE ITEMS. CONTRACTOR SHALL REVIEW AND APPROVE ALL PENETRATIONS PRIOR TO CONSTRUCTION. PENETRATIONS WHICH LOCAL THICKENING OF CONCRETE OR STEEL MEMBERS AND /OR SUPPLEMENTAL REINFORCING SHALL BE SHOWN ON THE STRUCTURAL DRAWINGS.
4. THE VERTICAL CONTROL OF ALL TRACK STRUCTURES IS BASED ON THE TOP OF LOW RAIL ELEVATION IN SUPERELEVATED STRUCTURES.

5. CONTRACTORS ATTENTION IS DIRECTED TO THE AREAS OF SAG VERTICAL CURVES. IN SUCH AREAS CAUTION SHOULD BE EXERCISED THAT THE DIMENSION TO THE INVERT OF CONCRETE OF GUIDEWAY IS NEVER LESS THAN THAT SHOWN FOR INVERT DETAILS.

6. ALL CONSTRUCTION JOINTS IN EARTH RETAINING STRUCTURES AND IN STRUCTURES BELOW THE FINISH GRADE SHALL CONTAIN CONTINUOUS WATERSTOPS, AND SHALL HAVE REINFORCEMENT CONTINUOUS ACROSS ALL JOINTS. HYDROSWELLING STRIPS SHALL BE INSTALLED ON ALL JOINT SURFACES WHICH WILL BE EXPOSED TO EARTH AND PERMANENTLY UNDER THE GROUNDWATER ELEVATION.

7. ALL WATERSTOPS SHALL BE INSTALLED SECURELY IN ACCORDANCE WITH THE SPECIFICATIONS. THE WATERSTOPS SHALL BE PLACED CONTINUOUSLY THROUGHOUT THE LENGTH OF THE CONSTRUCTION JOINT. LAPPING OF WATERSTOPS SHALL NOT BE PERMITTED. SPLICING SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS.

8. UNLESS INDICATED OTHERWISE, CONCRETE SURFACES LEADING TO DRAINS SHALL BE SLOPED A MINIMUM OF 1/8 INCH PER FOOT TOWARD THE DRAIN AND THE ADJACENT SURFACES WARPED AS REQUIRED TO SATISFY AN ADEQUATE DRAINAGE FLOW.

D. MATERIAL PROPERTIES

1. CONCRETE 28 DAY COMPRESSIVE STRENGTH (MINIMUM)
 - a) DRILLED SHAFTS: $f'c=4,000$ PSI
 - b) PRECAST-PRESTRESSED PILES: $f'c=6,000$ PSI
 - c) FORMED CAST-IN-PLACE STRUCTURAL CONCRETE:
 - $f'c$ (UNDER GROUND)=4000 PSI
 - $f'c$ (ABOVE GROUND)=5000 PSI
 - d) PRECAST GIRDERS OR SEGMENTS OF GIRDERS: $f'c=6,000$ PSI
 - e) UNLESS NOTED OTHERWISE ON THE DRAWINGS, OR SPECIFIED, MINIMUM STRUCTURAL CONCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 4,000 PSI.
 - f) ALL EXPOSED CONCRETE EDGES AND CORNERS SHALL BE CHAMFERED WITH A 3/4 INCH, 45 DEGREE CHAMFER UNLESS NOTED OTHERWISE.
2. REINFORCING STEEL SHALL CONFORM TO THE SPECIFICATIONS OF ASTM A 706 GRADE 60.
3. PRESTRESSING STEEL
 - a) STRAND: ASTM A416/AASHTO M203, GRADE 270, LOW RELAXATION
 FRICTION COEFFICIENT: 0.25
 WOBBLE COEFFICIENT: 0.0002 PER FT
 ANCHOR SET: 0.375"
 APPARENT MODULUS: 28,500 KSI
 MINIMUM JACKING STRESS: 216 KSI (80% ULTIMATE)
 MAXIMUM ANCHORING STRESS: 189 KSI (70% ULTIMATE)
 MAXIMUM STRESS AFTER ANCHOR SET: 202 KSI (75% ULTIMATE)
 STRAND DIAMETER: 0.6" (AREA=0.216 SQ IN)

b) POST TENSIONING BARS:
 ASTM A722/AASHTO M275, GRADE 150, TYPE II
 ANCHOR SET: 0.0625"
 APPARENT MODULUS: 30,000 KSI
 MAXIMUM JACKING STRESS: 113 KSI
 MAXIMUM ANCHORING STRESS: 105 KSI
 MAXIMUM STRESS AFTER LOSSES: 96 KSI

4. STRUCTURAL STEEL SHAPES SHALL CONFORM TO ASTM A6 WITH A YIELD STRENGTH OF $FY = 50$ KSI UNLESS NOTED OTHERWISE. THE FOLLOWING MATERIAL PROPERTIES SHALL APPLY:

- a) WIDE FLANGE SHAPES: ASTM A992
- b) M-SHAPES, S-SHAPES, HP SHAPES: ASTM A572
- c) ANGLES, CHANNELS: ASTM A572
- d) RECTANGULAR AND SQUARE HSS: ASTM A500 GR B (46 KSI)
- e) ROUND HSS: ASTM A500 GR B (42 KSI)
- f) STEEL PIPE: ASTM A53 GR B (35 KSI)
- g) PLATES, BARS: ASTM A36 (36 KSI)
- h) BOLTS: ASTM A325
- i) NUTS: ASTM A563
- j) WASHERS: ASTM F436

5. STEEL FABRICATIONS

- a) WELDING OF BUILT UP MEMBERS AND STEEL FABRICATIONS SHALL COMPLY WITH AASHTO/AWS D 1.5
- b) WELDING OF HSS SECTIONS AND PIPES SHALL COMPLY WITH AWS D 1.1
- c) MISCELLANEOUS STEEL ITEMS SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION UNLESS COMPLETELY EMBEDDED IN CONCRETE AND UNLESS NOTED OTHERWISE.

6. FASTENERS

- a) ALL HIGH STRENGTH BOLTS NUTS AND WASHERS SHALL BE ZINC COATED
- b) ALL BOLTED CONNECTIONS SHALL COMPLY WITH RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS (RCSC) "SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS".
- c) ALL BOLTS ARE ASTM A325 HIGH STRENGTH SLIP CRITICAL WITH THREADS EXCLUDED FROM THE SHEAR PLANE

E. CONCRETE COVER

1. UNLESS OTHERWISE NOTED, MINIMUM CONCRETE COVER SHALL CONFORM TO AASHTO LRFD WITH CALTRANS AMENDMENTS TABLE 5.12.3-1 WITH THE FOLLOWING EXCEPTIONS:
 - a) UNCASSED DRILLED SHAFTS: 6 INCHES
 - b) CASSED DRILLED SHAFTS WITH TEMPORARY CASING: 4 INCHES

F. SEISMIC LOADING AND DESIGN

1. THERE ARE TWO LEVELS OF DESIGN EARTHQUAKES:
 - a) MAXIMUM CONSIDERED EARTHQUAKE (MCE): GROUND MOTIONS CORRESPONDING TO GREATER OF (1) A PROBABILISTIC SPECTRUM BASED UPON A 10% PROBABILITY OF EXCEEDANCE IN 100 YEARS (i.e., A RETURN PERIOD OF 950 YEARS) AND (2) A DETERMINISTIC SPECTRUM BASED UPON THE LARGEST MEDIAN RESPONSE RESULTING FROM THE MAXIMUM RUPTURE (CORRESPONDING TO M_{max}) OF ANY FAULT IN THE VICINITY OF THE STRUCTURE.
 - b) OPERATING BASIS EARTHQUAKE (OBE): GROUND MOTIONS CORRESPONDING TO A PROBABILISTIC SPECTRUM BASED UPON AN 86% PROBABILITY OF EXCEEDANCE IN 100 YEARS (i.e., A RETURN PERIOD OF 50 YEARS).

9/30/2014 11:27:03 AM CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\laverdev\dms32160\DD-GE-003.dgn

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY P. LIN
DRAWN BY R. MINCIO
CHECKED BY T. JACKSON
IN CHARGE J. CHIRCO
DATE 08/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
GENERAL DIRECTIVE

GENERAL DIRECTIVE NOTES
 STRUCTURAL

CONTRACT NO.
DRAWING NO. DD-GE-003
SCALE NO SCALE
SHEET NO.

9/30/2014 11:20:29 AM CAHSR_PDF_half_black.plt c:\projects\wise\p\project\wise\nt\laverdev\dms32160\DD-GE-100.dgn

A

@ ARCHITECTURAL AND ENGINEERING
 A&E ARCHITECTURAL AND ENGINEERING
 A/G AT-GRADE
 AADT AVERAGE ANNUAL DAILY TRAFFIC
 AB AGGREGATE BASE,
 ANCHOR BOLT
 ABBC ASBESTOS BONDED BITUMINOUS COATED
 ABM AIR-BLOWN MORTAR
 ABN ABANDON
 ABUT ABUTMENT
 ABV ABOVE
 AC ALTERNATING CURRENT,
 ASPHALT CONCRETE
 ACB ASPHALT CONCRETE BASE
 ACMB AC DISTRIBUTION PANEL MAIN BREAKER
 ACOUS ACOUSTICAL
 ACP ASBESTOS CEMENT PIPE
 ACS ACCESS CONTROL ROOM
 ACSR ALUMINUM CONDUCTOR STEEL REINFORCED
 AD AREA DRAIN,
 ACCESS DETERRING
 ADJ ADJACENT,
 ADJUST,
 ADJUSTABLE
 ADL ADDED DEAD LOAD
 ADP AC DISTRIBUTION PANEL
 ADT AVERAGE DAILY TRAFFIC
 AEC AERIAL EARTH (GROUND) CONDUCTOR
 AED AUTOMATED EXTERNAL DEFIBRILLATOR
 AFC AUTOMATIC FARE COLLECTION
 AFES ALTERNATIVE FLARED END SECTION
 AGW AERIAL GROUND WIRE
 AHD AHEAD
 AL ALUMINUM
 ALIGN ALIGNMENT
 ALT ALTERNATE
 AM TIME FROM MIDNIGHT TO NOON
 ANC ANCHOR
 ANI AUTOMATIC NUMBER IDENTIFICATION
 ANN ANNUNCIATOR
 ANS AMBIENT NOISE SENSOR
 AP ALTERNATIVE PIPE
 APC ALTERNATIVE PIPE CULVERT
 APE AREA OF POTENTIAL EFFECTS
 APEFZ ALQUIST-PRIOLO EARTHQUAKE FAULT ZONE
 API APPLICATION PROGRAMMING INTERFACE
 APPROX APPROXIMATE
 APU ALTERNATIVE PIPE UNDERDRAIN
 AR ACCESS RESTRICTION
 ARCH ARCHITECTURAL
 ARS ACCELERATION RESPONSE SPECTRUM
 AS AGGREGATE SUBBASE
 ASPH ASPHALT
 ASRP ALUMINUM SPIRAL RIB PIPE
 ASSY ASSEMBLY
 AT AUTOTRANSFORMER,
 AUTOMATIC TENSION
 ATC AUTOMATIC TRAIN CONTROL
 ATEL ADMINISTRATIVE TELEPHONE
 ATM ALONG TRACK MOVEMENT
 ATO AUTOMATIC TRAIN OPERATION
 ATP AUTOMATIC TRAIN PROTECTION
 ATPB ASPHALT TREATED PERMEABLE BASE
 ATPM ASPHALT TREATED PERMEABLE MATERIAL
 ATR ABOVE TOP OF RAIL
 ATS AUTOMATIC TRAIN SUPERVISION,
 AUTOTENSIONED SYSTEM
 AUX AUXILIARY
 AVE AVENUE
 AVG AVERAGE
 AVL AUTOMATIC VEHICLE LOCATION
 AWG AMERICAN WIRE GAUGE

B

B/SPAN BODY SPAN
 B/W BLACK & WHITE
 BAGR BRIDGE APPROACH GUARD RAILING
 BAR BARRIER
 BAT BATTERY
 BB BEGINNING OF BRIDGE
 B-B BACK-TO-BACK
 BC BOLT CIRCLE

B CONTINUED

BCR BEGIN CURB RETURN
 BD BOARD
 BDA BI-DIRECTIONAL AMPLIFIER
 BDD BRIDGE DESIGN DETAILS (CALTRANS)
 BDP BRIDGE DESIGN PRACTICE (CALTRANS)
 BDS BRIDGE DESIGN SPECIFICATIONS (CALTRANS)
 BEC BURIED EARTH (GROUND) CONDUCTOR
 BEG BEGIN
 BFA BY PASS FEEDER ANCHOR
 BIL BASIC IMPULSE INSULATION LEVEL
 BITUM BITUMINOUS
 BK BACK
 BKF BACKFILL
 BKR BREAKER
 BL BASE LINE
 BLDG BUILDING
 BLKG BLOCKING
 BLM BRIDGE-LOG MILE
 BLST BALLAST
 BLVD BOULEVARD
 BM BENCH MARK
 BN BACKBONE NETWORK
 BND BOUND
 BOC BOTTOM OF CURB
 BOCC BACK-UP OPERATIONAL CONTROL CENTER
 BOS BOTTOM OF SLOPE
 BOT BOTTOM
 BOW BOTTOM OF WALL
 BR BRIDGE
 BRG BEARING
 BRKT BRACKET
 BRS BROADBAND RADIO SYSTEM
 BRT BUS RAPID TRANSIT
 BS BODY SPAN WIRE
 BSC BASE STATION CONTROLLER
 BT BUS TIE
 BTM BOTTOM
 BTS BASE TRANSCEIVER STATION
 BTWN BETWEEN
 BW BARBED WIRE,
 BALANCE WEIGHT
 BWA BALANCE WEIGHT ANCHOR
 BWLAN BROADBAND WIRELESS LOCAL AREA NETWORK
 BZ BRONZE

C

C CLOSE,
 CONTACT,
 CONTROL
 CA CERTIFICATION ACCEPTANCE
 CAA CABLE ANCHOR ASSEMBLY
 CAB CABINET
 CADD COMPUTER-AIDED DESIGN AND DRAFTING
 CAH CONTROLLED ACCESS HIGHWAY
 CAI CUSTOMER ASSISTANCE INTERCOM
 CALP CORRUGATED ALUMINUM PIPE
 CANT CANTILEVER
 CAP CAPACITY,
 CAPACITOR,
 CORRUGATED ALUMINUM PIPE
 CORRUGATED ALUMINUM PIPE ARCH
 CONSTRUCTION AREA SIGN
 CAPA CATEGORY,
 CATEGORY SPECIFICATION FOR
 TWISTED PAIR CABLING,
 CATENARY
 CATF CANTENARY FOUNDATION
 CATP CATENARY POLE
 CB CATCH BASIN,
 CIRCUIT BREAKER
 CONCRETE BARRIER
 COMMUNICATIONS BASED TRAIN CONTROL
 CONCRETE BLOCK WALL
 CENTER LINE TO CENTER LINE
 CONTRACT CHANGE ORDER
 CCS CALIFORNIA COORDINATE SYSTEM
 CCTV CLOSED CIRCUIT TELEVISION
 CCVT COUPLING CAPACITOR VOLTAGE TRANSFORMER
 CEG CERTIFIED ENGINEERING GEOLOGIST

C CONTINUED

CEM CEMENT
 CER COMMUNICATIONS EQUIPMENT ROOM
 C&G CURB & GUTTER
 CG CENTER OF GRAVITY
 CGS CALIFORNIA GEOLOGICAL SURVEY
 CHNL CHANNEL
 CI CAST IRON
 CIC COMMUNICATIONS INTERFACE CABINET
 CIDH CAST-IN-DRILLED-HOLE
 CIF COMMON INTERMEDIATE FORMAT
 CIP CAST IRON PIPE
 C-I-P CAST-IN-PLACE
 CIPCP CAST-IN-PLACE CONCRETE PIPE
 CIS CUSTOMER INFORMATION SIGN
 CISS CAST-IN-STEEL-SHELL
 CJ CONSTRUCTION JOINT
 CJP COMPLETE JOINT PENETRATION
 CKT CIRCUIT
 CL CLASS
 CL2 CLASS 2
 CL-6 CHAIN LINK FENCE (6 FT)
 CLG CEILING
 CLK CHAIN LINK
 CLKG CAULKING
 CLO CLOSET
 CLR CLEAR,
 CLEARANCE
 CM CONTROL MODULE,
 CORRUGATED METAL
 CMP CORRUGATED METAL PIPE
 CMU CONCRETE MASONRY UNIT
 CNTR COUNTER
 CO CLEANOUT,
 COUNTY
 COL COLUMN
 COMM COMMUNICATIONS
 CONC CONCRETE
 COND CONDUIT
 CONN CONNECTOR,
 CONNECTION
 CONST CONSTRUCT,
 CONSTRUCTION
 CONT CONTINUOUS,
 CONTINUATION
 CONTR CONTRACTOR
 COORD COORDINATE
 CORR CORRIDOR
 CP CONTROL POINT
 CPT CONE PENETRATION TEST,
 CONTROL POWER TRANSFORMER
 CPU CENTRAL PROCESSING UNIT
 CR CREEK,
 CONDUIT RISER
 CRC COMBINED RELAY AND CONTROL PANEL
 CRCP CONTINUOUS REINFORCED CONCRETE PAVEMENT
 CRSP CONCRETED ROCK SLOPE PROTECTION
 CRZ CLEAR RECOVERY ZONE
 CS CONTROL SWITCH
 CSA CONSTRUCTION STAGING AREA
 CSP CORRUGATED STEEL PIPE
 CSPA CORRUGATED STEEL PIPE ARCH
 CT CERAMIC TILE,
 COURT,
 CURRENT TRANSFORMER/TRANSUCER
 CTB CEMENT TREATED BASE
 CTPB CEMENT TREATED PERMEABLE BASE
 CTPM CEMENT TREATED PERMEABLE MATERIAL
 CTR CENTER
 CTSK COUNTERSUNK
 CTVT COMBINED CURRENT TRANSFORMER AND
 VOLTAGE TRANSFORMER
 CTW COUNTERWEIGHT TAIL WIRE
 CU COPPER
 CULV CULVERT
 CV CURVE
 CVR COVER
 CW CONTACT WIRE
 CWA CONTACT WIRE ANCHOR
 CWH CONTACT WIRE HEIGHT
 CWR CONTINUOUSLY WELDED RAIL
 CWT COUNTER WEIGHT

D

D DEPTH
 DB DESIGN-BUILD
 DBE DESIGN BASIS EARTHQUAKE
 DBL DOUBLE
 DC DIRECT CURRENT
 DCMB Dc DISTRIBUTION PANEL MAIN BREAKER
 DCP Dc DISTRIBUTION PANEL
 DD DOWNDRAIN,
 DEVICE DRIVER
 DE DEAD END
 DEL DELINEATOR
 DEMO DEMOLISH
 DEPT DEPARTMENT
 DET DETOUR
 DF DIRECT FIXATION,
 DRINKING FOUNTAIN
 DGA DOWN GUY ANCHOR
 DHV DESIGN HOURLY VOLUME
 DI DRAINAGE INLET
 DIAG DIAGONAL
 DIAPH DIAPHRAGM
 DIFF DIFFERENTIAL
 DIM DIMENSION
 DIN DROP INLET
 DIR DIRECTION
 DISC DISCONNECT
 DISP DISPENSER
 DIST DISTANCE
 DISTR DISTRIBUTION
 DMBB DOUBLE METAL BEAM BARRIER
 DN DOWN
 DNS DOMAIN NAME SYSTEM
 DO DOOR OPENING
 DPDT DOUBLE-POLE DOUBLE-THROW
 DR DRIVE
 DS DOWNSPOUT,
 DISCONNECT SWITCH
 DSC DIFFERING SITE CONDITIONS
 DSCW DIRECT SUSPENSION CONTACT WIRE
 DSG DISCONNECT SWITCH GROUP
 DSHA DETERMINISTIC SEISMIC HAZARD ANALYSIS
 DST DISTRICT
 DTBB DOUBLE THRIE BEAM BARRIER
 DTM DIGITAL TERRAIN MODEL
 DVR DIGITAL VIDEO RECORDERS
 DWG DRAWING
 DWY DRIVEWAY
 DXO DOUBLE CROSSOVER

E

E EAST
 EA EACH
 EB EASTBOUND,
 END OF BRIDGE
 EC END HORIZONTAL CURVE,
 ELECTRICAL CONDUCTOR
 END CURB RETURN
 ECR EACH END
 EE EACH FACE
 EF EMERGENCY GROUND SWITCH
 EGS EXTRA HIGH STRENGTH
 EHS EMERGENCY INTERCOM
 EI EXPANSION JOINT
 E-LAN ETHERNET LAN
 ELAST ELASTOMERIC
 ELEC ELECTRICAL,
 ELECTRIC
 ELECT ELECTROLIER
 ELEV ELEVATION
 ELOCK ELECTRONIC LOCK
 EMB EMBANKMENT
 EMC ELECTROMAGNETIC COMPATIBILITY
 EMER EMERGENCY
 EMF ELECTROMAGNETIC FIELD
 EMI ELECTRO MAGNETIC INTERFERENCE
 EMS ELEMENT MANAGEMENT SYSTEM
 EMU ELECTRIC MULTIPLE UNIT
 ENCL ENCLOSURE
 ENGR ENGINEER,
 ENGINEERING
 EOB END OF BRIDGE

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
R. MINCIO
 DRAWN BY
V. LAVERDE
 CHECKED BY
S. MILITELLO
 IN CHARGE
G. LUSHEROVICH
 DATE
08/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
DIRECTIVE DRAWING
 ACRONYMS AND ABBREVIATIONS 1

CONTRACT NO.
 DRAWING NO.
 DD-GE-100
 SCALE
 NO SCALE
 SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

mincio 2/11/2014 5:13:14 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\nt\mincio\dms32160\DD-GE-101.dgn

E CONTINUED

EOD EDGE OF DECK
 EOS ELECTRICAL OPERATED SWITCH
 EOW END OF WALL
 EP EDGE OF PAVEMENT
 EPBM EARTH PRESSURE BALANCING MACHINE
 EPR ETHYLENE PROPYLENE RUBBER
 EQ EQUAL,
 EQUILATERAL
 EQN EQUATION
 EQUIP EQUIPMENT
 ES EDGE OF SHOULDER,
 EXTRA STRENGTH,
 ELECTRICAL SECTION
 ENVIRONMENTALLY SENSITIVE AREA
 ESC ESCALATOR
 ESEW EMERGENCY SHOWER / EYE WASH
 ESMT EASEMENT
 ETCS EUROPEAN TRAIN CONTROL SYSTEM
 ETEL EMERGENCY TELEPHONE
 ETS EMERGENCY TRIP SYSTEM
 ETW EDGE OF TRAVELED WAY
 EW EACH WAY,
 ENDWALL
 EXC EXCAVATION
 EXIST EXISTING
 EXP EXPANSION
 EXPO EXPOSED
 EXWY EXPRESSWAY
 EXT EXTERIOR

F

F/F FACE TO FACE
 F&C FRAME AND COVER
 F&G FRAME AND GRATE
 FA FIRE ALARM
 FACP FIRE ALARM CONTROL PANEL
 FAS FIRE ALARM SYSTEM
 FB FLAT BAR,
 FLOOR BEAM,
 FEEDER BREAKER
 FURNISHED BY OTHERS
 FBO FARE COLLECTION
 FC FLOOR DRAIN
 FDC FIRE DEPARTMENT CONNECTION
 FDN FOUNDATION
 FDP FIBER DISTRIBUTION PANEL
 FDR FEEDER
 FDU FIBER DISTRIBUTION UNIT
 FE FIRE EXTINGUISHER
 FES FLARED END SECTION
 FF FILTER FABRIC
 FFJ FULL FEEDING JUMPER
 FFL FINISHED FLOOR LEVEL
 FG FINISHED GRADE
 FH FIRE HYDRANT
 FHC FIRE HOSE CABINET
 FID FIRE INITIATING DEVICE
 FIG FIGURE
 FIN FINISH
 FIRM FLOOD INSURANCE RATE MAPS
 FJ FEEDER JUMPER
 FL FLOW LINE
 FLB FLOOR BEAM
 FLH FLAT HEAD
 FLR FLOOR
 FNA FIRE NOTIFICATION APPLIANCE
 FO FIBER OPTIC
 FOC FIBER OPTIC CABLE,
 FACE OF CURB
 FOCN FIBER OPTIC CABLING NETWORK
 FOF FACE OF FINISH
 FOP FACE OF POLE
 FOS FACE OF STUDS,
 FACTOR OF SAFETY
 FP FULL PENETRATION
 FPLM FULL SPAN PRECAST LAUNCHING
 FPRF FIREPROOF
 FPS FRAMES PER SECOND
 FR FRAME
 FREQ FREQUENCY
 FS FINISHED SURFACE

F CONTINUED

FTEL FIRE TELEPHONE
 FOOTING
 FTP FILE TRANSFER PROTOCOL
 FTW FIXED END TAIL WIRE
 FUT FUTURE
 FW FEEDER WIRE
 FWY FREEWAY

G

G1 ENTRANCE GRADE
 G2 EXIT GRADE
 G/L GROUND LINE
 GALV GALVANIZED
 GCL GRADING CONTROL LINE
 GD GRADE
 GHS GALVANIZED HIGH STRENGTH
 GIGE GIGABIT ETHERNET
 GIS GAS INSULATED SWITCH,
 GEOGRAPHIC INFORMATION SYSTEM
 GLASS
 GMA GROUND MOTION ANALYSIS
 GND GROUND
 GO-95 PUC GENERAL ORDER 95
 GP GRADING PLANE
 GPS GLOBAL POSITIONING SYSTEM
 GR GUARDRAIL,
 GROUND ROD
 GRP GLASS REINFORCED PLASTIC ROD
 GRS GALVANIZED RIGID STEEL
 GRX GRADE CROSSING
 GSHA GEOLOGIC AND SEISMIC HAZARDS
 ANALYSIS
 GSP GALVANIZED STEEL PIPE
 GT GENERAL INFORMATION
 GTGM GEOTECHNICAL TECHNICAL GUIDANCE
 MANUAL (FHWA)
 GTR GUTTER
 GW GUY WIRE
 GYP GYPSUM
 GYPBD GYPSUM BOARD

H

H/SPAN HEADSPAN
 HAZ HAZARDOUS
 HB HARDNESS BRINELL,
 HOSE BIBB
 HC HANDICAP
 HD HARD DRAWN,
 HORIZONTAL DRAIN
 HDG HOT DIP GALVANIZED
 HDPE HIGH DENSITY POLYETHYLENE
 HDWE HARDWARE
 HDWL HEADWALL
 HEX HEXAGONAL
 HH HANDHOLE,
 HEAD HARDENED
 HI HIGH
 HI-RAIL HIGHWAY TO RAILROAD VEHICLE
 HM HOLLOW METAL
 HMA HOT MIXED ASPHALT
 HMI HUMAN MACHINE INTERFACE
 HO HAND OPERATED
 HOR HORIZONTAL
 HOV HIGH-OCCUPANCY VEHICLE
 HP HIGH POINT,
 HINGE POINT
 HP&R HIGHWAY PLANTING AND RESTORATION
 HPS HIGH PERFORMANCE STEEL
 HR HANDRAIL
 HRL HIGH RAIL LEVEL
 HS HIGH STRENGTH
 HSR HIGH-SPEED RAIL
 HST HIGH-SPEED TRAIN
 HT HIGH TEMPERATURE
 HTR HEATER
 HV HIGH VOLTAGE

H CONTINUED

HVAC HEATING VENTILATION AND AIR CONDITIONING
 HW HIGH WATER
 HWM HIGH WATER MARK
 HWY HIGHWAY

I

I/O INPUT/OUTPUT
 IB IMPEDANCE BOND
 IBC INTERNATIONAL BUILDING CODE
 IDS INTRUSTION DETECTION CODE
 IIMP INTEGRATED INFORMATION MANAGEMENT PLATFORM
 IJ INSULATED JOINT
 IJP INSULATED JOINT PLUG
 INSR INSULATOR
 INST INSTANTANEOUS
 INSUL INSULATION
 INT INTERIOR
 Inter-LATA INTER-LOCAL ACCESS AND TRANSPORT
 AREA
 INV INVERT
 IR IN-RUNNING (RIDING CONTACT WIRE)
 IRR IRRIGATION
 I/S IN-SPAN
 I/SJ IN-SPAN JUMPER

J

J JUMPER
 JAN JANITOR
 JB JUNCTION BOX
 JCT JUNCTION
 JP JOINT POLE
 JT(S) JOINT(S)

L

LA LANDSCAPE ARCHITECT,
 LIGHTNING ARRESTER
 LAM LAMINATE
 LAN LOCAL AREA NETWORK
 LAT LATITUDE
 LAV LAVATORY
 LC LANDSCAPE CONTRACTOR
 LCB LEAN CONCRETE BASE
 LCX LOWER-LEVEL DESIGN BASIS EARTHQUAKE
 LD BE LEAKY COAXIAL RADIO CABLE
 LED LIGHT EMITTING DIODE
 LF LINEAR FEET
 LG LONG
 LGT LIGHT,
 LIGHTING
 LH LEFT-HAND
 LKR LOCKER
 LL LIGHT LOADING
 LLT LAST LONG TIE
 LN LANE
 LO LOCKOUT
 LOC LOCATION
 LOL LAYOUT LINE
 LONG LONGITUDE,
 LONGITUDINAL
 LOS LEVEL OF SERVICE
 LOTB LOGS OF TEST BORINGS
 LP LOW POINT,
 LOW PROFILE
 LPL LIGHT POLE
 LR LOW RAIL
 LRFD LOAD AND RESISTANCE FACTOR DESIGN
 LRT LIGHT RAIL TRANSIT
 LRV LIGHT RAIL VEHICLE
 LS LANDSCAPING,
 LUMP SUM
 LT LEFT
 LV LOW VOLTAGE
 LVL LEVEL
 LVT LOW VIBRATION TRACK
 LWP LOWER WORKING POINT

M

M MEDIUM LOADING
 MAINT MAINTENANCE
 MAT MATERIAL
 MAX MAXIMUM
 MB METAL BEAM
 MBB METAL BEAM BARRIER
 MBGR METAL BEAM GUARD RAILING
 MCC MAINTENANCE CONTROL CENTER
 MCE MAXIMUM CONSIDERED EARTHQUAKE
 MCR MASTER CONTROL ROOM
 MDS MOBILE DATA SYSTEM
 MECH MECHANICAL
 MED MEDIAN
 MEM MEMBRANE
 MESSGR MESSENGER WIRE
 MET METAL
 MFR MANUFACTURER
 MH MANHOLE
 MHHW MEAN HIGHEST HIGH WATER
 MI MILD IRON
 MIN MINIMUM
 MISC MISCELLANEOUS
 MKR MARKER
 ML MAIN LINE
 MLLW MEAN LOWER LOW WATER
 MMIS MAINTENANCE MANAGEMENT INFORMATION SYSTEM
 MO MASONRY OPENING
 MOC MOTOR OPERATED CONTRACTOR
 MOD MODIFIED,
 MODIFY
 MODC MOTOR OPERATED DISCONNECT SWITCH
 MOI MAINTENANCE OF INFRASTRUCTURE
 MON MONUMENT
 MOP MOTOR OPERATED
 MOS MANUALLY OPERATED SWITCH
 MOV METAL-OXIDE VARISTOR
 MOW MAINTENANCE OF WAY
 MP MILEPOST
 MPA MIDPOINT ANCHOR
 MPLS MULTI-PROTOCOL LABEL SWITCHING
 MR MOVEMENT RATING
 MSE MECHANICALLY STABILIZED EMBANKMENT
 MSF MAINTENANCE AND STORAGE FACILITY
 MSL MEAN SEA LEVEL
 MTD MEMO TO DESIGNERS (CALTRANS),
 MOUNTED
 MUL MULLION
 MVC MINIMUM VERTICLE CLEARANCE
 MW MESSENGER WIRE

N

N NORTH
 N/A NOT APPLICABLE
 NAVD NORTH AMERICAN VERTICAL DATUM
 NB NORTHBOUND
 NBR NONBRIDGING
 NCL NO COLLAPSE PERFORMANCE LEVEL
 NDP NONLINEAR DYNAMIC PROCEDURE
 NEC NATIONAL ELECTRICAL CODE
 NEG NEGATIVE
 NEUT NEUTRAL
 NF NEGATIVE FEEDER,
 NEAR FACE
 NGVD NATIONAL GEODETIC VERTICAL DATUM
 NI NETWORK INTERFACE
 NIC NOT IN CONTRACT
 NMS NETWORK MANAGEMENT SYSTEM
 NO. NUMBER
 NO NORMALLY OPEN
 NOM NOMINAL
 NP NETWORK PORT
 NPRM NOTICE OF PROPOSED RULE MAKING
 NPS NOMINAL PIPE SIZE
 NR NOT REGISTERED
 NS NOT SUPPORTED
 NT NETWORK
 NTP NETWORK TIME PROTOCOL,
 NOTICE TO PROCEED
 NTS NETWORK TIME SERVER,
 NOT TO SCALE

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
R. MINCIO
 DRAWN BY
V. HUANTE
 CHECKED BY
S. MILITELLO
 IN CHARGE
J. CHIRCO
 DATE
01/24/2014



**CALIFORNIA HIGH-SPEED TRAIN PROJECT
 DIRECTIVE DRAWING**

ACRONYMS AND ABBREVIATIONS 2

CONTRACT NO.
 DRAWING NO.
DD-GE-101
 SCALE
NO SCALE
 SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

O

P CONTINUED

S

S CONTINUED

O&M OPERATIONS AND MAINTENANCE
OA OVERALL
OBLR OBLITERATE
OC ON CENTER,
OVERCROSSING
OCC OPERATIONS CONTROL CENTER
OCS OVERHEAD CONTACT SYSTEM
OF OUTSIDE FACE
OFF OFFSET
OG ORIGINAL GROUND
OH OVERHEAD
O-O OUT TO OUT
OOR OUT-OF-RUNNING (NONRIDING CONTACT WIRE)
OP OVERPASS
OPL OPERABILITY PERFORMANCE LEVEL
OPNG OPENING
OPP OPPOSITE
ORS OPERATIONS RADIO SYSTEM
OSP OUTSIDE PLANT
OVERTEMP OVERTEMPERATURE

PTD/R PAPER TOWEL DISPENSER & RECEPTACLE
PTEL PASSENGER ASSISTANCE TELEPHONE
PTM PARKING TICKET MACHINE
PTT PUSH TO TALK
PTZ PAN-TILT-ZOOM
PUE PUBLIC UTILITY EASEMENT
PVC POLYVINYL CHLORIDE
PVMT PAVEMENT
PWR POWER

S SOUTH, SLOPE
SAE STRUCTURE APPROACH EMBANKMENT
SALV SALVAGE
SAPP STRUCTURAL ALUMINUM PLATE PIPE
SB SOUTHBOUND
SC SWITCH CABLE
SCADA SUPERVISORY CONTROL AND DATA ACQUISITION
SCAT SIMPLE CATENARY-AUTO TENSION
SCB SUBSTATION CONTROL BUILDING
SCC STATION CONTROL CENTER
SCD SEAT COVER DISPENSER
SCFT SIMPLE CATENARY-FIXED TENSION SCHEDULE
SCHD SCHEDULE
SCN SECURITY CLASSIFICATION NUMBERS
SCPE SEISMIC CAPACITY AND PERFORMANCE EVALUATION

SURF SURFACING
SUSP SUSPENDED
SWK SIDEWALK
SW SOUND WALL, SOFTWARE
SWA SINGLE WIRE ANCHOR
SWAT SINGLE WIRE AUTO TENSIONED
SWFT SINGLE WIRE-FIXED TERMINATION
SWGR SWITCHGEAR
SWT SWITCH
SWPPP STORM WATER POLLUTION PREVENTION PLAN
SWR SEWER
SWS SWITCHING STATION
SYM SYMMETRICAL

Q

QOS QUALITY OF SERVICE
QT QUARRY TILE
QTY QUANTITY

R

R RADIUS, RED
R/A ROCK ANCHOR
R/W, ROW RIGHT OF WAY
R&D REMOVE AND DISPOSE
R&S REMOVE AND SALVAGE
RA REMOTE ANNUNCIATOR
RAID REDUNDANT ARRAY OF INDEPENDENT DISKS
RB RESILIENT BASE
RBM RAILBOUND MANGANESE FROG
RC REGIONAL CONSULTANT, REINFORCED CONCRETE
RCA REINFORCED CONCRETE ARCH
RCB REINFORCED CONCRETE BOX
RCC REGIONAL CONTROL CENTER
RCE REGISTERED CIVIL ENGINEER
RCP REINFORCED CONCRETE PIPE
RCPA REINFORCED CONCRETE PIPE ARCH
RD ROAD, ROOF DRAIN
RDWY ROADWAY
RE RUNNING EDGE OF RAIL
REBAR CONCRETE REINFORCING BAR
RECT RECTANGULAR
REF REFERENCE
REFP REFERENCE POINT
REINF REINFORCED, REINFORCEMENT, REINFORCING

REL RELOCATE, RELOCATED
REM REMOTE
REPL REPLACEMENT
REQD REQUIRED
RESIL RESILIENT
RET RETAINING
REV REVISED, REVISION
RF RADIO FREQUENCY
RFI REQUEST FOR INFORMATION
RGS RIGID GALVANIZED STEEL
RH RIGHT-HAND
R-M ROAD-MIXED
RM RESTRICTED MANUAL, ROOM
RO ROUGH OPENING
RP RADIUS POINT
RR RAILROAD, RUNNING RAIL
RRR RESURFACING, RESTORATION, REHABILITATION (3R)
RRRR RESURFACING, RESTORATION, REHABILITATION, RECONSTRUCTION (4R)
RRX RAILROAD GRADE CROSSING
RSP ROCK SLOPE PROTECTION
RT RESILIENT TILE, RIGHT
RTE ROUTE
RTU REMOTE TERMINAL UNIT
RW RETAINING WALL
RWL RAIN WATER LEADER
RWY RAILWAY

SCSP SLOTTED CORRUGATED STEEL PIPE
SD STORM DRAIN
SDB SYSTEM DUCT BANK
SDC SEISMIC DESIGN CRITERIA
SDOF SINGLE DEGREE OF FREEDOM
SE SUPER ELEVATION
SECTLEG SECTIONALIZING
SECT SECTION
SEP SEPARATION
SERV SERVICE
SF SPRING FROG
SG SUBGRADE
SHA SEISMIC HAZARDS ANALYSIS
SHLD SHOULDER
SHS STATE HIGHWAY SYSTEM
SHT SHEET
SI SECTION INSULATOR, SITE INVESTIGATION
SIG SIGNAL
SIM SIMILAR
SLAN PASSENGER STATION LOCAL AREA NETWORK
SM SELECTED MATERIAL
SMF SOLID MANGANESE FROG, SINGLE MODE FIBER

SNF SWING NOSE FROG
SNTP SIMPLE NETWORK TIME PROTOCOL
SP SPARE
SPC SPECIAL
SPEC SPECIFICATION
SPKR SPEAKER
SPL SAFETY PERFORMANCE LEVEL
SPS SMALL PART STEELWORK
SPST SINGLE POLE SINGLE THROW
SPT STANDARD PENETRATION TEST
SQ SQUARE
SR SYSTEM REQUIREMENT, STATE ROUTE
SRRR SAFETY ROADSIDE REST AREA
SRSS SQUARE ROOT OF SUM OF SQUARES
S/SPAN STEADY SPAN
SS SLOPE STAKE, SUB STATION

SSCOM SEISMIC SAFETY COMMISSION
SSI SOIL STRUCTURE INTERACTION
SSK SERVICE SINK
SSPA STRUCTURAL STEEL PLATE ARCH
SSPP STRUCTURAL STEEL PLATE PIPE
SSPPA STRUCTURAL STEEL PLATE PIPE ARCH
SSRP STEEL SPIRAL RIB PIPE
SST STAINLESS STEEL
SSW STEADY SPAN WIRE
SSWR SANITARY SEWER
ST STREET
STA STATION, STATIONING
STBB SINGLE THRIE BEAM BARRIER
STD STANDARD
STC SINGLE TRACK CANTILEVER
STIFF STIFFENER
STL STEEL
STOR STORAGE
STP SHIELDED TWISTED PAIR CABLE
STR STRUCTURAL, STRUCTURE
STS SPIRAL TANGENT SPIRAL
STW STATIC WIRE
SUPV SUPERVISORY

T TREAD
T&B TOP AND BOTTOM
TAN TANGENT
TASAS TRAFFIC ACCIDENT SURVEILLANCE ANALYSIS SYSTEM
TBD TO BE DETERMINED
TBM TUNNEL BORING MACHINE
TCL TRACK CENTERLINE
TC TRAIN CONTROL
TCB TRAFFIC CONTROL BOX
TCC TRAIN CONTROL AND COMMUNICATIONS
TCCR TRAIN CONTROL AND COMMUNICATIONS ROOM
TCCT TRACK CIRCUIT
TCE TEMPORARY CONSTRUCTION EASEMENT
TCP/IP TRANSMISSION CONTROL PROTOCOL/ INTERNET PROTOCOL
TCR TRANSMISSION COMMUNICATIONS ROOM
TD TRENCH DRAIN, TIME DELAY
TDA TIRE DERIVED AGGREGATE
TDD TELECOMMUNICATIONS DEVICE FOR THE DEAF
TDM TIME DIVISION MULTIPLEXING
TEL TELEPHONE
TEMP TEMPORARY
TERM TERMINATION
TES TRACTION ELECTRIFICATION SYSTEM
TESC TEMPORARY EROSION AND SETTLEMENT CONTROL
TETEL TRAIN EMERGENCY TELEPHONE/SPEAKERPHONE
TFE TETRAFLUROETHYLENE
TG TOP OF GRADE
THK THICK
TIS TELEPHONE AND INTERCOM SYSTEM
TL TENSION LENGTH
TM TECHNICAL MEMORANDUM
TMP TEMPERATURE
TO TURNOUT, TELECOM OUTLET
TOC TOP OF CURB
TOG TOP OF GRATE
TOL TOLERANCE
TOLR TOP OF LOW RAIL
TOF TOP OF FOUNDATION
TOFG TOP OF FINISH GRADE
TOP TOP OF PAVEMENT
TOR TOP OF RAIL
TOS TOP OF SLOPE
TOT TOP OF TIE, TOTAL
TOW TOP OF WALL
TP TELEPHONE POLE, TRACTION POWER
TPB TREATED PERMEABLE BASE
TPD TOILET PAPER DISPENSER
TPF TRACTION POWER FACILITY
TPM TREATED PERMEABLE MATERIAL
TPS TRACTION POWER SUPPLY SYSTEM
TRANS TRANSVERSE, TRANSITION
TRK TRACK
TS TRAFFIC SIGNAL
TSI TUBULAR STEEL
TSI TECHNICAL SPECIFICATIONS FOR INTEROPERABILITY
TSM TRAFFIC SYSTEMS MANAGEMENT
TSMF TRAFFIC SYSTEMS MANAGEMENT PLAN

T

P

P/L PROPERTY LINE
PA PUBLIC ADDRESS
PACIS PUBIC ADDRESS / CUSTOMER INFORMATION SYSTEM
PAN PANTOGRAPH
PAP PERFORATED ALUMINUM PIPE
PB PULL BOX, PUSH BUTT (ON ELECTRICAL DIAGRAMS)
PBX PRIVATE BRANCH EXCHANGE
PC PRECAST CONCRETE
PCC PORTLAND CEMENT CONCRETE
PCP PERFORATED CONCRETE PIPE
PCPT PIEZOONE PENETROMETER TEST
PE PORCELAIN ENAMEL
PED PEDESTRIAN
PERF PERFORATED
PERM PERMEABLE
PET POTENTIAL EQUALIZING JUMPER
PF POWER FACTOR
PFDHA PROBABILISTIC FAULT DISPLACEMENT HAZARD ANALYSIS
PG PROFILE GRADE
PH PHASE
PHE POTHOLE
PID PASSENGER INFORMATION DISPLAY
PITO POINT OF INTERSECTION TURNOUT
PJP PARTIAL JOINT PENETRATION
PL PLATE
PLAM PLASTIC LAMINATE
PLAS PLASTER
PLC PROGRAMMABLE LOGIC CONTROLLER
PLYWD PLYWOOD
PM POST MILE, TIME FROM NOON TO MIDNIGHT
PMS PAVEMENT MANAGEMENT SYSTEM
PN PAVING NOTCH
PNL PANEL
PNT POINT
PO PULL OFF
POC POINT OF CONNECTION
POE POINT OF ENDING
POS POSITIVE
POTS PLAIN ORDINARY TELEPHONE SERVICE
PP PLASTIC PIPE, POWER POLE
PPL PREFORMED PERMEABLE LINER
PPP PERFORATED PLASTIC PIPE
PR PAIR
PRI PRIMARY RATE INTERFACE (ISDN SERVICE)
PROP PROPOSED
PS PARALLELING STATION
P/S PRESTRESSED, PERFORATED STEEL PIPE
PSP PRODUCT SAFETY PLAN
PSTN PUBLIC SWITCHED TELEPHONE NETWORK
PSTTWS PUBLIC SAFETY TRENCH AND TUNNEL WIRELESS SYSTEM
PSU POWER SUPPLY UNIT
PT POTENTIAL TRANSFORMER
PTC POSITIVE TRAIN CONTROL

2/11/2014 5:14:14 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\nt\mincio\dms32160\DD-GE-102.dgn mincio

04/02/2014 - RFP No.: HSR 13-57

Table with columns: REV, DATE, BY, CHK, APP, DESCRIPTION. Row 1: 01/24/2014

Table with columns: DESIGNED BY, DRAWN BY, CHECKED BY, IN CHARGE, DATE. Values: R. MINCIO, V. HUANTE, S. MILITELLO, J. CHIRCO, 01/24/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT DIRECTIVE DRAWING
ACRONYMS AND ABBREVIATIONS 3

Table with columns: CONTRACT NO., DRAWING NO., SCALE, SHEET NO. Values: DD-GE-102, NO SCALE

T CONTINUED

W CONTINUED

TRACK GEOMETRY - HORIZONTAL

UNITS OF MEASUREMENT

TTC TWO TRACK CANTILEVER
TTEL TRAIN EMERGENCY SPEAKERPHONE
TV TELEVISION
TVM(S) TICKET VENDING MACHINE(S)
TW TIE WIRE
TYP TYPICAL

WS WATER SURFACE,
WORK STATION
WSP WELDED STEEL PIPE
WT WEIGHT
WV WATER VALVE
WW WINGWALL,
WALKWAY
WWF WELDED WIRE FABRIC
WWLOL WINGWALL LAYOUT LINE
WWM WELDED WIRE MESH

BC BEGIN HORIZONTAL CURVE
CC COMPOUND CURVE
CS POINT OF CHANGE FROM CIRCULAR CURVE TO SPIRAL
K1 TANGENT DISTANCE PF SHIFT PC
REFERENCE TO THE TS
K2 TANGENT DISTANCE PF SHIFT PT
REFERENCE TO THE ST

Ac ACRES
AMP AMPERES
BTU BRITISH THERMAL UNIT
CAL CALIPER
CF CUBIC FEET
CP CANDLE POWER
CY CUBIC YARD

U

X

U/S UNDERSIDE
UB UTILITY BOX
UC UNDERCROSSING
UD UNDERDRAIN
UG UNDERGROUND,
UNDER GRADE
UGB UNDERGRADE BRIDGE
UI USER INTERFACE
UNF UNFINISHED
UNINS UNINSULATED
UON UNLESS OTHERWISE NOTED
UP UNDERPASS
UPS UNINTERRUPTIBLE POWER SUPPLY
UR URINAL
UrEDAS URGENT EARTHQUAKE DETECTION AND
ALARM SYSTEM
USCS UNITED SOIL CLASSIFICATION SYSTEM
UTIL UTILITY
UTP UNSHIELDED TWISTED PAIR
UWP UPPER WORKING POINT

X/CAT CROSS CANTENARY
X/SPAN CROSS SPAN
XD TRANSDUCER
XFMR TRANSFORMER
XO CROSSOVER
XO ST CROSSOVER SPRING TENSIONER
XSEC CROSS SECTION
XING CROSSING
XMITTER TRANSMITTER

Lc LENGTH OF CIRCULAR CURVE
Ls1 LENGTH OF SPIRAL
Ls2 LENGTH OF SPIRAL FROM TS TO SC
LSC LENGTH OF SPIRAL FROM CS TO ST
LVC LENGTH OF COMPOUND SPIRAL FROM CS TO SC
p1 OFFSET FROM INITIAL TANGENT TO PC OF THE SHIFTED
CIRCLE OF SPIRALIZED CURVE
p2 OFFSET FROM INITIAL TANGENT TO PT OF THE SHIFTED
CIRCLE OF SPIRALIZED CURVE
PC POINT OF CURVATURE
PCC POINT OF COMPOUND CURVE
PF POINT OF FROG
PI POINT OF INTERSECTION
PITO POINT OF INTERSECTION TURNOUT
POC POINT ON HORIZONTAL CURVE
POE POINT OF ENDING
POS POINT ON SPIRAL,
POVC POINT ON VERTICAL CURVE
POVT POINT ON VERTICAL TANGENT
PRC POINT OF REVERSE CURVE
PRVC POINT OF REVERSE VERTICAL CURVE
PS POINT OF SWITCH
PT POINT OF TANGENT

dB DECIBEL
DEG DEGREE
DIA DIAMETER
Eu UNBALANCED SUPERELEVATION
F FARENHEIT
FT FOOT,
FEET
g ACCELERATION DUE TO GRAVITY
GA GAUGE
GAL GALLON
GB GIGABYTE
GBPS GIGABITS PER SECOND
GHZ GIGAHERTZ
HR HOUR
HT HEIGHT
HZ HERTZ
ID INSIDE DIAMETER
IF INSIDE FACE
IN INCHES
IR INSIDE RADIUS

V

V DESIGN SPEED,
VALVE
VAC VOLTS ALTERNATING CURRENT
VAR VARIABLE,
VARIES,
VOLT-AMPERE REACTIVE
VCAT VIRTUAL CONCATENATION
VCP VITRIFIED CLAY PIPE
VCT VINYL COMPOSITION TILE
VDC VOLT DC
VE VALUE ENGINEERING
VERT VERTICAL
VEST VESTIBULE
VIA VIADUCT
VLAN VIRTUAL LOCAL AREA NETWORK
VMS VARIABLE MESSAGE SIGN,
VARIABLE MESSAGE SYSTEM,
VOLTIMETER
VOL VOLUME
VOIP VOICE OVER INTERNET PROTOCOL
VPN VIRTUAL PRIVATE NETWORK
VRCS VOICE RADIO COMMUNICATIONS SYSTEM
VS VOLTAGE SWITCH
VT VOLTAGE TRANSFORMER/TRANSDUCER

SC POINT OF CHANGE FROM SPIRAL TO
CIRCULAR CURVE
SPO POINT ON ORIGIN OF COMPOUND SPIRAL
SS POINT OF CHANGE BETWEEN SPIRALS
SSC SPIRAL TO SPIRAL POINT OF CURVATURE
ST POINT OF CHANGE FROM SPIRAL TO TANGENT
TC POINT OF CHANGE FROM TANGENT TO CURVE
TS POINT OF CHANGE FROM TANGENT TO SPIRAL
Ts1 TANGENT DISTANCE FROM TS TO PI
Ts2 TANGENT DISTANCE FROM ST TO PI
Xs1 TANGENT OFFSET AT THE SC
Xs2 TANGENT OFFSET AT THE CS
Ys1 TANGENT DISTANCE AT THE SC
Ys2 TANGENT DISTANCE AT THE CS
Δ TOTAL CENTRAL ANGLE OF THE SPIRALIZED CURVE
Δc CENTRAL ANGLE OF CIRCULAR CURVE (Lc) FROM
SC TO CS
Δc1 CENTRAL ANGLE OF FIRST CIRCULAR CURVE OF
COMPOUND CURVATURE
Δc2 CENTRAL ANGLE OF SECOND CIRCULAR CURVE OF
COMPOUND CURVATURE
θs1 CENTRAL ANGLE OF SPIRAL LENGTH Ls1 OR SPIRAL
ANGLE OF FIRST SPIRAL IN SPIRALIZED CURVE
θs2 CENTRAL ANGLE OF SPIRAL LENGTH Ls2 OR SPIRAL
ANGLE OF SECOND SPIRAL IN SPIRALIZED CURVE
θsc CENTRAL ANGLE OF COMPOUND SPIRAL OR COMPOUND
SPIRAL ANGLE FROM CS TO SC

K KIPS (1000 POUNDS)
KCMIL THOUSAND CIRCULAR MILS
KHZ KILOHERTZ
KSF KIPS PER SQAURE FOOT
KSI KIPS PER SQUARE INCH
kV KILOVOLTS
KVA KILOVOLT-AMPERE
KVAR KILOVOLT-AMPERE REACTIVE
KW KILOWATT
KWH/D KILOWATT HOUR / DEMAND
L LENGTH
LB POUNDS
LB/FT POUNDS PER FOOT
LF LINEAR FEET
m METER
MBPS MEGA-BITS PER SECOND
MCM THOUSAND CIRCULAR MILS
MHZ MEGAHERTZ
mm MILLIMETER
MPH MILES PER HOUR
MVA MEGAVOLT-AMPERE
MW MEGA WATT
OD OUTSIDE DIAMETER
PSF POUNDS PER SQUARE FOOT
PSI POUNDS PER SQUARE INCH
PSIG POUNDS PER SQUARE INCH GAUGE

W

W WEST,
WIDTH
W/ WITH
W/O WITHOUT
WA WORK AREA
WB WESTBOUND
WC WATER CLOSET
WCS WIRELESS COMMUNICATIONS SYSTEM
WD WOOD
WLAN WIRELESS LOCAL AREA NETWORK
WM WIRE MESH
WP WORK POINT,
WOOD POLE
WPF WATERPROOF
WPC WAYSIDE POWER CUBICLES
WR WIRE RUN
WRT WITH RESPECT TO

TRACK GEOMETRY - VERTICAL

BVC BEGIN VERTICAL CURVE
Ea ACTUAL SUPERELEVATION
EVC END VERTICAL CURVE
PCVC POINT OF COMPOUND VERTICAL CURVE
POVC POINT OF VERTICAL INTERSECTION
POVT POINT ON VERTICAL CURVE
PVI POINT ON VERTICAL TANGENT
VC VERTICAL CURVE
VPI VERTICAL POINT OF INTERSECTION


SEC SECOND
SF SQUARE FEET
SY SQUARE YARD
TF TRACK FEET
VA VOLTS
VAC VOLT-AMPERE
Y YARDS
YR(S) YEAR(S)

c:\projectwise\pb\projectwise\int\mincio\dms32160\DD-GE-103.dgn
CAHSRP.tbl CAHSRP.tbl CHSR_half_black.plt 2/11/2014 5:15:13 PM mincio

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY R. MINCIO
DRAWN BY V. HUANTE
CHECKED BY S. MILITELLO
IN CHARGE J. CHIRCO
DATE 01/24/2014



**CALIFORNIA HIGH-SPEED TRAIN PROJECT
DIRECTIVE DRAWING**

ACRONYMS AND ABBREVIATIONS 4

CONTRACT NO.
DRAWING NO. DD-GE-103
SCALE NO SCALE
SHEET NO.

AGENCIES/ORGANIZATIONS/REFERENCE

AGENCIES/ORGANIZATIONS/REFERENCE CONTINUED

SEGMENT/COUNTY CODES AND SUBDIVISIONS

AAR ASSOCIATION OF AMERICAN RAILROADS
 AASHTO AMERICAN ASSOCIATION OF STATE HIGHWAY TRANSPORTATION OFFICIALS
 ACI AMERICAN CONCRETE INSTITUTE
 AISC AMERICAN INSTITUTE OF STEEL CONSTRUCTION
 AMTRAK NATIONAL RAILROAD PASSENGER CORPORATION
 ANSI AMERICAN NATIONAL STANDARDS INSTITUTE
 ANSS ADVANCED NATIONAL SEISMIC SYSTEM
 APWA AMERICAN PUBLIC WORKS ASSOCIATION
 AREA AMERICAN RAILWAY ENGINEERING ASSOCIATION
 AREMA AMERICAN RAILWAY ENGINEERING AND MAINTENANCE-OF-WAY ASSOCIATION
 ASCE AMERICAN SOCIETY OF CIVIL ENGINEERS
 ASTM ASTM INTERNATIONAL
 ATC AMERICAN SOCIETY OF TESTING & MATERIALS
 AWS APPLIED TECHNOLOGY COUNCIL
 BART AMERICAN WELDING SOCIETY
 BDA BAY AREA RAPID TRANSIT DISTRICT
 BDD BRIDGE DESIGN AIDS (CALTRANS)
 BDP BRIDGE DESIGN DETAILS (CALTRANS)
 BDS BRIDGE DESIGN PRACTICE (CALTRANS)
 BNSF BRIDGE DESIGN SPECIFICATIONS (CALTRANS)
 CALNET BURLINGTON NORTHERN SANTA FE RAILWAY CALIFORNIA INTEGRATED TELECOMMUNICATIONS NETWORK
 CALTRANS CALIFORNIA DEPARTMENT OF TRANSPORTATION
 CBC CALIFORNIA BUILDING CODE
 CBDM CALIFORNIA DEPARTMENT OF TRANSPORTATION - BRIDGE DESIGN MANUAL
 CCR CALIFORNIA CODE OF REGULATIONS
 CDC CALIFORNIA HIGH-SPEED TRAIN DESIGN CRITERIA
 CEC CALIFORNIA ELECTRIC CODE
 CEQA CALIFORNIA ENVIRONMENTAL QUALITY ACT
 CFR CODE OF FEDERAL REGULATIONS
 CHD COUNTY HEALTH DEPARTMENT
 CHP CALIFORNIA DEPARTMENT OF HIGHWAY PATROL (STATE)
 CHST CALIFORNIA HIGH-SPEED TRAIN
 CHSTP CALIFORNIA HIGH-SPEED TRAIN PROJECT
 CIWMB CALIFORNIA INTEGRATED WASTE MANAGEMENT BOARD (STATE)
 CPH CALIFORNIA PERMIT HANDBOOK
 CPUC CALIFORNIA PUBLIC UTILITIES COMMISSION
 CRR COMMUTER RAIL PROGRAM (STATE)
 DOD DEPARTMENT OF DEFENSE (FEDERAL)
 DOT DEPARTMENT OF TRANSPORTATION (FEDERAL)
 DTX DOWNTOWN EXTENSION (CALTRAIN)
 EIRENE EUROPEAN INTEGRATED RADIO ENHANCED NETWORK
 ERTMS EUROPEAN RAIL TRAFFIC MANAGEMENT SYSTEM
 FAA FEDERAL AVIATION ADMINISTRATION
 FCC FEDERAL COMMUNICATIONS COMMISSION
 FEMA FEDERAL EMERGENCY MANAGEMENT AGENCY
 FHWA FEDERAL HIGHWAY ADMINISTRATION
 FMFCD FRESNO METROPOLITAN FLOOD CONTROL DISTRICT
 FRA FEDERAL RAILROAD ADMINISTRATION
 FSTIP FEDERAL STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM
 FTA FEDERAL TRANSIT ADMINISTRATION
 GBR GEOTECHNICAL BASELINE REPORT
 GBR-B GEOTECHNICAL BASELINE REPORT FOR BIDDING
 GBR-C GEOTECHNICAL BASELINE REPORT FOR CONSTRUCTION
 GDR GEOTECHNICAL DATA REPORT
 IEEE INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS
 ISO INTERNATIONAL ORGANIZATION FOR STANDARDIZATION
 LADWP LOS ANGELES DEPARTMENT OF WATER AND POWER
 LAUS LOS ANGELES UNION STATION
 LTC LOCAL TRANSPORTATION COMMISSION
 MUTCD MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES
 NAAQS NATIONAL AMBIENT AIR QUALITY STANDARDS
 NAC NOISE ABATEMENT CRITERIA
 NBSSR NOISE BARRIER SCOPE SUMMARY REPORT
 NEMA NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
 NENA NATIONAL EMERGENCY NUMBER ASSOCIATION
 NESC NATIONAL ELECTRICAL SAFETY CODE
 NFPA NATIONAL FIRE PROTECTION ASSOCIATION
 NIST NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY
 OSHA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
 PEER PACIFIC EARTHQUAKE ENGINEER RESEARCH

PG&E PACIFIC GAS & ELECTRIC COMPANY
 PUC PUBLIC UTILITIES COMMISSION (STATE)
 RSIA RAIL SAFETY IMPROVEMENT ACT (2008)
 RWQCB REGIONAL WATER QUALITY CONTROL BOARD (STATE)
 SDG&E SAN DIEGO GAS & ELECTRIC COMPANY
 SDNR SAN DIEGO NORTHERN RAILWAY
 SAVE SOCIETY OF AMERICAN VALUE ENGINEERS
 SHOPP STATE HIGHWAY OPERATION AND PROTECTION PROGRAM (FORMERLY HSOPP)
 SHPO STATE HISTORIC PRESERVATION OFFICER (STATE)
 SJRRA SAN JOAQUIN REGIONAL RAIL AUTHORITY
 SMUD SACRAMENTO MUNICIPAL UTILITY DISTRICT
 SPTC SOUTHERN PACIFIC TRANSPORTATION COMPANY
 SSORC SAFETY AND SECURITY OVERSIGHT AND REVIEW COMMITTEE
 SVBX SILICON VALLEY BERRYESSA EXTENSION
 SVRT SILICON VALLEY RAPID TRANSIT
 UPRR UNION PACIFIC RAILROAD
 US UNITED STATES
 USCE UNITED STATES (ARMY) CORPS OF ENGINEERS
 USCG UNITED STATES COAST GUARD
 USCS UNITED SOIL CLASSIFICATION SYSTEM
 VTA VALLEY TRANSPORTATION AUTHORITY (OF SANTA CLARA COUNTY)

A-J ALTAMONT PASS
 B-P BAKERSFIELD TO PALMDALE
 F-B FRESNO TO BAKERSFIELD
 F-J SAN FRANCISCO TO SAN JOSE
 J-M SAN JOSE TO MERCED
 L-D LOS ANGELES TO SAN DIEGO
 L-O LOS ANGELES TO ANAHEIM
 M-F MERCED TO FRESNO
 P-L PALMDALE TO LOS ANGELES
 S-M SACRAMENTO TO MERCED
 B BAY SUBDIVISION
 C CAPITAL SUBDIVISION
 D DESERT SUBDIVISION
 J SAN JACINTO SUBDIVISION
 P PACHECO SUBDIVISION
 S SIERRA SUBDIVISION
 T TONGVA SUBDIVISION
 ALA ALAMEDA
 ALP ALPINE
 AMA AMADOR
 BUT BUTTE
 CAL CALAVERAS
 CC CONTRA COSTA
 COL COLUSA
 DN DEL NORTE
 ED EL DORADO
 FRE FRESNO
 GLE GLENN
 HUM HUMBOLDT
 IMP IMPERIAL
 INY INYO
 KER KERN
 KIN KINGS
 LA LOS ANGELES
 LAK LAKE
 LAS LASSEN
 MAD MADERA
 MEN MENDOCINO
 MER MERCED
 MNO MONO
 MOD MODOC
 MON MONTEREY
 MPA MARIPOSA
 MRN MARIN
 NAP NAPA
 NEV NEVADA
 ORA ORANGE
 PLA PLACER
 PLU PLUMAS
 RIV RIVERSIDE
 SAC SACRAMENTO
 SB SANTA BARBARA
 SBD SAN BERNADINO
 SBT SAN BENITO
 SCL SANTA CLARA
 SCR SANTA CRUZ
 SD SAN DIEGO
 SF SAN FRANCISCO
 SHA SHASTA
 SIE SIERRA
 SIS SISKIYOU
 SJ SAN JOAQUIN
 SLO SAN LUIS OBISPO
 SM SAN MATEO
 SOL SOLANO
 SON SONOMA
 STA STANISLAUS
 SUT SUTTER
 TEH TEHAMA
 TRI TRINITY
 TUL TULARE
 TUO TUOLUMNE
 VEN VENTURA
 YOL YOLO
 YUB YUBA

2/11/2014 5:16:45 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32160\DD-GE-104.dgn mincio

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
R. MINCIO
 DRAWN BY
V. HUANTE
 CHECKED BY
S. MILITELLO
 IN CHARGE
J. CHIRCO
 DATE
01/24/2014



**CALIFORNIA HIGH-SPEED TRAIN PROJECT
 DIRECTIVE DRAWING**

ACRONYMS AND ABBREVIATIONS 5

CONTRACT NO.
DRAWING NO. DD-GE-104
SCALE NO SCALE
SHEET NO.

California High-Speed Rail Authority



RFP No.: HSR 13-57


**Request for Proposals for Design-Build
Services for Construction Package 2-3**

**Book II, Part B.1
Directive Drawings**

Civil

NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. SUBGRADE THICKNESS SHALL BE DETERMINED BASED ON THE EXISTING GROUND CONDITION.
3. THE CONTROL POINT (CP) SHALL BE 2'-6" ABOVE THE TOP OF SUBBALLAST.
4. FOR EMBANKMENT SLOPE GRADING, S=2 (MIN).
5. PROTECTIVE BARRIER, SUCH AS A BERM OR A DIKE, SHALL BE INSTALLED AT THE RIGHT-OF-WAY BOUNDARY TO INTERCEPT STORM WATER RUN OFF, WHERE THERE IS A POTENTIAL FOR STORM WATER RUN OFF TO ENTER CHST RIGHT-OF-WAY FROM ADJACENT PROPERTY.



3/28/2014 3:21:43 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\m\incio\dms32166\DD-CV-100.dgn

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
D. MANITI
DRAWN BY
V. HUANTE
CHECKED BY
G. HARRIS
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014

**PARSONS
BRINCKERHOFF**



**CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE**


TYPICAL CROSS SECTION
TWO TRACK
EMBANKMENT

CONTRACT NO.
DRAWING NO.
DD-CV-100
SCALE
AS SHOWN
SHEET NO.


04/02/2014 - RFP No.: HSR 13-57

NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. SUBGRADE THICKNESS SHALL BE DETERMINED BASED ON THE EXISTING GROUND CONDITION.
3. THE CONTROL POINT (CP) SHALL BE 2'-6" ABOVE THE TOP OF SUBBALLAST.
4. FOR EMBANKMENT SLOPE GRADING, S=2 (MIN).
5. PROTECTIVE BARRIER, SUCH AS A BERM OR A DIKE, SHALL BE INSTALLED AT THE RIGHT-OF-WAY BOUNDARY TO INTERCEPT STORM WATER RUN OFF, WHERE THERE IS A POTENTIAL FOR STORM WATER RUN OFF TO ENTER CHST RIGHT-OF-WAY FROM ADJACENT PROPERTY.
6. A 20-FOOT MAINTENANCE ACCESS IS REQUIRED FOR CUT SLOPES HIGHER THAN 30 FEET.



PROTECTIVE BARRIER DETAILS
(SEE NOTE 5)




TYPICAL SECTION
TWO TRACK
OPEN CUT



3/28/2014 4:41:30 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32166\DD-CV-101.dgn mincio

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
D. MANITI
DRAWN BY
R. MINCIO
CHECKED BY
G. HARRIS
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE

TYPICAL CROSS SECTION
TWO TRACK
OPEN CUT

CONTRACT NO.
DRAWING NO.
DD-CV-101
SCALE
AS SHOWN
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

9/30/2014 12:28:14 PM CAHSR.tbl CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32166\DD-CV-102.dgn



- NOTES:**
1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. SUBGRADE THICKNESS SHALL BE DETERMINED BASED ON THE EXISTING GROUND CONDITION.
 3. THE CONTROL POINT (CP) SHALL BE 2'-6" ABOVE THE TOP OF SUBBALLAST.
 4. PROTECTIVE BARRIER, SUCH AS A BERM OR A DIKE, SHALL BE INSTALLED AT THE RIGHT-OF-WAY BOUNDARY TO INTERCEPT STORM WATER RUN OFF, WHERE THERE IS A POTENTIAL FOR STORM WATER RUN OFF TO ENTER CHST RIGHT-OF-WAY FROM ADJACENT PROPERTY.
 5. 10' MIN MAINTENANCE ACCESS REQUIRED WHEN THERE IS NO FENCE OR CONTINUOUS OBSTRUCTION.
 6. PROVIDE APPROPRIATE DRAINAGE SYSTEM FOR THE TYPE OF RETAINING WALL.

TYPICAL SECTION
TWO TRACK
RETAINED FILL



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
S. MILITELLO

DRAWN BY
R. MINCIO

CHECKED BY
G. HARRIS

IN CHARGE
G. LUSHEROVICH

DATE
08/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE

TYPICAL CROSS SECTION
TWO TRACK
RETAINED FILL

CONTRACT NO.


DRAWING NO.
DD-CV-102

SCALE
AS SHOWN

SHEET NO.


RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

3/28/2014 4:43:17 PM CAHSR.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32166\DD-CV-103.dgn




TYPICAL SECTION
ONE TRACK
EMBANKMENT

- NOTES:**
1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. SUBGRADE THICKNESS SHALL BE DETERMINED BASED ON THE EXISTING GROUND CONDITION.
 3. THE CONTROL POINT (CP) SHALL BE 2'-6" ABOVE THE TOP OF SUBBALLAST.
 4. FOR EMBANKMENT SLOPE GRADING, S=2 (MIN).
 5. PROTECTIVE BARRIER, SUCH AS A BERM OR A DIKE, SHALL BE INSTALLED AT THE RIGHT-OF-WAY BOUNDARY TO INTERCEPT STORM WATER RUN OFF, WHERE THERE IS A POTENTIAL FOR STORM WATER RUN OFF TO ENTER CHST RIGHT-OF-WAY FROM ADJACENT PROPERTY.
 6. A 20-FOOT MAINTENANCE ACCESS IS REQUIRED FOR CUT SLOPES HIGHER THAN 30 FEET.



PROTECTIVE BARRIER DETAILS
(SEE NOTE 5)



TYPICAL SECTION
ONE TRACK
OPEN CUT



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
D. MANITI
 DRAWN BY
R. MINCIO
 CHECKED BY
G. HARRIS
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE
 TYPICAL CROSS SECTION
 ONE TRACK
 EMBANKMENT AND OPEN CUT

CONTRACT NO.
 DRAWING NO.
DD-CV-103
 SCALE
AS SHOWN
 SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. SUBGRADE THICKNESS SHALL BE DETERMINED BASED ON THE EXISTING GROUND CONDITION.
3. THE CONTROL POINT (CP) SHALL BE 2'-6" ABOVE THE TOP OF SUBBALLAST.
4. FOR EMBANKMENT SLOPE GRADING, S=2 (MIN).
5. PROTECTIVE BARRIER, SUCH AS A BERM OR A DIKE, SHALL BE INSTALLED AT THE RIGHT-OF-WAY BOUNDARY TO INTERCEPT STORM WATER RUN OFF, WHERE THERE IS A POTENTIAL FOR STORM WATER RUN OFF TO ENTER CHST RIGHT-OF-WAY FROM ADJACENT PROPERTY.



TYPICAL SECTION
FOUR TRACK
EMBANKMENT



3/28/2014 3:32:46 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32166\DD-CV-104.dgn mincio

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
D. MANITI
DRAWN BY
R. MINCIO
CHECKED BY
G. HARRIS
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE

TYPICAL CROSS SECTION
FOUR TRACK
EMBANKMENT

CONTRACT NO.
DRAWING NO.
DD-CV-104
SCALE
AS SHOWN
SHEET NO.

c:\projectwise\bb\projectwise\int\mincio\dms32166\DD-CV-105.dgn
 CAHSRP.tbl CHSR_half_black.plt
 2/27/2014 4:27:12 PM
 mincio



TYPICAL SECTION
AERIAL TRACKWAY

NOTES:

1. STRUCTURE, TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. SUBGRADE THICKNESS SHALL BE DETERMINED BASED ON THE EXISTING GROUND CONDITION.
3. THE CONTROL POINT (CP) SHALL BE 2'-6" ABOVE THE TOP OF STRUCTURE WITH NON-BALLASTED TRACK. FOR BALLASTED TRACK THE CONTROL POINT (CP) SHALL BE LOCATED ABOVE STRUCTURE DECK AT A DISTANCE 2'-9" PLUS ALLOWANCE FOR WATER PROOFING MEMBRANE AND PROTECTION LAYER (IF REQUIRED).
4. PROTECTIVE BARRIER, SUCH AS A BERM OR A DIKE, SHALL BE INSTALLED AT THE RIGHT-OF-WAY BOUNDARY TO INTERCEPT STORM WATER RUN OFF, WHERE THERE IS A POTENTIAL FOR STORM WATER RUN OFF TO ENTER CHST RIGHT-OF-WAY FROM ADJACENT PROPERTY.

REV	DATE	BY	CHK	APP	DESCRIPTION


DESIGNED BY
D. MANITI
 DRAWN BY
R. MINCIO
 CHECKED BY
G. HARRIS
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE
 TYPICAL CROSS SECTION
 TWO TRACK
 AERIAL TRACKWAY

CONTRACT NO.
 DRAWING NO.
DD-CV-105
 SCALE
AS SHOWN
 SHEET NO.

04/02/2014 - RFP No.: HSR 13-57



- NOTES:**
1. STRUCTURE, TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. SUBGRADE THICKNESS SHALL BE DETERMINED BASED ON THE EXISTING GROUND CONDITION.
 3. THE CONTROL POINT (CP) SHALL BE 2'-6" ABOVE THE TOP OF SUBBALLAST.
 4. PROTECTIVE BARRIER, SUCH AS A BERM OR A DIKE, SHALL BE INSTALLED AT THE RIGHT-OF-WAY BOUNDARY TO INTERCEPT STORM WATER RUN OFF, WHERE THERE IS A POTENTIAL FOR STORM WATER RUN OFF TO ENTER CHST RIGHT-OF-WAY FROM ADJACENT PROPERTY.



TYPICAL SECTION
TRENCH

3/28/2014 4:45:31 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32166\DD-CV-106.dgn mincio

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
D. MANITI
DRAWN BY
R. MINCIO
CHECKED BY
G. HARRIS
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE

TYPICAL CROSS SECTION
TWO TRACK
TRENCH STRUCTURE

CONTRACT NO.
DRAWING NO. DD-CV-106
SCALE AS SHOWN
SHEET NO.


04/02/2014 - RFP No.: HSR 13-57

9/30/2014 11:40:16 AM CAHSR.tbl CHSR_PDF_half_black.plt c:\projects\hst\project\hst\laverdev\dms32166\DD-CV-900.dgn




ACCESS RESTRICTION FENCE

- NOTES:**
1. ALL PERMANENT FENCING AND GATES SHALL BE BONDED, GROUNDED AND INSULATED TO PREVENT ELECTRIC SHOCK.
 2. ACCESS RESTRICTION (AR) FENCING SHALL BE 8 FEET HIGH MINIMUM (AS SHOWN HERE). ACCESS DETERRING (AD) FENCING (NOT SHOWN) SHALL BE 6 FEET HIGH, WITH NO BARBED WIRE.
 3. GATES FOR VEHICULAR ACCESS (DRIVING GATES) SHALL BE SIZED IN COORDINATION WITH EMERGENCY RESPONDERS AND MAINTENANCE EQUIPMENT. IF NO OTHER INFORMATION IS AVAILABLE THESE GATES SHOULD HAVE A MINIMUM WIDTH OF 12 FEET.
 4. GATES CAN EITHER BE SWINGING OR SLIDING TYPE. VEHICULAR ACCESS SWINGING GATES SHALL BE A PAIR AND SHALL BE HINGED FROM THE INSIDE. PROVISIONS SHALL BE MADE FOR SWINGING GATES TO SWING NOT LESS THAN 90 DEGREES AWAY FROM THE HST FACILITIES.
 5. THIS DRAWING DEPICTS MINIMUM STANDARDS FOR RIGHT-OF-WAY FENCING AND GATE. ALTERNATIVE FENCE TYPE OF EQUIVALENT OR ENHANCED KIND MAY BE ALLOWED UPON APPROVAL OF THE AUTHORITY.
 6. FENCE AND GATES SHALL BE DESIGNED AND INSTALLED TO NOT PRECLUDE FUTURE INSTALLATION OF TYPICAL FENCE MOUNTED ELECTRONIC ACCESS CONTROL.
 7. FOR ADDITIONAL FENCE INSTALLATION DETAILS SEE CALTRANS STANDARD PLANS.



VEHICLE ACCESS GATE ALONG AR FENCE



PEDESTRIAN ACCESS GATE ALONG AR FENCE



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
S. MILITELLO
DRAWN BY
V. LAVERDE
CHECKED BY
A. ABTAHI
IN CHARGE
G. LUSHEROVICH
DATE
08/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE

ACCESS RESTRICTION
FENCE AND GATE DETAILS

CONTRACT NO.
DRAWING NO.
DD-CV-900
SCALE
AS SHOWN
SHEET NO.


RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

9/30/2014 12:26:43 PM CAHSR.tbl CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\m\incio\dms32166\DD-CV-901.dgn




**GATE LOCATIONS ALONG HST TRACKWAY
AT GRADE**


- NOTES:**
1. LOCATION OF GATES ALONG RIGHT-OF-WAY FENCING MAY REQUIRE COORDINATION WITH THE LOCAL FIRE PROTECTION AGENCY AND EMERGENCY RESPONDERS.
 2. IN GENERAL VEHICULAR ACCESS GATE ALONG AT-GRADE TRACKWAY, SHALL BE LOCATED NOMINALLY AT 2.5 MILE INTERVALS AND COORDINATED WITH THE LOCATION OF HST WAYSIDE FACILITIES.
 3. GATE LOCATIONS ALONG FENCING WITHIN FREEWAY RIGHT-OF-WAY REQUIRE CALTRANS APPROVAL.
 4. VEHICULAR ACCESS GATES SHALL BE PROVIDED IN CONJUNCTION WITH EITHER ACCESS ROADS OR AT LOCATIONS WHERE EXISTING ROADS MAKE IT PRACTICABLE FOR MAINTENANCE AND EMERGENCY VEHICLE TO ACCESS THE TRACKWAY.
 5. FOR ADDITIONAL DETAILS SEE CIVIL DRAWING "ACCESS RESTRICTION FENCE AND GATE DETAILS".
 6. AD FENCE CAN BE USED IF AR FENCE IS PLACED ALONG THE RIGHT-OF-WAY OR THE HEIGHT OF THE WALL IS GREATER THAN 10 FEET. 15 FOOT MINIMUM REQUIRED TO THE FENCE WHEN AD FENCE IS PLACED ALONG THE RIGHT-OF-WAY.




**FENCE LOCATION ALONG
HST TRACKWAY
RETAINED CUT SECTION**



**FENCE LOCATION ALONG
HST TRACKWAY
RETAINED FILL SECTION**



**FENCE LOCATION ALONG
HST TRACKWAY
OPEN CUT SECTION**



**FENCE LOCATION ALONG
HST TRACKWAY
EMBANKMENT SECTION**

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
S. MILITELLO
DRAWN BY
V. LAVERDE
CHECKED BY
A. ABTAHI
IN CHARGE
G. LUSHEROVICH
DATE
08/29/2014




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE**

ACCESS RESTRICTION
FENCE AND GATE LOCATIONS


CONTRACT NO.
DRAWING NO.
DD-CV-901
SCALE
NO SCALE
SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014


9/30/2014 11:41:34 AM CAHSR.tbl CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\laverdev\dms32166\DD-CV-902.dgn



CROSS SECTION
FENCE AT GRADE SEPARATED STRUCTURES
WITHOUT SIDEWALK




CROSS SECTION
FENCE AT GRADE SEPARATED STRUCTURES
WITH SIDEWALK



CROSS SECTION
FENCE AT PEDESTRIAN
GRADE SEPARATED STRUCTURE

NOTES:

1. TRACK, SYSTEMS, STRUCTURES AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. FOR MESH SCREEN REQUIREMENT, SEE OVERHEAD CONTACT SYSTEM AND TRACTION POWER RETURN SYSTEM CHAPTER OF THE DESIGN CRITERIA.
3. EXTEND MESH SCREEN 30 FEET FROM CENTERLINE OF OUTERMOST TRACK, OR 10 FEET BEYOND THE OUTERMOST ENERGIZED CONDUCTOR OR COMPONENT, WHICHEVER IS GREATER.



OVERHEAD STRUCTURE ELEVATION

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
A. ABTAHI
DRAWN BY
V. LAVERDE
CHECKED BY
S. MILITELLO
IN CHARGE
G. LUSHEROVICH
DATE
08/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE


ACCESS DETERRING
FENCING ON GRADE SEPARATED STRUCTURES

CONTRACT NO.	
DRAWING NO.	DD-CV-902
SCALE	NO SCALE
SHEET NO.	

RFP No.: 13-57 – Addendum No. 5 - 10/09/2014



ELEVATION



PLAN

NOTES:

1. CULVERT STRUCTURE IS SCHEMATIC AND DOES NOT REPRESENT DESIGN.
2. INSTALL GRATE IN THE CULVERT IF REQUIRED BY THREAT AND VULNERABILITY ANALYSIS, USING THE FOLLOWING CRITERIA:
 - A. GRATES SHALL BE INSTALLED UPSTREAM AND DOWNSTREAM OF CULVERT HEADWALLS.
 - B. GRATES SHALL HAVE BARS SPACED 6 INCHES APART AND SHALL BE DESIGNED TO WITHSTAND MAXIMUM IMPACT FROM LARGEST EXPECTED FLOATING DEBRIS.
 - C. THE MAXIMUM DISTANCE FROM THE BOTTOM OF THE GRATE TO THE BOTTOM AND SIDE SLOPES OF THE WATERWAY CROSSING SHALL BE 6 INCHES.
 - D. THE MINIMUM HEIGHT OF THE GRATES SHALL BE SUCH THAT IT RESTRICTS ACCESS DURING ALL CONDITIONS (DRY, HIGH WATER, ETC).
 - E. GRATE INSTALLATIONS SHALL BE COORDINATED WITH THE HYDRAULIC ENGINEER TO ENSURE PRESERVATION OF THE CULVERT FLOW CAPACITY.
3. INSTALLATION OF GRATES IN DESIGNATED WILDLIFE CORRIDORS ARE SUBJECT TO APPROVAL BY THE APPROPRIATE REGULATORY AGENCY.

3/28/2014 5:11:43 PM CAHSR.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32166\DD-CV-903.dgn mincio

REV	DATE	BY	CHK	APP	DESCRIPTION


DESIGNED BY
S. MILITELLO
 DRAWN BY
V. HUANTE
 CHECKED BY
A. ABTAHI
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE
 FENCE AT CULVERT CROSSINGS


CONTRACT NO.
DRAWING NO. DD-CV-903
SCALE NO SCALE
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57



NEW STRUCTURE OVER HST TRACKS

	HEIGHT "A"	HEIGHT "B"	MIN VERTICAL CLEARANCE
DEDICATED HST TRACK	17'-5"	8'-3"	27'-0"
SHARED USE TRACK	18'-9"	6'-11"	27'-0"




EXISTING STRUCTURE OVER HST TRACKS

	HEIGHT "A"	HEIGHT "B"	MIN VERTICAL CLEARANCE
DEDICATED HST TRACK	17'-5"	8'-3"	27'-0"
DEDICATED HST TRACK (V ≤ 125 MPH)	17'-5"	5'-3"	24'-0"*
SHARED USE TRACK	18'-9"	4'-0"	24'-6"***

* SEE NOTE 4
 *** PER CALTRAIN


NOTES:

- TOLERANCES ARE NOT ADDITIVE FOR INCREMENTAL DISTANCES.
- HST TRACKFORM IS SCHEMATIC AND DOES NOT REPRESENT THE DESIGN.
- AT LOCATIONS WHERE SUPERELEVATION IS PRESENT, VERTICAL CLEARANCES SHALL BE MEASURED FROM THE HIGH RAIL.
- DEFINED CLEARANCES ASSUMES GRADE SEPARATED STRUCTURE LENGTH ALONG TRACK IS NO MORE THAN 160 FEET FOR HST TRACK OVER 125 MPH. THE OCS SHALL BE FREE RUNNING UNDER GRADE SEPARATED STRUCTURES WITH NO SUPPORTS. STRUCTURES WIDER THAN 160 FEET REQUIRE FURTHER APPROVAL.
- PROTECTIVE PANEL IS REQUIRED FOR VERTICAL CLEARANCES LESS THAN THE PANTOGRAPH ZONE HEIGHT (26 FEET - 3 INCHES) FOR STRUCTURES OVER HST TRACKS.
- FOR LOCAL ROADWAYS, 15 FEET MINIMUM VERTICAL CLEARANCE SHALL BE CONFIRMED BY AGENCY HAVING JURISDICTION.
- PROTECTIVE STRUCTURE IS REQUIRED IF SIDE CLEARANCE IS LESS THAN 25 FEET. SEE THE AREMA MANUAL FOR RAILWAY ENGINEERING FOR PIER PROTECTION REQUIREMENTS.
- PROTECTIVE TRAFFIC BARRIER REQUIREMENTS SHALL BE CONFIRMED BY AGENCY HAVING JURISDICTION.
- SIDE CLEARANCE DESIGN CRITERIA SHALL BE CONFIRMED BY AGENCY HAVING JURISDICTION.



NEW HST STRUCTURE OVER TRACK



	MIN VERTICAL CLEARANCE
FREIGHT TRACKS	
BNSF	23'-4"
UPRR	23'-0"
NON-FREIGHT TRACKS	
METROLINK	24'-0"
CALTRAIN	24'-6"



NEW HST STRUCTURE OVER ROADWAY

	MIN VERTICAL CLEARANCE
FREEWAY/EXPRESSWAY	16'-6"
LOCAL ROADWAY	15'-0" *
EXTRA LEGAL LOAD NETWORK(ELLN)	20'-3"

* SEE NOTE 6



	MIN SIDE CLEARANCE
FREEWAY/EXPRESSWAY	30'-0"
OTHER	SEE NOTE 9

c:\projectwise\pb\projectwise\int\m\incio\dms32166\DD-CV-904.dgn
 CAHSR.tbl CAHSR_half_black.plt
 3/28/2014 5:17:45 PM
 m\incio

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION


DESIGNED BY S. MILITELLO
DRAWN BY V. HUANTE
CHECKED BY H. NGUYEN
IN CHARGE G. LUSHEROVICH
DATE 01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE
 MINIMUM CLEARANCE
 GRADE SEPARATED STRUCTURES

CONTRACT NO.
DRAWING NO. DD-CV-904
SCALE NO SCALE
SHEET NO.


c:\projectwise\pb\projectwise\int\m\incio\dms32166\DD-CV-905.dgn
 CHSR_half_black.plt
 CAHSRP.tbl
 3/28/2014 11:13:31 AM
 m\incio




TYPICAL 22 FT ROADWAY SECTION-PAVED
CLOSED DRAINAGE




TYPICAL 22 FT ROADWAY SECTION-PAVED
OPEN DRAINAGE




AUTHORITY ROADWAYS WIDTH




TYPICAL 22 FT ROADWAY SECTION-UNPAVED
CLOSED DRAINAGE



TYPICAL 22 FT ROADWAY SECTION-UNPAVED
OPEN DRAINAGE



PAVEMENT CONNECTION DETAIL
SCALE: 1"=1'-0"



- NOTES:**
1. AUTHORITY ROADWAYS ARE REFERRED TO AS ACCESS ROADS AND SERVICE ROADS.
 2. UNPAVED ROADWAYS CAN BE USED AS TEMPORARY ACCESS TO SITES.
 3. REFER TO CALTRANS STANDARD PLANS FOR:
 - A) CURBS AND DRIVEWAYS (A87A)
 - B) UNDERDRAINS (D102)
 4. IF FIRE HYDRANT IS LOCATED ON ROAD, MINIMUM ROADWAY WIDTH SHALL BE 26 FEET.
 5. TWO-WAY SERVICE ROADS SHALL BE 24 FEET WIDE WITH NO SHOULDERS.
 6. COMPACT SUBGRADE TO 95% COMPACTION.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
S. MILITELLO
 DRAWN BY
V. HUANTE
 CHECKED BY
A. ABTAHI
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
CIVIL DIRECTIVE
 AUTHORITY ROADWAYS

CONTRACT NO.
 DRAWING NO.
DD-CV-905
 SCALE
AS SHOWN
 SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

California High-Speed Rail Authority




RFP No.: HSR 13-57

**Request for Proposals for Design-Build
Services for Construction Package 2-3**


**Book II, Part B.1
Directive Drawings**

Drainage

5/21/2014 5:05:36 PM CAHSRP.tbl CAHSRP_PDF_half_black.plt c:\projectwise\pb\projectwise\int\averdev\dms32168\DD-CD-003.dgn




TYPICAL SECTION
AT GRADE TRACK OPEN DRAINAGE SYSTEM



TYPICAL SECTION
AT GRADE TRACK CLOSED DRAINAGE SYSTEM

NOTES:

1. TRACK AND SYSTEMS ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. THE CONTROL POINT (CP) IS THE INTERSECTION OF THE CENTERLINE OF TRACK AND THE TOP OF THE RAIL, FOR SUPERELEVATED TRACK SECTIONS THE CP IS THE INTERSECTION OF THE CENTERLINE OF THE TRACK AND THE TOP OF THE LOW RAIL.
3. TRACK DRAINAGE SYSTEM SHALL BE CONNECTED AND DISCHARGE TO THE LOCAL STORM DRAIN SYSTEM.
4. DITCH SHALL CONFORM TO THE FOLLOWING REQUIREMENTS:
DEPTH OF DITCH = 1' MINIMUM
SIDE SLOPE =
2:1 MAXIMUM FOR CONCRETE LINED DITCH AND
3:1 MAXIMUM FOR GRASS LINED DITCH
WIDTH OF FLAT BOTTOM = 4' MINIMUM



DETAIL 1
NO SCALE

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
K. SISTLA
DRAWN BY
V. HUANTE
CHECKED BY
A. ABTAHI
IN CHARGE
G. LUSHEROVICH
DATE
05/09/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
DRAINAGE DIRECTIVE

AT-GRADE TRACK
DRAINAGE SYSTEM

CONTRACT NO.
DRAWING NO.
DD-CD-003
SCALE
NO SCALE
SHEET NO.

RFP No.: 13-57 – Addendum No. 1 - 05/30/2014

3/28/2014 11:20:42 AM CAHSR.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32168\DD-CD-010.dgn



- NOTES:**
1. TRACK, SYSTEMS AND STRUCTURES ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. CLEANOUTS AND PIPE PENETRATIONS FROM THE COLUMNS SHALL BE OUTSIDE OF THE PLASTIC HINGE ZONE.



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
K. SISTLA
DRAWN BY
V. HUANTE
CHECKED BY
A. ABTAHI
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
DRAINAGE DIRECTIVE

ELEVATED STATION PLATFORM
DRAINAGE SYSTEM


CONTRACT NO.
DRAWING NO.
DD-CD-010
SCALE
AS SHOWN
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57


3/28/2014 11:21:48 AM CAHSR.tbl CAHSR.tbl c:\projectwise\pb\projectwise\int\mincio\dms32168\DD-CD-900.dgn




PLAN
DRAINAGE INLET ON AERIAL STRUCTURE DECK




DETAIL 1
8" Ø GRATE (SEE NOTE 1)



DETAIL 2
VERTICAL INLET



SECTION A
DRAINAGE INLET



DETAIL 3
45° ANGLE INLET

NOTES:
1. DRAIN GRATES SHALL BE SECURELY CONNECTED TO THE INLET.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
K. SISTLA
DRAWN BY
V. HUANTE
CHECKED BY
A. ABTAHI
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014

**PARSONS
BRINCKERHOFF**




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
DRAINAGE DIRECTIVE**
NON-BALLASTED AERIAL STRUCTURE BRIDGE DECK
DRAINAGE INLET DETAIL

CONTRACT NO.
DRAWING NO.
DD-CD-900
SCALE
NO SCALE
SHEET NO.


04/02/2014 - RFP No.: HSR 13-57

NOTES:

1. TRACK, SYSTEMS AND STRUCTURES ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. FOR DRAINAGE SYSTEM DETAILS SEE DD-CD-001.
3. THE 8" HALF CIRCLE PERFORATED PIPE SHALL BE INSTALLED ALONG THE ENTIRE INVERTED CROWN OF THE BRIDGE DECK, EXCEPT AT THE EXPANSION JOINT.



1
- **DRAIN DETAIL**
ON CONCRETE DECK



2
- **EXPANSION JOINT DETAIL**
ON BALLASTED AERIAL STRUCTURE

c:\projectwise\pb\projectwise\int\m\incio\dms32168\DD-CD-901.dgn
 3/28/2014 11:22:32 AM CAHSRP.tbl CHSR_half_black.plt
 m\incio

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
A. ABTAHI
 DRAWN BY
V. HUANTE
 CHECKED BY
H. NGUYEN
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
DRAINAGE DIRECTIVE
 BALLASTED AERIAL STRUCTURE
 DECK DRAINAGE SYSTEM DETAILS

CONTRACT NO.	13259
DRAWING NO.	DD-CD-901
SCALE	NO SCALE
SHEET NO.	

04/02/2014 - RFP No.: HSR 13-57

California High-Speed Rail Authority




RFP No.: HSR 13-57

**Request for Proposals for Design-Build
Services for Construction Package 2-3**

**Book III, Part B.1
Directive Drawings**

Utility



- NOTES:**
1. TRACK, SYSTEMS, DRAINAGE, AND STRUCTURES ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. FOR ADDITIONAL REQUIREMENTS, SEE AREMA MANUAL.
 3. SHUTOFF VALVE MUST BE ACCESSIBLE FROM OUTSIDE THE RIGHT OF WAY. IT MAY NOT BE REQUIRED ON BOTH SIDES.
 4. THE CASING SHALL CONTINUE 3'-0" BEYOND THE RIGHT OF WAY.
 5. TRANSVERSE UTILITIES SHALL BE LOCATED AWAY FROM MANHOLES, OCS FOOTINGS, AND OTHER HST SUBSURFACE ELEMENTS.
 6. MINIMUM CLEARANCE FOR GAS TRANSMISSION PIPELINE CROSSING SHALL BE 10'-6" BELOW TOP OF RAIL.
 7. MINIMUM CLEARANCE FOR UNDERGROUND WIRE LINE CROSSING, OVER 750 VOLTS, SHALL BE 4'-0" AND FOR GAS TRANSMISSION PIPELINE CROSSING SHALL BE 6'-0" BELOW DRAINAGE FACILITIES.
 8. UTILITY MARKER TO INDICATE LOCATION OF UTILITY CROSSING AT RIGHT-OF-WAY.

3/28/2014 11:52:47 AM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\m\incio\dms32170\DD-UT-001.dgn

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
A. ABTAHI
 DRAWN BY
V. HUANTE
 CHECKED BY
H. NGUYEN
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
UTILITIES DIRECTIVE
 UTILITY CROSSING CLEARANCES
 AT GRADE

CONTRACT NO.
DRAWING NO. DD-UT-001
SCALE NO SCALE
SHEET NO.

NOTES:

1. TRACK, SYSTEMS, DRAINAGE, AND STRUCTURES ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. NO UTILITIES ABOVE THE WALL FOOTINGS.
3. FOR ADDITIONAL REQUIREMENTS, SEE AREMA MANUAL.
4. TRANSVERSE UTILITIES SHALL BE LOCATED AWAY FROM MANHOLES, OCS FOOTINGS, AND OTHER HST SUBSURFACE ELEMENTS.



3/28/2014 11:53:57 AM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32170\DD-UT-002.dgn

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
A. ABTAHI
 DRAWN BY
V. HUANTE
 CHECKED BY
H. NGUYEN
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
UTILITIES DIRECTIVE
 UTILITIES CROSSING CLEARANCES
 RETAINED CUT TRENCH

CONTRACT NO.
 DRAWING NO.
DD-UT-002
 SCALE
NO SCALE
 SHEET NO.

^{VC} **California High-Speed Rail Authority**




RFP No.: HSR 13-57

**Request for Proposals for Design-Build
Services for Construction Package 2-3**


**Book II, Part B.1
Directive Drawings**

Intrusion Protection

5/22/2014 4:02:18 PM CAHSRP.tbl CHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\averdev\dms32164\DD-IP-100.dgn



TYPICAL SECTION
102' LATERAL SEPARATION
NO INTRUSION PROTECTION REQUIRED



TYPICAL SECTION
MINIMUM 10' HIGH HST EMBANKMENT
NO INTRUSION PROTECTION REQUIRED

NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. AR FENCE AND ITS FOUNDATION SHALL BE INSTALLED INSIDE AUTHORITY RIGHT-OF-WAY.
3. FOR COMMON EMBANKMENT FILL ONLY, USE 2:1 SIDE SLOPES.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
A. ABTAHI
DRAWN BY
V. HUANTE
CHECKED BY
H. NGUYEN
IN CHARGE
G. LUSHEROVICH
DATE
05/09/2014




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
INTRUSION PROTECTION DIRECTIVE**

RAILROAD ADJACENT TO HST
AT-GRADE WITHOUT INTRUSION PROTECTION


CONTRACT NO.
DRAWING NO.
DD-IP-100
SCALE
NO SCALE
SHEET NO.

RFP No.: 13-57 – Addendum No. 1 - 05/30/2014


5/21/2014 4:45:16 PM CAHSRP.tbl CAHSRP_PDF_half_black.plt c:\projectwise\pb\projectwise\int\laverdev\dms32164\DD-IP-101.dgn



TYPICAL SECTION
EARTHEN BERM OR DITCH



TYPICAL SECTION
EARTHEN BERM AND DITCH



TYPICAL SECTION
CONCRETE WALL BARRIER

- NOTES:**
1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. SIDE SLOPES (S:1) DETERMINED THROUGH SLOPE STABILITY ANALYSIS. FOR COMMON EMBANKMENT FILL ONLY, USE 2:1 SIDE SLOPES.
 3. MINIMUM DISTANCE IS BASED ON S=1.
 4. MINIMUM DISTANCE CONSIDERS A MINIMUM OF 3'-6" HIGH EMBANKMENT, INCLUSIVE OF SUBBALLAST.
 5. BERM MATERIAL AND COMPACTION SHALL BE SIMILAR TO EMBANKMENT.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
A. ABTAHI
DRAWN BY
V. HUANTE
CHECKED BY
H. NGUYEN
IN CHARGE
G. LUSHEROVICH
DATE
05/09/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
INTRUSION PROTECTION DIRECTIVE


RAILROAD ADJACENT TO HST
AT-GRADE WITH INTRUSION PROTECTION

CONTRACT NO.
DRAWING NO.
DD-IP-101
SCALE
NO SCALE
SHEET NO.


RFP No.: 13-57 – Addendum No. 1 - 05/30/2014



PLAN



ELEVATION



HST STRUCTURE PIER - PROTECTION WALL

CLEARANCE (D)	WALL HEIGHT ABOVE TOP OF RAIL (H)
≥ 25 FT	N/A
12 FT - 25 FT	6 FT
≤ 12 FT	12 FT

NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. PIER PROTECTION WALL IS REQUIRED IF CLEARANCE FROM FACE OF HST STRUCTURE TO NEAREST RAILROAD TRACK CENTERLINE IS LESS THAN 25'-0".
3. LOCATION WHERE PIER PROTECTION WALL IS REQUIRED SHALL BE DETERMINED THROUGH SITE SPECIFIC HAZARD ANALYSES.

c:\projectwise\pb\projectwise\int\m\incio\dms32164\DD-IP-102.dgn
 CHSR_half_black.plt
 CAHSRP.tbl
 3/30/2014 11:31:13 AM
 m\incio

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY A. ABTAHI
DRAWN BY V. HUANTE
CHECKED BY H. NGUYEN
IN CHARGE G. LUSHEROVICH
DATE 01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
INTRUSION PROTECTION DIRECTIVE

 HST PIER PROTECTION
 IN RAILROAD RIGHT OF WAY

CONTRACT NO.
DRAWING NO. DD-IP-102
SCALE NO SCALE
SHEET NO.


c:\projectwise\pb\projectwise\int\m\incio\dms32164\DD-IP-103.dgn
 CHSR_half_black.plt
 CAHSRP.tbl
 3/30/2014 11:31:58 AM
 m\incio




HST AT GRADE ADJACENT TO HIGHWAY/ROADWAY

NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. WHEN HST CORRIDOR IS CONSTRUCTED LONGITUDINALLY TO A FREEWAY, EXPRESSWAY, OR HIGHWAY, METAL BEAM GUARDRAIL OR CONCRETE BARRIER SHALL BE REQUIRED AT HST FIXED OBJECT IF THE DISTANCE FROM ULTIMATE ETW TO HST AERIAL STRUCTURE COLUMN, OR ANY HST FIXED OBJECT IS LESS THAN 52'-0". IF HST CORRIDOR IS NOT LONGITUDINAL TO A FREEWAY, EXPRESSWAY, OR HIGHWAY, THE CLEARANCE REQUIREMENT TO A HST FIXED OBJECT IS 30'-0".
3. IF HEIGHT DIFFERENTIAL AT ROADWAY CUT SLOPE HINGE POINT AND HST ROW FENCE IS GREATER THAN 7'-0", NO GUARDRAIL OR CONCRETE BARRIER IS REQUIRED.
4. IF THE HEIGHT DIFFERENTIAL AT ROADWAY FILL HINGE POINT AND HST ROW FENCE IS GREATER THAN 10'-0", GUARDRAIL WILL BE REQUIRED AT ROADWAY FILL HINGE POINT.
5. IF THE VERTICAL CLEARANCE BETWEEN THE RECOVERY AREA AND THE HST STRUCTURE BENT CAP IS LESS THAN 16'-6", METAL BEAM GUARDRAIL OR CONCRETE BARRIER WILL BE REQUIRED 3'-0" FROM EDGE OF HST BENT CAP.



HST AERIAL STRUCTURE ADJACENT TO HIGHWAY/ROADWAY



HST AT GRADE ADJACENT TO HIGHWAY/ROADWAY WITH 10 FEET CLEAR RECOVERY ZONE (CRZ)

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
A. ABTAHI
 DRAWN BY
V. HUANTE
 CHECKED BY
H. NGUYEN
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
INTRUSION PROTECTION DIRECTIVE


 HST ADJACENT TO HIGHWAY/ROADWAY

CONTRACT NO.
DRAWING NO. DD-IP-103
SCALE NO SCALE
SHEET NO.

9/30/2014 11:29:32 AM CAHSR.tbl CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\laverdev\dms32164\DD-IP-104.dgn



HIGHWAY/ROADWAY AT GRADE ADJACENT TO HST TRENCH



HIGHWAY/ROADWAY AT GRADE ADJACENT TO HST RETAINED FILL

- NOTES:**
1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. IF THE DISTANCE BETWEEN HST WALL AND THE ULTIMATE ETW IS LESS THAN 52'-0", THE WALL HEIGHT SHALL BE 7'-6" ABOVE THE GROUND SURFACE AND CALTRANS CONCRETE BARRIER TYPE 60D SHALL BE INCLUDED IN CONSTRUCTION OF THE WALL.
 3. FOR CONCRETE BARRIER TYPE AND THE END TREATMENT OF THE CONCRETE BARRIER REFER TO CHAPTER 7 OF CALTRANS TRAFFIC MANUAL AND CALTRANS STANDARD PLANS.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
A. ABTAHI
DRAWN BY
V. HUANTE
CHECKED BY
H. NGUYEN
IN CHARGE
G. LUSHEROVICH
DATE
08/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
INTRUSION PROTECTION DIRECTIVE
HST TRENCH AND RETAINING WALL PROTECTION



CONTRACT NO.
DRAWING NO.
DD-IP-104
SCALE
NO SCALE
SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

9/30/2014 11:30:51 AM CAHSR.tbl CAHSR.plt c:\projectwise\bb\projectwise\nt\laverdev\dms32164\DD-IP-105.dgn

NOTES:

1. METAL BEAM GUARDRAIL OR CONCRETE BARRIER SHALL BE REQUIRED AT HST FIXED OBJECT IF THE DISTANCE FROM ULTIMATE ETW TO HST FIXED OBJECT IS LESS THAN 30'-0". REFER TO CHAPTER 7 OF CALTRANS TRAFFIC MANUAL AND CALTRANS STANDARD PLANS.



HST GRADE SEPARATED STRUCTURE OVER HIGHWAY/ROADWAY WITH MEDIAN

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
A. ABTAHI
DRAWN BY
V. HUANTE
CHECKED BY
H. NGUYEN
IN CHARGE
G. LUSHEROVICH
DATE
08/29/2014



**CALIFORNIA HIGH-SPEED TRAIN PROJECT
INTRUSION PROTECTION DIRECTIVE**

HST PIER PROTECTION
IN HIGHWAY/ROADWAY RIGHT-OF-WAY

CONTRACT NO.
DRAWING NO. DD-IP-105
SCALE NO SCALE
SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

California High-Speed Rail Authority



RFP No.: HSR 13-57


**Request for Proposals for Design-Build
Services for Construction Package 2-3**

**Book II, Part B.1
Directive Drawings**

Structure

NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. ON CURVED ALIGNMENT, THE RELATIVE DIMENSIONS BETWEEN BRIDGE DECK AND BOX GIRDER SHALL BE ADJUSTED PROPERLY. IF A STRAIGHT DECK EDGE IS SELECTED, THE WIDER DECK WIDTH MAY BE REQUIRED.
3. THE HEIGHT OF SOUND WALLS SHALL BE AS DEFINED IN THE TABLE 12-1 OF THE DESIGN CRITERIA. THE STRUCTURE AND CONNECTION BETWEEN PARAPET AND STRUCTURE DECK SHALL BE DESIGNED TO RESIST THE LOAD COMBINATIONS AS DESCRIBED IN TABLE 12-4 OF THE DESIGN CRITERIA TO ACCOMMODATE INSTALLATION OF SOUND WALLS. NO LONGITUDINAL GAPS SHALL BE PERMITTED BETWEEN THE BOTTOM OF SOUND WALL AND THE PARAPET OR DECK, NOR ANY VERTICAL GAPS BETWEEN ADJACENT SOUND WALL PANELS.
4. THE DIRECT FIXATION RAIL SYSTEM AND THE TRACK SLAB SHOWN ARE FOR ILLUSTRATION ONLY. THE CONTRACTOR SHALL DESIGN AND INSTALL SHEAR REINFORCEMENTS OR CONNECTORS, WHICH ARE CAPABLE OF TRANSFERRING THE TRACTION OR BRAKING FORCES AS DESCRIBED IN THE STRUCTURES CHAPTER OF THE DESIGN CRITERIA, IN THE STRUCTURAL DECK BELOW THE TRACK SLAB IN ACCORDANCE WITH THE PROVISIONS PROVIDED BY THE TRACK WORK DESIGNER THROUGH SYSTEM INTERFACE WORKSHOP MEETINGS. THE TOP SURFACE OF STRUCTURAL DECK BELOW THE TRACK SLAB SHALL BE PROPERLY ROUGHENED BY THE CONTRACTOR. SHEAR REINFORCEMENTS OR CONNECTORS SHALL BE HOT-DIP GALVANIZED. THE DESIGN AND INSTALLATION OF SHEAR REINFORCEMENTS OR CONNECTORS SHALL BE CONSIDERED AS PART OF THE CONTRACTOR'S SCOPE OF WORK.
5. FOR BALLASTED STRUCTURES, THE DESIGN DEPTH FROM TOP OF RAIL TO THE STRUCTURE DECK OR INVERT SHALL BE SET EQUAL TO 2'-9" PLUS ALLOWANCE FOR WATER PROOFING MEMBRANE AND PROTECTION LAYER.



SEE STRUCTURAL DRAWING "AERIAL STRUCTURE CONCRETE PARAPET" FOR CONCRETE PARAPET DETAILS

SEE STRUCTURAL DRAWING "AERIAL STRUCTURE CABLE TROUGH DETAILS AT OCS POLE" FOR OCS POLE FOUNDATION DETAILS

SEE STRUCTURAL DRAWING "AERIAL STRUCTURE TYPICAL CABLE TROUGH DETAILS" FOR TYPICAL CABLE TROUGH DETAILS


SEE DRAINAGE DRAWING "NON-BALLASTED AERIAL STRUCTURE BRIDGE DECK DRAINAGE SYSTEM" FOR BRIDGE DECK DRAINAGE SYSTEM

CABLE TROUGH SECTION CUT NOT AT OCS POLE

CABLE TROUGH SECTION CUT AT OCS POLE

FOR TANGENT TRACK

FOR SUPERELEVATED TRACK



7/30/2014 11:40:27 AM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\m\incio\dms32172\DD-ST-100.dgn

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
P. LIN
DRAWN BY
V. HUANTE
CHECKED BY
K. PUGASAP
IN CHARGE
G. LUSHEROVICH
DATE
07/18/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE
TYPICAL CROSS SECTION
AERIAL STRUCTURE
TWO TRACK NON-BALLASTED
TYPICAL CONFIGURATION ON TOP OF DECK


CONTRACT NO.
DRAWING NO.
DD-ST-100
SCALE
AS SHOWN
SHEET NO.

RFP No.: 13-57 - Addendum No. 3 - 07/31/2014

8/1/2014 10:17:31 AM CAHSR-AD-TBCHSR_half_black.plt c:\projectwise\pb\projectwise\int\m\incio\dms32172\DD-ST-101.dgn



- NOTES:**
1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. ON CURVED ALIGNMENT, THE RELATIVE DIMENSIONS BETWEEN BRIDGE DECK AND BOX GIRDER SHALL BE ADJUSTED PROPERLY. IF A STRAIGHT DECK EDGE IS SELECTED, THE WIDER DECK WIDTH MAY BE REQUIRED.
 3. THE HEIGHT OF SOUND WALLS SHALL BE AS DEFINED IN THE TABLE 12-1 OF THE DESIGN CRITERIA. THE STRUCTURE AND CONNECTION BETWEEN PARAPET AND STRUCTURE DECK SHALL BE DESIGNED TO RESIST THE LOAD COMBINATIONS AS DESCRIBED IN TABLE 12-4 OF THE DESIGN CRITERIA TO ACCOMMODATE INSTALLATION OF SOUND WALLS. NO LONGITUDINAL GAPS SHALL BE PERMITTED BETWEEN THE BOTTOM OF SOUND WALL AND THE PARAPET OR DECK, NOR ANY VERTICAL GAPS BETWEEN ADJACENT SOUND WALL PANELS.
 4. THE DIRECT FIXATION RAIL SYSTEM AND THE TRACK SLAB SHOWN ARE FOR ILLUSTRATION ONLY. THE CONTRACTOR SHALL DESIGN AND INSTALL SHEAR REINFORCEMENTS OR CONNECTORS, WHICH ARE CAPABLE OF TRANSFERRING THE TRACTION OR BRAKING FORCES AS DESCRIBED IN THE STRUCTURES CHAPTER OF THE DESIGN CRITERIA, IN THE STRUCTURAL DECK BELOW THE TRACK SLAB IN ACCORDANCE WITH THE PROVISIONS PROVIDED BY THE TRACK WORK DESIGNER THROUGH SYSTEM INTERFACE WORKSHOP MEETINGS. THE TOP SURFACE OF STRUCTURAL DECK BELOW THE TRACK SLAB SHALL BE PROPERLY ROUGHENED BY THE CONTRACTOR. SHEAR REINFORCEMENTS OR CONNECTORS SHALL BE HOT-DIP GALVANIZED. THE DESIGN AND INSTALLATION OF SHEAR REINFORCEMENTS OR CONNECTORS SHALL BE CONSIDERED AS PART OF THE CONTRACTOR'S SCOPE OF WORK.
 5. FOR BALLASTED STRUCTURES, THE DESIGN DEPTH FROM TOP OF RAIL TO THE STRUCTURE DECK OR INVERT SHALL BE SET EQUAL TO 2'-9" PLUS ALLOWANCE FOR WATER PROOFING MEMBRANE AND PROTECTION LAYER.



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
P. LIN
 DRAWN BY
V. HUANTE
 CHECKED BY
K. PUGASAP
 IN CHARGE
G. LUSHEROVICH
 DATE
07/18/2014





CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE
 TYPICAL CROSS SECTION
 AERIAL STRUCTURE
 ONE TRACK NON-BALLASTED
 TYPICAL CONFIGURATION ON TOP OF DECK


CONTRACT NO.
 DRAWING NO.
DD-ST-101
 SCALE
AS SHOWN
 SHEET NO.

RFP No.: 13-57 – Addendum No. 3 - 07/31/2014

8/1/2014 10:22:04 AM CAHSR-AD-TBCHSR_half_black.plt c:\projectwise\pb\projectwise\int\m\incio\dms32172\DD-ST-102.dgn



- NOTES:**
1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. ON CURVED ALIGNMENT, THE RELATIVE DIMENSIONS BETWEEN BRIDGE DECK AND BOX GIRDER SHALL BE ADJUSTED PROPERLY. IF A STRAIGHT DECK EDGE IS SELECTED, THE WIDER DECK WIDTH MAY BE REQUIRED.
 3. THE HEIGHT OF SOUND WALLS SHALL BE AS DEFINED IN THE TABLE 12-1 OF THE DESIGN CRITERIA. THE STRUCTURE AND CONNECTION BETWEEN PARAPET AND STRUCTURE DECK SHALL BE DESIGNED TO RESIST THE LOAD COMBINATIONS AS DESCRIBED IN TABLE 12-4 OF THE DESIGN CRITERIA TO ACCOMMODATE INSTALLATION OF SOUND WALLS. NO LONGITUDINAL GAPS SHALL BE PERMITTED BETWEEN THE BOTTOM OF SOUND WALL AND THE PARAPET OR DECK, NOR ANY VERTICAL GAPS BETWEEN ADJACENT SOUND WALL PANELS.
 4. CONCRETE TIES SHOWN ARE FOR ILLUSTRATION ONLY.
 5. FOR BALLASTED STRUCTURES, THE DESIGN DEPTH FROM TOP OF RAIL TO THE STRUCTURE DECK OR INVERT SHALL BE SET EQUAL TO 2'-9" PLUS ALLOWANCE FOR WATER PROOFING MEMBRANE AND PROTECTION LAYER.



1
-
WATERPROOFING SYSTEM
ON CONCRETE DECK

REV	DATE	BY	CHK	APP	DESCRIPTION


DESIGNED BY
P. LIN
 DRAWN BY
V. HUANTE
 CHECKED BY
G. HARRIS
 IN CHARGE
G. LUSHEROVICH
 DATE
07/18/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE
 TYPICAL CROSS SECTION
 AERIAL STRUCTURE
 TWO TRACK BALLASTED
 TYPICAL CONFIGURATION ON TOP OF DECK

CONTRACT NO.
 DRAWING NO.
DD-ST-102
 SCALE
NO SCALE
 SHEET NO.

RFP No.: 13-57 – Addendum No. 3 - 07/31/2014




CABLE TROUGH PLAN
SCALE: 1"=1'-0"



SECTION A
SCALE: 1"=1'-0"

NOTES:


1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. THE CABLE TROUGH DETAIL IS FOR STANDARD TWO TRACK. FOR CABLE TROUGH INFORMATION IN SPECIAL TRACK AREA, THE CONTRACTOR SHALL COORDINATE WITH THE INTERFACED TRACK WORK DESIGNER FOR DETAILED INFORMATION.



DETAIL 1
SCALE: 1/2"=1'-0"

	NON-BALLASTED TRACK		BALLASTED TRACK	
	TWO TRACK	ONE TRACK	TWO TRACK	ONE TRACK
A	3'-1/2"	3'-3 3/16"	3'-3 1/2" + T*	3'-6 3/16" + T*
B	2'-11 1/8"	3'-2 1/4"	2'-2 1/8" + T*	3'-5 1/4" + T*

T* = SUM OF WATERPROOFING MEMBRANE THICKNESS AND PROTECTION LAYER THICKNESS



SECTION B
SCALE: 1/2"=1'-0"

3/30/2014 11:38:40 AM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32172\DD-ST-900.dgn

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
P. LIN
DRAWN BY
V. HUANTE
CHECKED BY
K. PUGASAP
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE

AERIAL STRUCTURE
TYPICAL CABLE TROUGH DETAILS


CONTRACT NO.
DRAWING NO.
DD-ST-900
SCALE
AS SHOWN
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57


9/30/2014 11:45:08 AM CAHSR.tbl CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\laverdev\dms32172\DD-ST-901.dgn




PRECAST CABLE TROUGH PLAN
SCALE: 1"=1'-0"




DETAIL 1
SCALE: 1/2"=1'-0"



SECTION A
SCALE: 1"=1'-0"



SECTION B
SCALE: 1/2"=1'-0"



DETAIL 2
SCALE: 1"=1'-0"

NOTES:

- CONTRACTOR SHALL DETERMINE WORK SEGMENT LENGTH BASED ON CONSTRUCTION METHOD.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
B. VALENTI
DRAWN BY
V. LAVERDE
CHECKED BY
P. LIN
IN CHARGE
G. LUSHEROVICH
DATE
08/29/2014

**PARSONS
BRINCKERHOFF**




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE**

TYPICAL CABLE TROUGH DETAILS
EMBANKMENT/CUT


CONTRACT NO.
DRAWING NO.
DD-ST-901
SCALE
AS SHOWN
SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014


3/30/2014 11:40:10 AM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32172\DD-ST-902.dgn




CABLE TROUGH PLAN AND CONDUIT DETAIL
SCALE: 1"=1'-0"



SECTION A
SCALE: 1"=1'-0"



DETAIL 1
SCALE: 1/2"=1'-0"



SECTION B
SCALE: 1/2"=1'-0"

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
B. VALENTI
DRAWN BY
V. HUANTE
CHECKED BY
P. LIN
IN CHARGE
J. CHIRCO
DATE
01/24/2014





CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE

CABLE TROUGH DETAILS
TRENCH/CUT AND COVER TUNNEL

CONTRACT NO.
DRAWING NO.
DD-ST-902
SCALE
AS SHOWN
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

3/30/2014 11:40:54 AM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\incio\dms32172\DD-ST-903.dgn



NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. FOR PRECAST COVER DETAIL, SEE DRAWING "AERIAL STRUCTURE TYPICAL CABLE TROUGH DETAILS".
3. SEE STRUCTURAL DRAWING "AERIAL STRUCTURE TYPICAL CABLE TROUGH DETAILS" FOR DIMENSIONS NOT SHOWN.
4. OCS POLE, ANCHOR BOLT ASSEMBLIES, BASE PLATES, AND GROUT PAD FOR OCS POLE FOUNDATION ARE SHOWN FOR ILLUSTRATION ONLY. THE LOCATION OF EMBEDDED PVC SLEEVES AND LOADS FOR DESIGN OF OCS POLE FOUNDATION SHALL CONFORM TO THE REQUIREMENTS IN THE STRUCTURAL CHAPTER OF THE DESIGN CRITERIA.



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
P. LIN
 DRAWN BY
V. HUANTE
 CHECKED BY
K. PUGASAP
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE





 AERIAL STRUCTURE
 CABLE TROUGH DETAILS
 AT OCS POLE

CONTRACT NO.
 DD-ST-903
 SCALE
 AS SHOWN
 SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

3/30/2014 11:41:40 AM CAHSR.tb1 CHSR_half_black.plt c:\projectwise\pb\projectwise\int\m\incio\dms32172\DD-ST-904.dgn

- NOTES:**
- BOTH HORIZONTAL AND VERTICAL TRANSITION OF THE CABLE TROUGH SHALL OCCUR WITHIN THE LONGITUDINAL STRUCTURAL TRANSITION ZONE.
 - SPECIAL TRANSITION TROUGH AND COVER WILL BE REQUIRED AT ANGLE POINTS. MAXIMIZE EXTENT OF STANDARD PIECES.



AERIAL STRUCTURE TO AT-GRADE/EMBANKMENT

TRENCH/CUT AND COVER TUNNEL TO AT-GRADE/EMBANKMENT



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
P. LIN
DRAWN BY
V. HUANTE
CHECKED BY
B. VALENTI
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE**

CABLE TROUGH LAYOUT TRANSITION AREAS


CONTRACT NO.
DRAWING NO.
DD-ST-904
SCALE
AS SHOWN
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

c:\projectwise\pb\projectwise\int\m\incio\dms32172\DD-ST-910.dgn
 CHSR_half_black.plt
 CAHSRP.tbl
 3/30/2014 11:42:59 AM
 m\incio



CONCRETE PARAPET
ELEVATION VIEW



SECTION A-A

NOTES:

1. PARAPETS SHALL BE PROVIDED ALONG EDGES OF AERIAL STRUCTURES, BRIDGES, AND HST GRADE SEPARATIONS.
2. PARAPETS SHALL BE DESIGNED FOR WIND LOADS, SLIPSTREAM EFFECTS, AND OTHER LOADS REQUIRED IN THE STRUCTURES CHAPTER OF THE DESIGN CRITERIA.
3. PARAPETS SHALL BE DESIGNED TO ACCOMMODATE FUTURE INSTALLATION OF SOUND WALLS.
4. AT CONSTRUCTION JOINTS OF CONCRETE PARAPETS, A JOINT WITH FILLER SHALL BE PROVIDED. IN ADDITION, A PARAPET EXPANSION JOINT SHALL BE DESIGNED AND PROVIDED AT EVERY AERIAL STRUCTURE AND BRIDGE EXPANSION JOINT LOCATION. THE INSIDE FACE OF JOINT OPENING SHALL BE COVERED WITH A GALVANIZED STEEL PLATE SECURELY FASTENED TO THE INSIDE FACE OF THE PARAPET ON ONE SIDE OF THE EXPANSION JOINT WITH A LENGTH OF THREE INCHES MORE THAN THE MAXIMUM JOINT MOVEMENT LENGTH.


	NON-BALLASTED TRACK		BALLASTED TRACK	
	TWO TRACK	ONE TRACK	TWO TRACK	ONE TRACK
B	2'-11 ¹ / ₈ "	3'-2 ¹ / ₄ "	3'-2 ¹ / ₈ " + T*	3'-5 ¹ / ₄ " + T*
C	7'-5 ⁵ / ₈ "	7'-8 ¹ / ₄ "	7'-8 ⁵ / ₈ " + T*	7'-11 ¹ / ₄ " + T*

T* = SUM OF WATERPROOFING MEMBRANE THICKNESS AND PROTECTION LAYER THICKNESS



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
P. LIN
 DRAWN BY
V. HUANTE
 CHECKED BY
K. PUGASAP
 IN CHARGE
G. LUSHEROVICH
 DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE

 AERIAL STRUCTURE
 CONCRETE PARAPET


CONTRACT NO.
 DD-ST-910
 DRAWING NO.
 SCALE
 AS SHOWN
 SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

3/30/2014 11:44:00 AM CAHSR.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32172\DD-ST-911.dgn




ELEVATION
CONCRETE PARAPET NOT SHOWN



SECTION
1/2" = 1'-0"

NOTES:

1. THE SHEAR KEY DETAILS SHOWN ARE FOR ILLUSTRATION ONLY. THE CONTRACTOR SHALL DEVELOP A SHEAR KEY SYSTEM THAT CONFORMS TO THE REQUIREMENTS IN THE STRUCTURES CHAPTER OF THE DESIGN CRITERIA.
2. BEARINGS SHALL BE EASILY ACCESSIBLE FOR INSPECTION AND MAINTENANCE. BEARINGS SHALL BE ADJUSTABLE AND REPLACEABLE AT ANYTIME DURING THE LIFE OF STRUCTURES WITHOUT INTERFERENCE TO NORMAL TRAIN OPERATIONS.
3. THE PROCEDURES FOR BEARING REPLACEMENT, INCLUDING THE LOCATIONS OF JACKS AND THE ALLOWED JACKING FORCES SHALL BE SPECIFIED ON THE DRAWINGS.



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY P. LIN
DRAWN BY V. HUANTE
CHECKED BY K. PUGASAP
IN CHARGE G. LUSHEROVICH
DATE 01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE

AERIAL STRUCTURE
TYPICAL SPAN
SHEAR KEY DETAILS

CONTRACT NO.
DRAWING NO. DD-ST-911
SCALE AS SHOWN
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57


3/30/2014 11:44:41 AM CAHSR.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\incio\dms32172\DD-ST-912.dgn




EXPANSION JOINT SECTION

NOTES:


1. THE EXPANSION JOINT DETAILS SHOWN ARE FOR ILLUSTRATION ONLY. THE CONTRACTOR SHALL DEVELOP AN EXPANSION JOINT SYSTEM THAT CONFORMS TO THE REQUIREMENTS IN THE STRUCTURES CHAPTER OF THE DESIGN CRITERIA.
2. THE EXPANSION OPENING BETWEEN THE ENDS OF BRIDGE DECK AND ABUTMENT SHALL ACCOMMODATE THE MOVEMENT RANGE AS SPECIFIED.
3. EXPANSION JOINTS SHALL BE EASILY ACCESSIBLE FOR INSPECTION AND MAINTENANCE. EXPANSION JOINTS SHALL BE REPLACEABLE AT ANYTIME DURING THE LIFE OF STRUCTURES WITHOUT INTERFERENCE TO NORMAL TRAIN OPERATIONS.
4. THE EXPANSION JOINT SHALL BE WATERTIGHT.
5. ALL STRUCTURAL STEEL PLATES SHALL BE GALVANIZED.




SECTION A



SECTION B



SECTION C



DETAIL 1

EXPANSION OPENING
SEE NOTES 2 & 3

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY P. LIN
DRAWN BY V. HUANTE
CHECKED BY K. PUGASAP
IN CHARGE G. LUSHEROVICH
DATE 01/24/2014

**PARSONS
BRINCKERHOFF**



CALIFORNIA
HIGH-SPEED RAIL AUTHORITY


**CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE**

AERIAL STRUCTURE
TYPICAL SPAN
EXPANSION JOINT DETAILS


CONTRACT NO.
DRAWING NO. DD-ST-912
SCALE NO SCALE
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57


3/30/2014 11:45:26 AM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32172\DD-ST-913.dgn




SECTION A
SCALE 1"=40'-0"




SECTION B
SCALE 1"=40'-0"




PLAN
SCALE: 1"=40'-0"




SECTION C
SCALE 1"=5'-0"



SECTION D
SCALE 1"=1'-0"



DETAIL 1
SCALE 1"=1'-0"



STAIR ELEVATION
SCALE: 1"=1'-0"

- NOTES:**
1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. THE STAIRWAY STRUCTURAL SYSTEM SHOWN IS FOR ILLUSTRATION ONLY. THE CONTRACTOR MAY DESIGN AN EQUIVALENT STAIRWAY SYSTEM TO FIT THE SITE CONDITION.
 3. WHERE VERTICAL DISTANCE BETWEEN LANDING EXCEEDS 12'-0", INTERMEDIATE LANDINGS MUST BE PROVIDED.
 4. THE DESIGN OF THE SECURITY FACILITY SHALL MEET THE REQUIREMENTS OF THE EMERGENCY ACCESS/EGRESS POINTS, AS SPECIFIED IN THE SYSTEM SAFETY AND SECURITY CHAPTER OF THE DESIGN CRITERIA.
 5. THE ACCESS ROAD FROM THE GATE OF SECURITY FACILITY TO THE LOCAL ROAD SHALL BE PROVIDED. THE CONTRACTOR SHALL COORDINATE WITH THE PERTINENT AUTHORITIES FOR REQUIRED EASEMENT ALONG THE AERIAL STRUCTURES.
 6. THE CONTRACTOR SHALL CONSIDER THE LOADS DUE TO THE STAIRWAY IN THE DESIGN OF AERIAL STRUCTURES.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
P. LIN
DRAWN BY
V. HUANTE
CHECKED BY
K. PUGASAP
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014





**CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE**

AERIAL STRUCTURE
EMERGENCY EXIT STAIRWAY DETAILS 1





CONTRACT NO.
DRAWING NO.
DD-ST-913
SCALE
AS SHOWN
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

3/30/2014 11:51:16 AM CAHSR.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms32172\DD-ST-914.dgn



- NOTES:**
1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
 2. THE STAIRWAY STRUCTURAL SYSTEM SHOWN IS FOR ILLUSTRATION ONLY. THE CONTRACTOR MAY DESIGN AN EQUIVALENT STAIRWAY SYSTEM TO FIT THE SITE CONDITION.
 3. WHERE VERTICAL DISTANCE BETWEEN LANDING EXCEEDS 12'-0", INTERMEDIATE LANDINGS SHALL BE PROVIDED.
 4. THE DESIGN OF THE SECURITY FACILITY SHALL MEET THE REQUIREMENTS OF THE EMERGENCY ACCESS/EGRESS POINTS, AS SPECIFIED IN THE SYSTEM SAFETY AND SECURITY CHAPTER OF THE DESIGN CRITERIA.
 5. THE ACCESS ROAD FROM THE GATE OF SECURITY FACILITY TO THE LOCAL ROAD SHALL BE PROVIDED. THE CONTRACTOR SHALL COORDINATE WITH THE PERTINENT AUTHORITIES FOR REQUIRED EASEMENT ALONG THE AERIAL STRUCTURES.
 6. THE CONTRACTOR SHALL CONSIDER THE LOADS DUE TO THE STAIRWAY IN THE DESIGN OF AERIAL STRUCTURES.



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
P. LIN
DRAWN BY
V. HUANTE
CHECKED BY
K. PUGASAP
IN CHARGE
G. LUSHEROVICH
DATE
01/24/2014




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE**

AERIAL STRUCTURE
EMERGENCY EXIT STAIRWAY DETAILS 2

CONTRACT NO.
DRAWING NO.
DD-ST-914
SCALE
AS SHOWN
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57


9/30/2014 11:46:22 AM CAHSR_PDF_half_black.plt c:\projectwise\bb\projectwise\int\laverdev\dms32172\DD-ST-920.dgn



RETAINING WALL ELEVATION


NOTES:

- ELEVATION OF TOP OF WALL AND BOTTOM OF FOOTING SHALL BE AS SHOWN ON OTHER CONTRACT DRAWINGS, VALUES OF H ARE DESIGN HEIGHTS ONLY.
- WALL OFFSET SHALL BE DETERMINED BY THE PROJECT STRUCTURAL ENGINEER IN CONSULTATION WITH THE PROJECT GEOTECHNICAL ENGINEER BASED ON THE CONSTRUCTION METHOD AND SEQUENCING AND IN ACCORDANCE WITH PROJECT DESIGN CRITERIA.
- WHEN A RETAINING WALL IS USED AS A CUT WALL (INCLUDING TRENCH WALLS) ALL JOINTS INCLUDING THE WEAKENED PLANE JOINTS SHALL CONTAIN A WATER STOP.




TYPICAL SECTION

PLACE CONCRETE IN TOE AND IN BASE KEY AGAINST UNDISTURBED MATERIAL (NOT REQUIRED WITH PILE FOOTINGS)




TYPICAL WEAKEND PLANE JOINT

(SEE NOTE 3)




TYPICAL EXPANSION JOINT



TYPICAL CONSTRUCTION JOINT

LOCATE AS REQUIRED TO SUITE CONSTRUCTION SEQUENCE



WALL OFFSET VALUES

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
B. VALENTI
DRAWN BY
V. LAVERDE
CHECKED BY
P. LIN
IN CHARGE
G. LUSHEROVICH
DATE
08/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
STRUCTURAL DIRECTIVE

RETAINING WALL
LAYOUT AND DETAILS

CONTRACT NO.	
DRAWING NO.	DD-ST-920
SCALE	NO SCALE
SHEET NO.	

RFP No. 13-57 - Addendum No. 5 - 10/09/2014

California High-Speed Rail Authority



RFP No.: HSR 13-57

**Request for Proposals for Design-Build
Services for Construction Package 2-3**

**Book II, Part B.1
Directive Drawings**

System Overall




DIAGRAM A
AT-GRADE LOW-VOLTAGE UNDERTRACK CONDUIT DUCTBANK, ACCESS ROADS AND GATES AT SYSTEMS SITE




DIAGRAM B
LOW-VOLTAGE UNDERTRACK CONDUIT DUCTBANK AT STATION PLATFORMS




DIAGRAM C
AT-GRADE LOW-VOLTAGE UNDERTRACK AND UNDERGROUND CONDUIT DUCT BANK, 25KV UNDERGROUND CONDUIT DUCT BANK, ACCESS ROADS AND GATES AT SYSTEMS SITE LOCATED AWAY FROM HSR ROW




DIAGRAM D
TRENCH LOW-VOLTAGE UNDERTRACK CONDUIT DUCT BANK AND ACCESS ROADS AND GATES AT SYSTEMS SITE




DIAGRAM E
AT-GRADE LOW-VOLTAGE UNDERTRACK CONDUIT DUCTBANK AT TUNNEL PORTAL SITES




DIAGRAM F
AT-GRADE LOW-VOLTAGE UNDERTRACK CONDUIT DUCTBANK AT O&M FACILITIES UNDIVIDED




DIAGRAM G
AT-GRADE LOW-VOLTAGE UNDERTRACK CONDUIT DUCTBANK AT O&M FACILITIES DIVIDED BY MAINLINE TRACK

NOTES:

1. SYSTEM SITES INCLUDE TRACTION POWER FACILITIES, TRAIN CONTROL HOUSES, STANDALONE RADIO SITES.
2. TYPICALLY THERE ARE FOUR 25KV UNDERGROUND CONDUIT DUCTBANKS AND ACCOMPANYING MANHOLES PER TRACTION POWER SITE.
3. ACCESS ROADS AND ACCESS GATES ARE SHOWN FOR INFORMATION ONLY. CONSULT CIVIL DESIGN CRITERIA AND PRELIMINARY DESIGN PLANS FOR REQUIREMENTS AND DETAILS.
4. SEE TRACTION POWER AND COMMUNICATIONS DRAWINGS FOR DUCTBANK, MANHOLE CROSS SECTIONS, DETAILS AND ELEVATIONS.
5. FOR NUMBERS OF CONDUITS SEE COMMUNICATION DESIGN CRITERIA AND DRAWING "TYPICAL CROSS SECTION SYSTEMS LOW-VOLTAGE CONDUIT DUCTBANK".
6. INTERMEDIATE MANHOLES TO BE INCLUDED BASED UPON APPLICABLE STANDARDS, REGULATIONS AND CODES.

11/19/2013 10:24:35 AM CAHSR_PDF_half_black.plt c:\projects\projectwise\projectwise\int\huante\dms32178\DD-SY-010.dgn Huante

DESIGNED BY	B. BANKS
DRAWN BY	V. HUANTE
CHECKED BY	C. DALOIA
IN CHARGE	R. SCHMEDES
DATE	11/19/2013

REV	DATE	BY	CHK	APP	DESCRIPTION
B	TBD				POST CP01 CONFORMED SET
A	05/31/13				EXECUTION VERSION

PARSONS BRINCKERHOFF




CALIFORNIA HIGH-SPEED TRAIN PROJECT SYSTEMS DIRECTIVE

TYPICAL CIVIL ACCOMMODATIONS FOR SYSTEMS AT SYSTEM SITES, STATIONS, TUNNEL PORTAL FACILITIES AND O&M FACILITIES

CONTRACT NO.	
DRAWING NO.	DD-SY-010
SCALE	NO SCALE
SHEET NO.	

04/02/2014 - RFP No.: HSR 13-57

9/30/2014 11:52:10 AM CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\laverdev\dms32178\DD-SY-030.dgn



PLAN

NOTES:

1. STRUCTURAL DESIGN DETAILS, CABLE TROUGH AND OCS SLEEVES SHOWN HERE ARE SCHEMATIC ONLY.
2. SLEEVE PENETRATION LOCATIONS SHALL BE LOCATED NOMINALLY 10³/₃₂ FROM THE EXPANSION JOINT.
3. SLEEVE PENETRATION LOCATIONS FOR FUTURE CONDUIT PENETRATIONS SHALL BE PROVIDED IN LINE WITH THE OCS POLE FOUNDATIONS.
4. FOR EACH SLEEVE PENETRATION, AREA SHALL BE SIZED TO HOUSE 10 TRADE SIZE 4 CONDUITS.
5. FOR CONDUIT RISER EMBEDMENTS AND PENETRATIONS ON AERIAL STRUCTURE REQUIREMENTS, REFER TO STRUCTURES CHAPTER OF THE DESIGN CRITERIA. PENETRATIONS SHALL BE PLACED AT THE NEAREST 3 COLUMNS TO THE SYSTEMS SITE OR FACILITY AS SHOWN.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
G. SPADAFORE
DRAWN BY
V. LAVERDE
CHECKED BY
B. MCNALLY
IN CHARGE
B. BANKS
DATE
8/29/2014



**CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL DIRECTIVE**

SYSTEMS SITE LOCATION AT AERIAL STRUCTURE
EMBEDMENTS AND KNOCKOUTS

CONTRACT NO.
DRAWING NO.
DD-SY-030
SCALE
NO SCALE
SHEET NO.

California High-Speed Rail Authority




RFP No.: HSR 13-57

**Request for Proposals for Design-Build
Services for Construction Package 2-3**

**Book II, Part B.1
Directive Drawings**

Traction Power

9/30/2014 12:10:37 PM CAHSR.tbl CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\laverdev\dms17831\DD-TP-D101.dgn



- NOTES:**
- INTERNAL DIMENSIONS ARE SHOWN FOR TYPICAL EQUIPMENT SIZES. CLEARANCES AND ACCESSIBILITY FOR OPERATION AND MAINTENANCE OF EQUIPMENT AND CONFORMANCE TO RELEVANT CODES, STANDARDS, AND GUIDELINES, FINAL DIMENSIONS AND CONFIGURATION OF EQUIPMENT TO BE DETERMINED DURING FINAL SYSTEMS DESIGN.
 - THE MAIN GANTRY POSITION SHALL BE PARALLEL TO AND ADJACENT TO THE TRACKWAY.
 - STRAIN GANTRY LOCATED WITHIN THE RIGHT-OF-WAY, SHALL BE PARALLEL TO AND ON THE OPPOSITE SIDE OF THE TRACKS WITH A FOOTPRINT EQUAL TO THAT OF THE MAIN GANTRY.
 - IF THE TRACTION POWER SUBSTATION IS LOCATED AWAY FROM THE TRACKS IN AN UNDESIRABLE CONFIGURATION THE MAIN GANTRY SHALL BE LOCATED AT THE TRACKWAY, PARALLEL TO AND TOWARDS SUBSTATION SIDE OF THE TRACKS. REFER TO CONCEPTUAL CROSS SECTIONS OF AWAY TRACTION POWER FACILITIES DIRECTIVE DRAWINGS.
 - THE COMMUNICATION SITE SHALL HOUSE COMMUNICATION INTERFACE EQUIPMENT FOR SCADA SYSTEM AND OTHER WAYSIDE COMMUNICATION EQUIPMENT, AND SHALL REQUIRE MINIMUM 100' VERTICAL CLEARANCE FOR RADIO TOWER.
 - THE GANTRIES SHALL BE 40 FEET HIGH (TYP).

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
M. PAZ
DRAWN BY
V. HUANTE
CHECKED BY
V. SIBAL
IN CHARGE
B. BANKS
DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRACTION POWER DIRECTIVE

CONCEPTUAL LAYOUT
TRACTION POWER SUBSTATION
WITH TWO HIGH-VOLTAGE TRANSFORMERS

CONTRACT NO.
DRAWING NO.
DD-TP-D101
SCALE
NO SCALE
SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

9/30/2014 12:13:40 PM CAHSR.tbl CAHSR.plt c:\projectwise\pb\projectwise\int\laverdev\dms17831\DD-TP-D201.dgn



- NOTES:**
- INTERNAL DIMENSIONS ARE SHOWN FOR TYPICAL EQUIPMENT SIZES. CLEARANCES AND ACCESSIBILITY FOR OPERATION AND MAINTENANCE OF EQUIPMENT AND CONFORMANCE TO RELEVANT CODES, STANDARDS, AND GUIDELINES, FINAL DIMENSIONS AND CONFIGURATION OF EQUIPMENT TO BE DETERMINED DURING FINAL SYSTEMS DESIGN.
 - THE MAIN GANTRY POSITION SHALL BE PARALLEL TO AND ADJACENT TO THE TRACKS.
 - STRAIN GANTRY SHALL BE LOCATED WITHIN THE RAILROAD RIGHT-OF-WAY, PARALLEL TO AND ON THE OPPOSITE SIDE OF THE TRACKS WITH A FOOTPRINT EQUAL TO THAT OF THE MAIN GANTRY.
 - IF THE SWITCHING STATION IS LOCATED AWAY FROM THE TRACKS IN AN UNDESIRABLE CONFIGURATION, THE MAIN GANTRY SHALL BE LOCATED AT THE TRACKWAY, PARALLEL TO AND TOWARDS SWITCH STATION SIDE OF THE TRACKS. REFER TO CONCEPTUAL CROSS SECTIONS OF AWAY TRACTION POWER FACILITIES DIRECTIVE DRAWINGS.
 - THE COMMUNICATION SITE SHALL HOUSE COMMUNICATION INTERFACE EQUIPMENT FOR SCADA SYSTEM AND OTHER WAYSIDE COMMUNICATION EQUIPMENT, AND SHALL REQUIRE 100' VERTICAL CLEARANCE.
 - THE GANTRIES SHALL BE 40 FEET HIGH (TYP).

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
M. PAZ
DRAWN BY
V. HUANTE
CHECKED BY
V. SIBAL
IN CHARGE
B. BANKS
DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRACTION POWER DIRECTIVE

CONCEPTUAL LAYOUT
SWITCHING STATION

CONTRACT NO.
DRAWING NO. DD-TP-D201
SCALE NO SCALE
SHEET NO.

9/30/2014 12:15:26 PM CAHSR.tbl CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\laverdev\dms17831\DD-TP-D301.dgn



NOTES:

1. INTERNAL DIMENSIONS ARE SHOWN FOR TYPICAL EQUIPMENT SIZES. CLEARANCES AND ACCESSIBILITY FOR OPERATION AND MAINTENANCE OF EQUIPMENT CONFORMANCE TO RELEVANT CODES, STANDARDS, AND GUIDELINES, FINAL DIMENSIONS AND CONFIGURATION OF EQUIPMENT TO BE DETERMINED DURING FINAL SYSTEMS DESIGN.
2. THE MAIN GANTRY POSITION SHALL BE PARALLEL TO AND ADJACENT TO THE TRACKS.
3. STRAIN GANTRY SHALL BE LOCATED WITHIN THE RAILROAD RIGHT-OF-WAY, PARALLEL TO AND ON THE OPPOSITE SIDE OF THE TRACKS WITH FOOTPRINT EQUAL TO THAT OF THE MAIN GANTRY.
4. IF THE PARALLELING STATION (PS) IS LOCATED AWAY FROM THE TRACKS IN AN UNDESIRE CONFIGURATION, THE MAIN GANTRY SHALL BE LOCATED AT THE TRACKWAY, PARALLEL TO AND TOWARDS PS SIDE OF THE TRACKS. REFER TO CONCEPTUAL CROSS SECTIONS OF AWAY TRACTION POWER FACILITIES.
5. THE COMMUNICATION SITE SHALL HOUSE COMMUNICATION INTERFACE EQUIPMENT FOR SCADA SYSTEM AND OTHER WAYSIDE COMMUNICATION EQUIPMENT, AND SHALL REQUIRE 100' VERTICAL CLEARANCE.
6. THE GANTRIES SHALL BE 40 FEET HIGH (TYP).

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
M. PAZ
DRAWN BY
V. LAVERDE
CHECKED BY
V. SIBAL
IN CHARGE
B. BANKS
DATE
8/29/2014



**CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRACTION POWER DIRECTIVE**


CONCEPTUAL LAYOUT
PARALLELING STATION

CONTRACT NO.
DRAWING NO.
DD-TP-D301
SCALE
NO SCALE
SHEET NO.


RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

NOTES:

1. THIS DRAWING SHOWS GANTRY ARRANGEMENT FOR AT-GRADE CONFIGURATION FOR TWO ALTERNATIVE OPTIONS:
 - 1) TPF LOCATED ADJACENT TO TRACK ALIGNMENT;
 - 2) TPF LOCATED AWAY FROM TRACK ALIGNMENT;
 ALTERNATIVE 1 IS THE PREFERRED OPTION. ALTERNATIVE 2 MAY BE USED IF ADEQUATE LAND IS NOT AVAILABLE ADJACENT TO RAILROAD ROW.
2. ALTERNATIVE 2 SHALL BE USED FOR TRACK ALIGNMENT ON AERIAL STRUCTURES. SEE "TYPICAL DOUBLE CATENARY FEEDING GANTRY ARRANGEMENT ON AERIAL STRUCTURE" DRAWING.
3. THE SPACING AND NUMBER OF MANHOLES IS INDICATIVE ONLY. ACTUAL LAYOUT WILL DEPEND UPON THE SITE CONDITIONS.
4. THE MAIN GANTRY AND THE STRAIN GANTRY SHALL BE TYPICALLY 4' WIDE AND 40' HIGH.
5. SEE "TYPICAL SINGLE CATENARY FEEDING GANTRY ARRANGEMENT" AND "TYPICAL DOUBLE CATENARY FEEDING GANTRY ARRANGEMENT" DIRECTIVE DRAWINGS FOR GANTRY LOCATION DETAILS.
6. CONCEPTUAL DIMENSIONS FOR MAIN AND STRAIN GANTRY FOUNDATIONS ARE APPROXIMATELY 40' LONG AND 4' WIDE.



ALTERNATIVE #1
 TPF LOCATED ADJACENT TO AT-GRADE HST TRACKWAY
 WITH EMBANKMENT HEIGHT (TOR-OG) ≤ 10 FEET



ALTERNATIVE #2
 TPF LOCATED AWAY FROM AT-GRADE HST TRACKWAY
 OR EMBANKMENT HEIGHT (TOR-OG) > 10 FEET

c:\projectwise\pb\projectwise\int\mincio\dms17831\DD-TP-D401.dgn
 CHSR_half_black.plt
 CAHSR.tbl
 3/30/2014 12:04:50 PM
 mincio

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY M. PAZ
DRAWN BY V. HUANTE
CHECKED BY V. SIBAL
IN CHARGE B. BANKS
DATE 01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRACTION POWER DIRECTIVE


 CONCEPTUAL LOCATIONS OF
 TRACTION POWER FACILITIES

CONTRACT NO. 13341
DRAWING NO. DD-TP-D401
SCALE NO SCALE
SHEET NO.

9/30/2014 12:20:20 PM CAHSRP.tbl CAHSRP.tbl CHSR_PDF_half_black.plt c:\projectwise\bb\projectwise\int\laverdev\dms17831\DD-TP-F103.dgn



TYPICAL SECTION
TRACTION POWER FACILITY SITE ADJACENT TO HST TRACKWAY
RETAINING WALL > 10' HIGH



TYPICAL SECTION
TRACTION POWER FACILITY SITE ADJACENT TO HST TRACKWAY
RETAINING WALL ≤ 10' HIGH

- NOTES:**
1. SYSTEM SITES AT RETAINED FILL TRACKWAY ARE UNDESIRABLE. THESE CROSS-SECTIONS ARE ONLY APPLICABLE IF AT-GRADE SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
 2. FOR RETAINED-FILLED TRACKWAYS, REINFORCED CONCRETE RETAINING WALLS SHALL BE USED AT SYSTEMS FACILITY SITES.
 3. TYPICAL CROSS SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR MINIMUM LENGTH EQUAL TO THE LONGITUDINAL WIDTH OF THE SYSTEMS SITE.
 4. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
 5. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
 6. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.
 7. A LOW VOLTAGE UNDERTRACK DUCTBANK WITH 2 LOW VOLTAGE MANHOLES SHALL BE PROVIDED AT SYSTEMS SITE. REFER TO COMMUNICATIONS DESIGN CRITERIA MANUAL AND DIRECTIVE DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE REQUIREMENTS.
 8. FOR TRACTION POWER SITE REQUIREMENTS, REFER TO TRACTION POWER CONCEPTUAL SITE LAYOUT DIRECTIVE DRAWINGS.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
M. PAZ
DRAWN BY
V. HUANTE
CHECKED BY
V. SIBAL
IN CHARGE
B. BANKS
DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRACTION POWER DIRECTIVE

TYPICAL CATENARY FEEDING ARRANGEMENT
IN RETAINED-FILL FOR TRACTION POWER FACILITIES
ADJACENT TO TRACKWAY

CONTRACT NO.
DRAWING NO.
DD-TP-F103
SCALE
NO SCALE
SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

9/30/2014 12:21:30 PM CAHSRP.tbl CAHSRP.plt c:\projectwise\pb\projectwise\int\laverdev\dms17831\DD-TP-F104.dgn




TYPICAL SECTION
TRACTION POWER FACILITY SITE AWAY FROM RETAINED-FILL HST TRACKWAY

- NOTES:**
1. SYSTEM SITES AT RETAINED FILL TRACKWAY ARE UNDESIRABLE. THESE CROSS-SECTIONS ARE ONLY APPLICABLE IF AT-GRADE SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
 2. FOR RETAINED-FILLED TRACKWAYS, REINFORCED CONCRETE RETAINING WALLS SHALL BE USED AT SYSTEMS FACILITY SITES.
 3. SYSTEM SITES AWAY FROM TRACKWAY SEPARATED BY A THIRD-PARTY RIGHT-OF-WAY ARE UNDESIRABLE. AWAY CROSS-SECTION IS ONLY APPLICABLE IF ADJACENT SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
 4. TYPICAL CROSS SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR MINIMUM LENGTH EQUAL TO THE LONGITUDINAL WIDTH OF THE SYSTEMS SITE.
 5. FOR TRACTION POWER DUCT BANKS AND MANHOLE DETAILS, REFER TO "TYPICAL 25KV DUCT BANK DETAIL AND TYPICAL 25KV MANHOLE DETAIL" DIRECTIVE DRAWINGS.
 6. A LOW VOLTAGE UNDERTRACK DUCTBANK WITH 2 LOW VOLTAGE MANHOLES SHALL BE PROVIDED AT SYSTEMS SITE. REFER TO COMMUNICATIONS DESIGN CRITERIA MANUAL AND DIRECTIVE DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE REQUIREMENTS.
 7. LOW VOLTAGE UNDERGROUND DUCTBANK AND MANHOLE TO BE PROVIDED UNDERNEATH 3RD PARTY RIGHT-OF-WAY.
 8. FOUR ASSEMBLIES, EACH CONSISTING OF A 25KV UNDERGROUND DUCTBANKS WITH 2 25KV MANHOLES, PROVIDED AT EACH TRACTION POWER FACILITY SEPARATED FROM THE TRACKWAY BY THIRD PARTY RIGHT-OF-WAY.
 9. FOR TRACTION POWER SITE REQUIREMENTS, REFER TO TRACTION POWER CONCEPTUAL SITE LAYOUT DIRECTIVE DRAWINGS.
 10. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
 11. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
 12. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
M. PAZ
DRAWN BY
V. HUANTE
CHECKED BY
V. SIBAL
IN CHARGE
B. BANKS
DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRACTION POWER DIRECTIVE

TYPICAL CATENARY FEEDING ARRANGEMENT
FOR TRACTION POWER FACILITIES
IN RETAINED-FILL AWAY FROM TRACKWAY


CONTRACT NO.
DRAWING NO.
DD-TP-F104
SCALE
NO SCALE
SHEET NO.

9/30/2014 12:22:31 PM CAHSR.tbl CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\nt\laverdev\dms17831\DD-TP-F105.dgn



TYPICAL SECTION

TRACTION POWER FACILITY SITE ADJACENT TO TRENCH HST TRACKWAY



TYPICAL SECTION

TRACTION POWER FACILITY SITE AWAY FROM TRENCH HST TRACKWAY

NOTES:

1. SYSTEM SITES AT TRENCH TRACKWAY ARE UNDESIRABLE. THESE CROSS-SECTIONS ARE ONLY APPLICABLE IF AT-GRADE SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
2. FOR RETAINED-FILLED TRACKWAYS, REINFORCED CONCRETE RETAINING WALLS SHALL BE USED AT SYSTEMS FACILITY SITES.
3. SYSTEM SITES AWAY FROM TRACKWAY SEPARATED BY A THIRD PARTY RIGHT-OF-WAY ARE UNDESIRABLE. AWAY CROSS-SECTION IS ONLY APPLICABLE IF ADJACENT SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
4. TYPICAL CROSS-SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR MINIMUM LENGTH EQUAL TO THE LONGITUDINAL WIDTH OF THE SYSTEMS SITE.
5. FOR TRACTION POWER DUCT BANKS AND MANHOLE DETAILS, REFER TO "TYPICAL 25KV DUCT BANK DETAIL" AND "TYPICAL 25KV MANHOLE DETAIL" DIRECTIVE DRAWINGS.
6. LOW VOLTAGE UNDERGROUND DUCTBANK AND MANHOLE SHALL BE PROVIDED UNDERNEATH THIRD PARTY RIGHT-OF-WAY TO CONNECT TO LOW VOLTAGE UNDERTRACK MANHOLES AND DUCTBANK. REFER TO COMMUNICATIONS DESIGN CRITERIA MANUAL AND DIRECTIVE DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE REQUIREMENTS.
7. FOUR ASSEMBLIES EACH CONSISTING OF 25KV UNDERGROUND DUCTBANKS WITH 2 25KV MANHOLES PROVIDED AT EACH TRACTION POWER FACILITY SEPARATED FROM THE TRACKWAY BY THIRD PARTY RIGHT-OF-WAY.
8. FOR TRACTION POWER SITE REQUIREMENTS, REFER TO TRACTION POWER CONCEPTUAL SITE LAYOUT DIRECTIVE DRAWINGS.
9. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
10. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
11. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
M. PAZ
 DRAWN BY
V. HUANTE
 CHECKED BY
V. SIBAL
 IN CHARGE
B. BANKS
 DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRACTION POWER DIRECTIVE
 SYSTEMS SITE
 TRACTION POWER FACILITY
 TRENCH

CONTRACT NO.
 DRAWING NO.
DD-TP-F105
 SCALE
NO SCALE
 SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

1/16/2014 10:28:31 AM CAHSR.tbl CAHSR_PDF_half_black.plt c:\projectwise\bb\projectwise\int\mcal\lybp\dd-TP-N101.dgn



3x4-WAY DUCT BANK (1)
NO SCALE

NOTES:

1. THIS DRAWING SHOWS TYPICAL DUCT BANK DETAILS FOR 5" CONDUIT FOR ILLUSTRATION PURPOSES ONLY. DESIGN THE DUCT BANK TO SITE AND EQUIPMENT SPECIFIC REQUIREMENTS CONFORMING TO RELEVANT CODES, SPECIFICATIONS AND DESIGN CRITERIA.
2. A 36" MINIMUM COVER SHALL BE MAINTAINED FROM TOP OF GRADE TO TOP OF DUCT BANK, WHEN NOT GOING UNDER RAILROAD TRACK, AND A MINIMUM 5'-6" UNDER RAILROAD TRACKS FROM THE BOTTOM OF TIE.
3. THE CONDUIT MATERIAL SHALL BE PVC OR FRE.
4. 25KV CATENARY FEEDER, 25KV NEGATIVE FEEDER, TRACTION RETURN CABLING, HV/MV CABLES FOR FACILITY/AUXILIARY POWER SUPPLY, AND LOW VOLTAGE CABLES (AUXILIARY POWER SUPPLY, COMMUNICATIONS, SIGNALING AND TRAIN CONTROL) MAY BE ROUTED IN THE SAME DUCTBANK BUT IN SEPARATE CONDUITS.

REV	DATE	BY	CHK	APP	DESCRIPTION


DESIGNED BY
M. PAZ
DRAWN BY
V. HUANTE
CHECKED BY
V. SIBAL
IN CHARGE
B. BANKS
DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRACTION POWER DIRECTIVE
TYPICAL 25KV DUCT BANK DETAIL

CONTRACT NO.
DRAWING NO. DD-TP-N101
SCALE NO SCALE
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57




PLAN
TYPICAL PRECAST ELECTRIC MANHOLE




PLAN
ELECTRIC MANHOLE FRAME AND COVER DETAIL

NOTES:

1. THIS DRAWING SHOWS TYPICAL DUCT BANK KNOCKOUTS IN A PRECAST MANHOLE. EXACT DETAILS TO BE WORKED OUT AT DETAILED DESIGN LEVEL.
2. ALL TRACTION POWER MANHOLES SHALL BE TYPICALLY 10'-0" L X 10'-0" W X 10'-0" DEEP AND BE WATERTIGHT WITH SILICON SEALING COMPOUND, OR APPROVED EQUAL.
3. THE MANHOLE FRAME SHALL BE GROUTED TO THE ROOF SLAB.
4. THICKNESS OF MANHOLE WALL SHALL BE 8" MINIMUM.
5. APPROVED CABLE RACK ARMS TO BE INSTALLED TO ACCOMMODATE CABLE, MINIMUM 2 RACKS PER WALL (TYP).
6. PULLING HOOKS SHALL BE GALVANIZED STEEL, SUPPLIED AND CAST INTO WALLS BY PRECASTER, AND ANCHORED BEHIND REINFORCEMENT. QUANTITY AND LOCATION TO SUIT.
7. CONNECT ALL METALLIC PARTS, FRAME, PULLING HOOKS, ETC., TO THE TRACTION POWER FACILITY GROUND GRID OR GROUND ROD.
8. PROVIDE FOR CONNECTION TO A PORTABLE PUMP TO REMOVE ACCUMULATED WATER FROM THE MANHOLE OR OTHER SITE SPECIFIC DRAINAGE SYSTEM.
9. 25KV CATENARY FEEDER, 25KV NEGATIVE FEEDER, TRACTION RETURN CABLING, HV/MV CABLES FOR FACILITY/AUXILIARY POWER SUPPLY, AND LOW VOLTAGE CABLES (AUXILIARY POWER SUPPLY, COMMUNICATIONS, SIGNALING AND TRAIN CONTROL) SHALL BE ROUTED IN SEPARATE MANHOLES.



TYPICAL PRECAST ELECTRIC MANHOLE
SECTION A
NO SCALE



TYPICAL PRECAST ELECTRIC MANHOLE
SECTION B
NO SCALE

9/30/2014 12:25:00 PM CAHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\laverdev\dms17831\DD-TP-N111.dgn

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
M. PAZ
DRAWN BY
V. HUANTE
CHECKED BY
V. SIBAL
IN CHARGE
B. BANKS
DATE
8/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRACTION POWER DIRECTIVE

TYPICAL 25KV MANHOLE DETAILS

CONTRACT NO.
DRAWING NO. DD-TP-N111
SCALE NO SCALE
SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

California High-Speed Rail Authority



RFP No.: HSR 13-57

**Request for Proposals for Design-Build
Services for Construction Package 2-3**

**Book II, Part B.1
Directive Drawings**

Overhead Contact System


c:\projectwise\pb\projectwise\int\mincio\dms17830\DD-OC-2046.dgn

CHSR_half_black.plt

CAHSRP.tbl

3/30/2014 12:12:48 PM

mincio



NOTES:

1. TRACK, STRUCTURES, AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. SMALL METALLIC ITEMS, SUCH AS RAILING, FENCE ETC, BEYOND THE STEP AND TOUCH POTENTIAL LIMIT NEED NOT BE GROUNDED. THE STEP AND TOUCH POTENTIAL EXISTS WITHIN 8' OF A STANDING TRAIN, 8' FROM ANY ELECTRICALLY CONTINUOUS BONDED FENCE, AND 8' FROM ANY METALLIC ITEM BONDED TO STATIC WIRE.
3. GROUNDEDING AND BONDING DETAILS DESIGN SHALL BE COORDINATED WITH OVERPASS STRUCTURE DESIGNER.
4. OVERHEAD BRIDGE GROUNDEDING AND BONDING DETAILS SHOWN IN DRAWING ARE GENERIC IN NATURE. THE OCS DESIGNER SHALL PROVIDE DETAILED ASSEMBLIES AND COMPONENTS THAT MEET THE REQUIREMENT.
5. GALVANIZED STEEL STRIP OR ANGLE SECTION SHALL BE INSTALLED ABOVE THE OVERHEAD LINE AT EACH BRIDGE FACE, IF THE BRIDGE SOFFIT IS WITHIN THE PANTOGRAPH ZONE. WHEN THE VERTICAL CLEARANCE BETWEEN OCS CONDUCTORS AND CONCRETE OVERPASSES IS LESS THAN 3 FEET, PROTECTION PANELS (FLASH PLATES) SHALL BE INSTALLED ABOVE THE OCS, ATTACHED TO THE UNDERSIDE OF THE STRUCTURE, AND INTERCONNECTED TO THE STATIC WIRE AT NOT LESS THAN TWO LOCATIONS.
6. THE GROUND PLATE SHALL BE NO LESS THAN 6" X 6" IN DIMENSION.
7. SEE OVERHEAD CONTACT SYSTEM AND TRACTION POWER RETURN SYSTEM AND CIVIL DESIGN CRITERIA CHAPTERS FOR PROTECTIVE FENCE CRITERIA.

TYPICAL OVERHEAD STRUCTURE GROUNDEDING AND BONDING

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
J. LAU
DRAWN BY
V. HUANTE
CHECKED BY
M. HSIAO
IN CHARGE
B. BANKS
DATE
01/24/2014



**CALIFORNIA HIGH-SPEED TRAIN PROJECT
OVERHEAD CONTACT SYSTEM DIRECTIVE**

TYPICAL GROUNDEDING AND BONDING ARRANGEMENT
OVERHEAD BRIDGE STRUCTURE

CONTRACT NO.
13341
DRAWING NO.
DD-OC-2046
SCALE
NO SCALE
SHEET NO.


04/02/2014 - RFP No.: HSR 13-57

c:\projectwise\pb\projectwise\int\mincio\dms17830\DD-OC-2047.dgn

CHSR_half_black.plt

3/30/2014 12:09:38 PM CAHSR.tbl

mincio



**TYPICAL OCS GROUNDING AND BONDING
AT AERIAL STRUCTURE**

NOTES:

1. TRACK, STRUCTURES, AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. GROUNDING AND BONDING DETAIL DESIGN SHALL BE COORDINATED WITH AERIAL STRUCTURE DESIGNER.
3. THE GROUNDING AND BONDING FOR THE EMERGENCY WALKWAY AREA AND OTHER PUBLICLY ACCESSIBLE AREAS SHALL BE DESIGNED TO AVOID INADMISSIBLE TOUCH AND STEP VOLTAGES AND ALSO MEET SIGNALING OPERATION REQUIREMENTS.
4. FOR LOCATIONS OF THE GROUND PLATES, SEE GROUNDING AND BONDING DESIGN CRITERIA FOR DETAIL.
5. THE GROUND PLATES ON THE AERIAL STRUCTURE SLAB SHALL BE PLACED BETWEEN THE EDGE OF THE TRACK SLAB AND DERAILMENT WALL.
6. THE GROUND PLATE SHALL BE NO LESS THAN 6"X6" IN DIMENSION.
7. INDIVIDUAL CONCRETE TIES DO NOT NEED TO BE BONDED TO THE TRACTION POWER RETURN SYSTEM. STEEL REINFORCEMENT IN PRECAST CONCRETE PANELS FOR DIRECT FIXATION TRACK SHALL BE BONDED AND CONNECTED TO THE TRACTION POWER RETURN SYSTEM.
8. STEEL REINFORCED CONCRETE PARAPETS AND CONDUCTIVE SCREEN, NOISE, WIND OR SAFETY BARRIERS OR RAILINGS SHALL BE BONDED TO THE TRACTION POWER RETURN SYSTEM.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
J. LAU
DRAWN BY
V. HUANTE
CHECKED BY
M. HSIAO
IN CHARGE
B. BANKS
DATE
01/24/2014



**CALIFORNIA HIGH-SPEED TRAIN PROJECT
OVERHEAD CONTACT SYSTEM DIRECTIVE**

TYPICAL GROUNDING AND BONDING ARRANGEMENT
AERIAL STRUCTURE

CONTRACT NO.	
DRAWING NO.	DD-OC-2047
SCALE	NO SCALE
SHEET NO.	

04/02/2014 - RFP No.: HSR 13-57

California High-Speed Rail Authority




RFP No.: HSR 13-57

**Request for Proposals for Design-Build
Services for Construction Package 2-3**

**Book II, Part B.1
Directive Drawings**


Automatic Train Control

9/30/2014 12:17:05 PM CAHSRP.TBL CHSR_half_black.plt C:\Users\mncio\Desktop\New Folder (3)\DD-TC-100.dgn



NOTES:

1. TYPICAL CROSS SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR MINIMUM LENGTH EQUAL TO THE LONGITUDINAL WIDTH OF THE CENTRALIZED TRAIN CONTROL SITE OR FOR THE LONGITUDINAL DISTANCE BETWEEN FURTHEST TRAIN CONTROL SITES AT AN INTERLOCKING.
2. FOR TRAIN CONTROL SITE REQUIREMENTS REFER TO TYPICAL TRAIN CONTROL SITES LAYOUT DIRECTIVE DRAWINGS.
3. A LOW VOLTAGE UNDERTRACK DUCTBANK WITH 2 LOW VOLTAGE MANHOLES PROVIDED AT EACH SYSTEMS SITE. REFER TO COMMUNICATIONS DESIGN CRITERIA MANUAL AND DIRECTIVE DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE REQUIREMENTS.
4. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
5. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
6. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.



REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
I. MUF TIC
 DRAWN BY
V. LAVERDE
 CHECKED BY
B. MCNALLY
 IN CHARGE
B. BANKS
 DATE
8/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL DIRECTIVE


 SYSTEMS SITE
 TCS
 AT GRADE

CONTRACT NO.
DRAWING NO. DD-TC-100
SCALE NO SCALE
SHEET NO.


RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

NOTES:

1. SYSTEM SITES AT AERIAL TRACKWAY ARE UNDESIRABLE. THESE CROSS-SECTIONS ARE ONLY APPLICABLE IF AT-GRADE SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
2. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
3. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
4. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.
5. TYPICAL CROSS SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR MINIMUM LENGTH EQUAL TO THE LONGITUDINAL WIDTH OF THE CENTRALIZED TRAIN CONTROL SITE OR FOR THE LONGITUDINAL DISTANCE BETWEEN FURTHEST TRAIN CONTROL SITES AT AN INTERLOCKING.
6. FOR TRAIN CONTROL SITE REQUIREMENTS REFER TO TYPICAL TRAIN CONTROL SITES LAYOUT DIRECTIVE DRAWINGS.



TYPICAL SECTION
TCS SITE AT AERIAL TRACKWAY



TYPICAL SECTION
CENTRALIZED TCS SITE AT AERIAL TRACKWAY

9/30/2014 12:17:07 PM CAHSRP.TBL CHSR_half_black.plt C:\Users\mincio\Desktop\New Folder (3)\DD-TC-101.dgn

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
I. MUF TIC
DRAWN BY
V. LAVERDE
CHECKED BY
B. MCNALLY
IN CHARGE
B. BANKS
DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL DIRECTIVE

SYSTEMS SITE
TCS
AERIAL

CONTRACT NO.
DRAWING NO. DD-TC-101
SCALE NO SCALE
SHEET NO.

RFP No.: 13-57 – Addendum No. 5 - 10/09/2014



TYPICAL SECTION
TCS SITE ADJACENT TO HST TRACKWAY TRENCH

NOTES:

1. TYPICAL CROSS SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR MINIMUM LENGTH EQUAL TO THE LONGITUDINAL WIDTH OF THE TRAIN CONTROL SITE D OR FOR THE LONGITUDINAL DISTANCE BETWEEN FURTHEST TRAIN CONTROL SITES AT AN INTERLOCKING.
2. FOR TRAIN CONTROL SITE REQUIREMENTS REFER TO TYPICAL TRAIN CONTROL SITES LAYOUT DIRECTIVE DRAWINGS.

C:\Users\mincio\Desktop\New Folder (3)\DD-TC-102.dgn

9/30/2014 12:17:09 PM CAHSR.TBL CHSR_half_black.plt mincio

RFP No.: 13-57 – Addendum No. 5 - 10/09/2014

REV	DATE	BY	CHK	APP	DESCRIPTION


DESIGNED BY
I. MUF TIC
DRAWN BY
V. HUANTE
CHECKED BY
B. MCNALLY
IN CHARGE
B. BANKS
DATE
8/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
AUTOMATIC TRAIN DIRECTIVE

SYSTEMS SITE
TCS
TRENCH


CONTRACT NO.
DRAWING NO.
DD-TC-102
SCALE
NO SCALE
SHEET NO.



TYPICAL SECTION
TCS SITE ADJACENT TO HST TRACKWAY
RETAINING WALL

NOTES:

1. FOR RETAINED-FILLED TRACKWAYS, REINFORCED CONCRETE RETAINING WALLS SHALL BE USED AT SYSTEMS SITES.
2. TYPICAL CROSS SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR MINIMUM LENGTH EQUAL TO THE LONGITUDINAL WIDTH OF THE CENTRALIZED TRAIN CONTROL SITE OR FOR THE LONGITUDINAL DISTANCE BETWEEN FURTHEST AUTOMATIC TRAIN CONTROL SITES AT AN INTERLOCKING.
3. FOR TRAIN CONTROL SYSTEM SITE REQUIREMENTS REFER TO TYPICAL TRAIN CONTROL SITES LAYOUT DIRECTIVE DRAWINGS.
4. A LOW VOLTAGE UNDERTRACK DUCTBANK WITH 2 LOW VOLTAGE MANHOLES PROVIDED AT EACH SYSTEMS SITE. REFER TO COMMUNICATIONS DESIGN CRITERIA MANUAL AND DIRECTIVE DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE REQUIREMENTS.
5. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
6. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
7. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.



TYPICAL SECTION
CENTRALIZED TCS SITE ADJACENT TO HST TRACKWAY
RETAINING WALL

9/30/2014 12:17:10 PM CAHSRP.TBL CHSR_half_black.plt C:\Users\mncio\Desktop\New Folder (3)\DD-TC-103.dgn

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
I. MUFTIC
DRAWN BY
V. LAVERDE
CHECKED BY
B. MCNALLY
IN CHARGE
B. BANKS
DATE
8/29/2014

**PARSONS
BRINCKERHOFF**




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL SYSTEM DIRECTIVE**

SYSTEMS SITE
TCS
RETAINED FILL

CONTRACT NO.
DRAWING NO.
DD-TC-103
SCALE
NO SCALE
SHEET NO.


RFP No.: 13-57 – Addendum No. 5 - 10/09/2014



PLAN

NOTES:

1. SITES A AND B MAY BE LOCATED ON EITHER SIDE OF THE TRACK.
2. WHERE POSSIBLE, FOR SITES A AND B, ALTERNATIVES SHALL BE PROVIDED ON THE OPPOSITE SIDE OF THE TRACK.
3. SITE A WILL ACCOMMODATE TRAIN CONTROL SYSTEM EQUIPMENT, COMMUNICATIONS SYSTEM EQUIPMENT WITH THE RADIO TOWER, AND WAYSIDE POWER CONTROL (WPC) EQUIPMENT.
4. AN ACCESS ROAD AND AN ACCESS GATE SHALL BE PROVIDED FOR EACH SITE PER THE CIVIL DESIGN CRITERIA.
5. AN ASSEMBLY, CONSISTING OF A LOW VOLTAGE UNDERTRACK DUCTBANK WITH 2 LOW VOLTAGE MANHOLES, SHALL BE PROVIDED AT EACH TRAIN CONTROL SITE. REFER TO COMMUNICATIONS DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE DETAIL REQUIREMENTS.
6. FOR NUMBER OF CONDUITS REFER TO COMMUNICATIONS DESIGN CRITERIA AND DRAWING "TYPICAL CROSS SECTION SYSTEMS LOW-VOLTAGE CONDUIT DUCTBANK".
7. ACCESS ROADS AND ACCESS GATES ARE SHOWN FOR INFORMATION ONLY. REFER TO CIVIL DESIGN CRITERIA FOR ACCESS ROADS AND ACCESS GATES DETAIL REQUIREMENTS.



SITE A, B OR C

WITH LOW-VOLTAGE UNDERTRACK CONDUIT DUCTBANK, ACCESS ROADS AND GATES

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
I. MUF TIC
DRAWN BY
V. LAVERDE
CHECKED BY
B. MCNALLY
IN CHARGE
B. BANKS
DATE
8/29/2014




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL DIRECTIVE**

TYPICAL TCS SITES
LAYOUT AT STATION AND INTERLOCKINGS


CONTRACT NO.
DRAWING NO. DD-TC-200
SCALE NO SCALE
SHEET NO.

9/30/2014 12:17:13 PM CAHSRP.TBL CHSR_half_black.plt C:\Users\mncio\Desktop\New Folder (3)\DD-TC-201.dgn



NOTES:

1. SITES B AND E MAY BE LOCATED ON EITHER SIDE OF THE TRACK.
2. WHERE POSSIBLE, FOR SITES B AND E, ALTERNATIVES SHALL BE PROVIDED ON THE OPPOSITE SIDE OF THE TRACK.
3. SITE E WILL ACCOMMODATE TRAIN CONTROL SYSTEM EQUIPMENT, COMMUNICATIONS SYSTEM EQUIPMENT WITH THE RADIO TOWER, AND WAYSIDE POWER CONTROL (WPC) EQUIPMENT.
4. AN ACCESS ROAD AND AN ACCESS GATE SHALL BE PROVIDED FOR EACH SITE PER THE CIVIL DESIGN CRITERIA.
5. AN ASSEMBLY, CONSISTING OF A LOW VOLTAGE UNDERTRACK DUCTBANK WITH 2 LOW VOLTAGE MANHOLES, SHALL BE PROVIDED AT EACH TRAIN CONTROL SITE. REFER TO COMMUNICATIONS DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE DETAIL REQUIREMENTS.
6. FOR NUMBER OF CONDUITS REFER TO COMMUNICATIONS DESIGN CRITERIA AND DRAWING "TYPICAL CROSS SECTION SYSTEMS LOW-VOLTAGE CONDUIT DUCTBANK".
7. ACCESS ROADS AND ACCESS GATES ARE SHOWN FOR INFORMATION ONLY. REFER TO CIVIL DESIGN CRITERIA FOR ACCESS ROADS AND ACCESS GATES DETAIL REQUIREMENTS.




SITE B OR E

WITH LOW-VOLTAGE UNDERTRACK CONDUIT DUCTBANK, ACCESS ROADS AND GATES

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
I. MUF TIC
 DRAWN BY
V. LAVERDE
 CHECKED BY
B. MCNALLY
 IN CHARGE
B. BANKS
 DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL DIRECTIVE
 TYPICAL TCS SITES AND
 INTERLOCKINGS LAYOUT AT UNIVERSAL CROSSOVERS

CONTRACT NO.
DRAWING NO. DD-TC-201
SCALE NO SCALE
SHEET NO.


RFP No.: 13-57 – Addendum No. 5 - 10/09/2014

C:\Users\mncio\Desktop\New Folder (3)\DD-TC-202.dgn


9/30/2014 12:17:14 PM CAHSRP.TBL CHSR_half_black.plt mncio




TYPICAL TCS SITES D AND E
PLACEMENT BETWEEN STATION AND UNIVERSAL CROSSOVERS



TYPICAL TCS SITES D AND E
PLACEMENT BETWEEN WYE AND UNIVERSAL CROSSOVERS



TYPICAL TCS SITES D AND E
PLACEMENT BETWEEN TWO ADJACENT UNIVERSAL CROSSOVERS



TYPICAL SITES D & E CONFIGURATION
WITH LOW-VOLTAGE UNDERTRACK CONDUIT DUCTBANK, ACCESS ROADS AND GATES

NOTES:

- THIS DRAWING SHOWS A TYPICAL SPACING BETWEEN STATION TRAIN CONTROL AND COMMUNICATIONS (TCC) ROOM, D SITES, AND E SITES AT UNIVERSAL CROSSOVERS.
- IF THE STATION DESIGN IS NOT AVAILABLE, THE CENTER LINE OF PLATFORM SHALL BE USED AS A REFERENCE POINT INSTEAD OF THE EXACT LOCATION OF THE TCC ROOM.
- D SITES SHALL BE PROVIDED AT THE NOMINAL DISTANCE OF 7.5 MILES BETWEEN STATION TCC ROOM AND ADJACENT SITE D, BETWEEN 2 ADJACENT D SITES, AND BETWEEN ADJACENT D SITE AND E SITE AT UNIVERSAL CROSSOVERS.
- MINIMUM SPACING BETWEEN STATION TCC ROOM AND ADJACENT SITE D, BETWEEN 2 ADJACENT D SITES, AND BETWEEN ADJACENT D SITE AND E SITE AT UNIVERSAL CROSSOVERS IS 5.8 MILES.
- MAXIMUM SPACING BETWEEN STATION TCC ROOM AND ADJACENT SITE D, BETWEEN 2 ADJACENT D SITES, AND BETWEEN ADJACENT D SITE AND E SITE AT UNIVERSAL CROSSOVERS IS 8.7 MILES.
- D SITES MAY BE LOCATED ON EITHER SIDE OF TRACK.
- FOR EACH D SITE, AN ALTERNATIVE SHALL BE PROVIDED.
- IF THERE IS AN EXISTING STAND ALONE RADIO SITE (SRS) WITHIN THE SPACING LIMITS FOR A D SITE, THE SRS CAN BE REPLACED WITH A NEW D SITE.
- IF THERE IS A TRACTION POWER FACILITY (TPF) WITHIN THE SPACING LIMITS FOR AN ATC D SITE, THE ATC D SITE CAN BE PLACED CLOSE TO THE TPF SITE TO UTILIZE THE SAME ACCESS ROAD.
- THIS CRITERIA IS NOT APPLICABLE FOR TUNNELS LONGER THAN 6 MILES AND THOSE WILL BE CONSIDERED AS A SPECIAL CASE.
- AN ASSEMBLY, CONSISTING OF A LOW VOLTAGE UNDERTRACK DUCTBANK WITH 2 LOW VOLTAGE MANHOLES, SHALL BE PROVIDED AT EACH TRAIN CONTROL SITE. REFER TO COMMUNICATIONS DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE DETAIL REQUIREMENTS.
- ACCESS ROADS AND ACCESS GATES ARE SHOWN FOR INFORMATION ONLY. REFER TO CIVIL DESIGN CRITERIA FOR ACCESS ROADS AND ACCESS GATES DETAIL REQUIREMENTS.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

REV	DATE	BY	CHK	APP	DESCRIPTION


DESIGNED BY
I. MUF TIC
DRAWN BY
V. LAVERDE
CHECKED BY
B. MCNALLY
IN CHARGE
B. BANKS
DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL DIRECTIVE

TYPICAL TCS
SITES D AND E CONFIGURATION


CONTRACT NO.	
DRAWING NO.	DD-TC-202
SCALE	NO SCALE
SHEET NO.	




SITE A TYPICAL CONFIGURATION



SITE AA TYPICAL CONFIGURATION



SITE B TYPICAL CONFIGURATION



SITE C TYPICAL CONFIGURATION

NOTES:

1. SITES A AND AA WILL ACCOMMODATE TRAIN CONTROL, COMMUNICATIONS SYSTEM (WITH RADIO TOWER), AND WAYSIDE POWER CONTROL (WPC) EQUIPMENT. A SEPARATE ROOM OF 25 SQUARE FEET SHALL BE RESERVED FOR WPC WITHIN THE SIGNAL HOUSE.
2. REFER TO COMMUNICATIONS DRAWINGS FOR DUCTBANK, MANHOLE CROSS SECTIONS, DETAILS AND ELEVATIONS.
3. FOR NUMBERS OF CONDUITS REFER TO COMMUNICATION DESIGN CRITERIA AND DRAWING "TYPICAL CROSS SECTION SYSTEMS LOW-VOLTAGE CONDUIT DUCTBANK".
4. FOR RADIO TOWER REQUIREMENTS AND CLEARANCES REFER TO COMMUNICATIONS DESIGN CRITERIA AND DRAWINGS.

9/30/2014 12:17:16 PM CAHSRP.TBL CHSR_half_black.plt C:\Users\mncio\Desktop\New Folder (3)\DD-TC-203.dgn

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
I. MUF TIC
DRAWN BY
V. LAVERDE
CHECKED BY
B. MCNALLY
IN CHARGE
B. BANKS
DATE
8/29/2014




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL DIRECTIVE**

TYPICAL TCS SITES
A, AA, B, & C LAYOUT

CONTRACT NO.
DRAWING NO. DD-TC-203
SCALE NO SCALE
SHEET NO.

RFP No.: 13-57 – Addendum No. 5 - 10/09/2014

9/30/2014 12:17:54 PM CAHSRP.TBL CHSR_half_black.plt C:\Users\mncio\Desktop\New Folder (3)\DD-TC-204.dgn



- NOTES:**
1. FOR RADIO TOWER REQUIREMENTS AND CLEARANCES REFER TO COMMUNICATIONS DESIGN CRITERIA AND DRAWINGS.
 2. INTERNAL DIMENSIONS ARE SHOWN FOR TYPICAL EQUIPMENT SIZES, CLEARANCES AND ACCESSIBILITY FOR OPERATION AND MAINTENANCE OF EQUIPMENT CONFORMANCE TO RELEVANT CODES, STANDARDS, AND GUIDELINES, FINAL DIMENSIONS AND CONFIGURATION OF EQUIPMENT TO BE DETERMINED DURING FINAL SYSTEMS DESIGN.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
I. MUF TIC
 DRAWN BY
V. LAVERDE
 CHECKED BY
B. MCNALLY
 IN CHARGE
B. BANKS
 DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL DIRECTIVE

 TYPICAL TCS SITE D LAYOUT

CONTRACT NO.
DRAWING NO. DD-TC-204
SCALE NO SCALE
SHEET NO.

RFP No.: 13-57 – Addendum No. 5 - 10/09/2014

9/30/2014 12:17:56 PM CAHSRP.tbl CAHSRP.tbl C:\Users\mncio\Desktop\New Folder (3)\DD-TC-205.dgn



NOTES:

1. FOR RADIO TOWER REQUIREMENTS AND CLEARANCES REFER TO COMMUNICATIONS DESIGN CRITERIA AND DRAWINGS.
2. INTERNAL DIMENSIONS ARE SHOWN FOR TYPICAL EQUIPMENT SIZES, CLEARANCES AND ACCESSIBILITY FOR OPERATION AND MAINTENANCE OF EQUIPMENT CONFORMANCE TO RELEVANT CODES, STANDARDS, AND GUIDELINES, FINAL DIMENSIONS AND CONFIGURATION OF EQUIPMENT TO BE DETERMINED DURING FINAL SYSTEMS DESIGN.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
I. MUF TIC
 DRAWN BY
V. LAVERDE
 CHECKED BY
B. MCNALLY
 IN CHARGE
B. BANKS
 DATE
8/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
TRAIN CONTROL DIRECTIVE
 TYPICAL TCS SITE E LAYOUT

CONTRACT NO.
DRAWING NO. DD-TC-205
SCALE NO SCALE
SHEET NO.

RFP No.: 13-57 – Addendum No. 5 - 10/09/2014

California High-Speed Rail Authority




RFP No.: HSR 13-57

**Request for Proposals for Design-Build
Services for Construction Package 2-3**

**Book III, Part B.1
Directive Drawings**

Communications

9/30/2014 1:19:13 PM CAHSRP.tbl CHSR_PDF_half_black.plt c:\projectwise\pb\projectwise\int\laverdev\dms17832\DD-CO-F080.dgn



- NOTES:**
1. ANTENNA AND SUPPORT DIMENSIONS ARE BASED ON ROHN 100' MONOPOLE T100HA.
 2. TOWER EMBEDMENT DEPTH ASSUMED TO BE APPROXIMATELY 25 FEET TOWER BASE AND FOUNDATION ASSUMED TO BE 5 FOOT DIAMETER.
 3. THESE ASSUMPTIONS SHALL BE VALIDATED BY DESIGN FOR SOIL AND ENVIRONMENTAL CONDITIONS.
 4. INTERNAL DIMENSIONS ARE SHOWN FOR TYPICAL EQUIPMENT SIZES. CLEARANCES AND ACCESSIBILITY FOR OPERATION AND MAINTENANCE OF EQUIPMENT AND CONFORMANCE TO RELEVANT CODES, STANDARDS, AND GUIDELINES, FINAL DIMENSIONS AND CONFIGURATION OF EQUIPMENT TO BE DETERMINED DURING FINAL SYSTEMS DESIGN.

ANTENNA CLEARANCE TO FENCE OR OTHER EQUIPMENT

POWER FEED FROM NEAREST OCS POLE MOUNTED AUXILIARY TRANSFORMER, ROUTED UNDERGROUND IN DUCTBANK

CABLE FEED FROM TRACKSIDE CABLE TROUGHS, ROUTED UNDERGROUND IN DUCTBANK

FENCED PERIMETER

← HST TRACKWAY →

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
C. DALOIA
DRAWN BY
V. LAVERDE
CHECKED BY
B. MCNALLY
IN CHARGE
B. BANKS
DATE
8/29/2014




**CALIFORNIA HIGH-SPEED TRAIN PROJECT
COMMUNICATIONS DIRECTIVE**

CONCEPTUAL LAYOUT
COMMUNICATIONS SPACES
PHYSICAL SITE LAYOUT


CONTRACT NO.
DRAWING NO. DD-CO-F080
SCALE NO SCALE
SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

9/30/2014 12:47:57 PM CAHSRP.TBL CHSR_half_black.plt C:\Users\mncio\Desktop\New Folder (3)\DD-CO-G023.dgn




20 CONDUIT CONCRETE ENCASED DUCT BANK




12 CONDUIT CONCRETE ENCASED DUCT BANK

NOTES:


1. CONCRETE ENCASED DUCT BANK TO BE PLACED A MINIMUM 6' BELOW TOP OF RAIL AND MINIMUM 3' BELOW GRADE WHEN NO RAIL IS PRESENT.
2. LOW VOLTAGE DUCT BANK TO BE LOCATED PER THE CRITERIA LISTED IN THE COMMUNICATIONS DESIGN CRITERIA CHAPTER.



PLAN



SECTION A-A



SECTION B-B

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
C. DALOIA
 DRAWN BY
V. LAVERDE
 CHECKED BY
B. MCNALLY
 IN CHARGE
B. BANKS
 DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
COMMUNICATIONS DIRECTIVE
 TYPICAL CROSS SECTION
 LOW VOLTAGE MANHOLE / CABLE TROUGH / DUCTBANK
 DETAILS

CONTRACT NO.	
DRAWING NO.	DD-CO-G023
SCALE	NO SCALE
SHEET NO.	

RFP No. 13-57 - Addendum No. 5 - 10/09/2014

NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.
2. MANHOLE SHALL NOT BE ALIGNED WITH OCS FOUNDATION OR FENCE FOOTING.



3/30/2014 12:14:16 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\mincio\dms17832\DD-CO-G040.dgn

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
B. BANKS
 DRAWN BY
V. HUANTE
 CHECKED BY
C. DALOIA
 IN CHARGE
R. SCHEDES
 DATE




CALIFORNIA HIGH-SPEED TRAIN PROJECT
COMMUNICATIONS DIRECTIVE
 TYPICAL CROSS SECTION
 SYSTEMS LOW-VOLTAGE
 UNDERTRACK CONDUIT DUCT BANK
 AT-GRADE

CONTRACT NO.
DRAWING NO. DD-CO-G040
SCALE NO SCALE
SHEET NO.

04/02/2014 - RFP No.: HSR 13-57

NOTES:

1. TRACK, SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN.



3/30/2014 12:16:20 PM CAHSRP.tbl CHSR_half_black.plt c:\projectwise\pb\projectwise\int\m\incio\dms17832\DD-CO-G041.dgn

04/02/2014 - RFP No.: HSR 13-57

REV	DATE	BY	CHK	APP	DESCRIPTION


DESIGNED BY
B. BANKS
 DRAWN BY
V. HUANTE
 CHECKED BY
C. DALOIA
 IN CHARGE
R. SCHMEDES
 DATE
01/24/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
COMMUNICATIONS DIRECTIVE
 TYPICAL CROSS SECTION
 SYSTEMS LOW-VOLTAGE
 UNDER TRACK/UNDERGROUND CONDUIT DUCT BANK
 AT-GRADE

CONTRACT NO.
DRAWING NO. DD-CO-G041
SCALE NO SCALE
SHEET NO.

9/30/2014 12:47:59 PM CAHSRP.TBL CHSR_half_black.plt C:\Users\mncio\Desktop\New Folder (3)\DD-CO-G050.dgn



TYPICAL SECTION
 STANDALONE RADIO SITE ADJACENT TO AT-GRADE HST TRACKWAY
 WITH EMBANKMENT HEIGHT (TOR-OG) ≤ 10 FEET



TYPICAL SECTION
 STANDALONE RADIO SITE AWAY FROM AT-GRADE HST TRACKWAY OR
 EMBANKMENT HEIGHT (TOR-OG) > 10 FEET

NOTES:

1. TYPICAL CROSS-SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR A MINIMUM LENGTH EQUAL TO THE LONGITUDINAL DIMENSION OF THE SYSTEMS SITE.
2. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
3. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
4. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.
5. FOR STANDALONE RADIO SITE REQUIREMENTS REFER TO COMMUNICATIONS SYSTEMS SITE REQUIREMENTS.
6. A LOW VOLTAGE UNDERTRACK DUCTBANK WITH 2 LOW VOLTAGE MANHOLES TO BE PROVIDED AT SYSTEMS SITE. REFER TO COMMUNICATIONS DESIGN CRITERIA MANUAL AND DIRECTIVE DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE REQUIREMENTS.
7. SYSTEM SITES AWAY FROM TRACKWAY, SEPARATED BY A THIRD-PARTY RIGHT-OF-WAY ARE UNDESIRABLE. AWAY CROSS-SECTION IS ONLY APPLICABLE IF ADJACENT SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
8. LOW VOLTAGE UNDERGROUND DUCTBANK AND MANHOLE TO BE PROVIDED UNDERNEATH 3RD PARTY RIGHT-OF-WAY TO CONNECT TO LOW VOLTAGE UNDERTRACK MANHOLES AND DUCTBANK.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
C. DALOIA
 DRAWN BY
V. LAVERDE
 CHECKED BY
B. MCNALLY
 IN CHARGE
B. BANKS
 DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
COMMUNICATIONS DIRECTIVE

 SYSTEMS SITE
 STANDALONE RADIO SITE
 AT-GRADE

CONTRACT NO.
DRAWING NO. DD-CO-G050
SCALE NO SCALE
SHEET NO.

RFP No.: 13-57 – Addendum No. 5 - 10/09/2014



TYPICAL SECTION
STANDALONE RADIO SITE AT AERIAL TRACKWAY

NOTES:

1. SYSTEM SITES AT AERIAL TRACKWAY ARE UNDESIRABLE. THESE CROSS-SECTIONS ARE ONLY APPLICABLE IF AT-GRADE SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
2. TYPICAL CROSS-SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR A MINIMUM LENGTH EQUAL TO THE LONGITUDINAL DIMENSION OF THE SYSTEMS SITE.
3. FOR STANDALONE RADIO SITE REQUIREMENTS REFER TO COMMUNICATIONS SYSTEMS SITE REQUIREMENTS.
4. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
5. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
6. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
C. DALOIA

DRAWN BY
V. LAVERDE

CHECKED BY
B. MCNALLY

IN CHARGE
B. BANKS

DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
COMMUNICATIONS DIRECTIVE


SYSTEMS SITE
STANDALONE RADIO SITE
AERIAL

CONTRACT NO.
DRAWING NO. DD-CO-G051
SCALE NO SCALE
SHEET NO.

9/30/2014 12:48:01 PM CAHSRP.TBL CHSR_half_black.plt C:\Users\mncio\Desktop\New Folder (3)\DD-CO-G052.dgn



TYPICAL SECTION
STANDALONE RADIO SITE ADJACENT TO TRENCH HST TRACKWAY



TYPICAL SECTION
STANDALONE RADIO SITE AWAY FROM TRENCH HST TRACKWAY

NOTES:

1. SYSTEM SITES AT TRENCH TRACKWAY ARE UNDESIRABLE. THESE CROSS-SECTIONS ARE ONLY APPLICABLE IF AT-GRADE SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
2. FOR RETAINED-FILLED TRACKWAYS, REINFORCED CONCRETE RETAINING WALLS SHALL BE USED AT SYSTEMS SITES.
3. TYPICAL CROSS-SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR A MINIMUM LENGTH EQUAL TO THE LONGITUDINAL DIMENSION OF THE SYSTEMS SITE.
4. FOR STANDALONE RADIO SITE REQUIREMENTS REFER TO COMMUNICATIONS SYSTEMS SITE REQUIREMENTS.
5. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
6. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
7. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.
8. SYSTEM SITES AWAY FROM TRACKWAY, SEPARATED BY A THIRD-PARTY RIGHT-OF-WAY ARE UNDESIRABLE. AWAY CROSS-SECTION IS ONLY APPLICABLE IF ADJACENT SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
9. LOW VOLTAGE UNDERGROUND DUCTBANK AND MANHOLES TO BE PROVIDED UNDERNEATH 3RD PARTY RIGHT-OF-WAY.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
C. DALOIA
 DRAWN BY
V. LAVERDE
 CHECKED BY
B. MCNALLY
 IN CHARGE
B. BANKS
 DATE
8/29/2014




CALIFORNIA HIGH-SPEED TRAIN PROJECT
COMMUNICATIONS DIRECTIVE

 SYSTEMS SITE
 STANDALONE RADIO SITE
 TRENCH


CONTRACT NO.
DRAWING NO. DD-CO-G052
SCALE NO SCALE
SHEET NO.

RFP No.: 13-57 - Addendum No. 5 - 10/09/2014

9/30/2014 12:48:02 PM CAHSRP.tbl CHSR_half_black.plt C:\Users\mimcio\Desktop\New Folder (3)\DD-CO-G053.dgn



TYPICAL SECTION
STANDALONE RADIO SITE ADJACENT TO HST TRACKWAY
RETAINING WALL



TYPICAL SECTION
STANDALONE RADIO SITE AWAY FROM HST TRACKWAY
RETAINING WALL

NOTES:

1. SYSTEM SITES AT RETAINED FILL TRACKWAY ARE UNDESIRABLE. THESE CROSS-SECTIONS ARE ONLY APPLICABLE IF AT-GRADE SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
2. FOR RETAINED-FILLED TRACKWAYS, REINFORCED CONCRETE RETAINING WALLS SHALL BE USED AT SYSTEMS SITES.
3. TYPICAL CROSS-SECTIONAL WIDTH SHOWN SHALL BE PROVIDED FOR A MINIMUM LENGTH EQUAL TO THE LONGITUDINAL DIMENSION OF THE SYSTEMS SITE.
4. FOR STANDALONE RADIO SITE REQUIREMENTS REFER TO COMMUNICATIONS SYSTEMS SITE REQUIREMENTS.
5. FOR ACCESS RESTRICTION FENCING AND BERM DETAILS, REFER TO CIVIL DIRECTIVE DRAWINGS.
6. TRACK SYSTEMS AND DRAINAGE ARE SCHEMATIC AND DO NOT REPRESENT DESIGN. FOR SITE DRAINAGE REQUIREMENTS REFER TO DRAINAGE DIRECTIVE DRAWINGS.
7. FOR ACCESS ROADS, ACCESS GATE AND ACCESS TO TRACKWAY REQUIREMENTS REFER TO SAFETY AND SECURITY DESIGN REQUIREMENTS FOR INFRASTRUCTURE ELEMENTS AND CIVIL DESIGN CRITERIA.
8. A LOW VOLTAGE UNDERTRACK DUCTBANK WITH 2 LOW VOLTAGE MANHOLES TO BE PROVIDED AT SYSTEMS SITE. REFER TO COMMUNICATIONS DESIGN CRITERIA MANUAL AND DIRECTIVE DRAWINGS FOR LOW VOLTAGE UNDERTRACK CONDUIT DUCTBANK AND MANHOLE REQUIREMENTS.
9. SYSTEM SITES AWAY FROM TRACKWAY, SEPARATED BY A THIRD-PARTY RIGHT-OF-WAY ARE UNDESIRABLE. AWAY CROSS-SECTION IS ONLY APPLICABLE IF ADJACENT SOLUTION IS DEMONSTRATED TO VIOLATE SITE SPACING REQUIREMENTS OR OTHER CRITICAL CRITERIA.
10. LOW VOLTAGE UNDERGROUND DUCTBANK AND MANHOLE TO BE PROVIDED UNDERNEATH 3RD PARTY RIGHT-OF-WAY TO CONNECT TO LOW VOLTAGE UNDERTRACK MANHOLES AND DUCTBANK.

REV	DATE	BY	CHK	APP	DESCRIPTION

DESIGNED BY
C. DALOIA
 DRAWN BY
V. LAVERDE
 CHECKED BY
B. MCNALLY
 IN CHARGE
B. BANKS
 DATE
8/29/2014



CALIFORNIA HIGH-SPEED TRAIN PROJECT
COMMUNICATIONS DIRECTIVE
 SYSTEMS SITE
 STANDALONE RADIO SITE
 RETAINED-FILL

CONTRACT NO.	
DRAWING NO.	DD-CO-G053
SCALE	NO SCALE
SHEET NO.	

RFP No.: 13-57 – Addendum No. 5 - 10/09/2014